

LEAD-BASED PAINT INSPECTION REPORT



**124 UNIT APARTMENT BUILDING
LOOMIS COURTS APARTMENTS
1314 and 1342 West 15th STREET, CHICAGO, IL 60608**

PREPARED FOR:



E A S T L A K E

MANAGEMENT GROUP, INC.

**2850 South Michigan Avenue
Chicago, IL 60616**

INSPECTION AND REPORT PREPARED BY:

Synergia[®] Pure & Applied Science INC

Chicago | Salt Lake City | Phoenix

Toll Free: 888.701.7014 Direct: 708.337.3307

www.Synergia.science

James W. Sundberg

Illinois Department of Public Health Licensed Risk Assessment/Inspector License # 1743

Signature

A handwritten signature in black ink that reads "James W. Sundberg". The signature is written in a cursive, flowing style.

December 12, 2020

Report Date

December 8 and 9, 2020

Inspection Dates

TABLE OF CONTENTS

Section 1: Executive Summary.....	1
1.1 Introduction	1
1.2 Summary of Property Evaluation.....	1
1.3 Summary of Lead-Based Paint and Lead-Based Paint Hazards	2
1.4 Propertywide Locations of Building Components with Lead-Based Paint.....	2
1.5 Summary of Regulatory Requirements and Recommendations	3
 Section 2: Lead-Based Paint Inspection (Evaluation) Report	 4
2.1 Overview of the Process	4
2.2 Lead Regulatory Levels	5
2.3 Lead-Based Paint Inspection	6
2.4 Conditions and Limitations—DISCLAIMER.....	6

Section 3: Appendices

Appendix A: Random Sample Documentation

Appendix B: XRF Sampling

B-1: XRF Summary Reports

B-2: XRF Detailed Reports

Appendix C: Lead-Based Paint Risk Assessor/Inspector License

Appendix D: XRF Performance Characteristic Sheets

Appendix E: Property and Apartment Layouts

Appendix F: Photograph Documentation of Components with LBP

124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608

Section 1: Executive Summary

1.1 Introduction

A Lead-Based Paint Inspection (Evaluation) was conducted on December 8 and 9, 2020, at a 124 Unit Apartment Building Complex located at 1314 and 1342 West 15th Street, Chicago, IL 60608. The **lead-based paint inspection** was performed to identify paint that contains lead at levels defined by HUD's Lead Safe Housing Rule (24 CFR part 35, subparts B-R) and the Illinois Department of Public Health (IDPH) Lead Poisoning Prevention Program (IAC 23-2).

The information in this report must be disclosed to new buyers in the future, under the Lead Disclosure Rule (24 CFR part 35, subpart A (HUD's rule) and 40 CFR part 7124, all subparts (EPA's identical rule).

1.2 Summary of Property Evaluation

The evaluation found that lead-based paint surfaces (defined in section 2.2) were present in all resident accessible areas (Exterior Common Areas, Interior Common Areas, and Apartment Units on the date(s) of the evaluation.

Table 1-1 Property Summary

Property Name: Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608		
Lead-Based Paint Present:	Exterior Common Areas:	YES
	Interior Common Areas:	YES
	Interior Apartment Units:	YES
LBP was Identified in all parts of the Property. Components must be maintained intact, only worked on by IDPH Licensed Abatement Contractors, and a summary list of components must be shared with tenants at lease initiation and renew.		

1.3 Summary of Lead-Based Paint

Table 1-3 summarizes lead-based paint as defined by the U.S. Environmental Protection Agency (EPA) and/or the U.S. Department of Housing and Urban Development (HUD) standards within each building group. Buildings have been grouped based on construction date, construction type, and/or written documentation or visual evidence of similar construction. Grouping buildings in this manner will permit

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

the Owner to focus corrective measures on the lead-based paint identified within each building. One group of buildings existed on this property, which consists of the following. Since the Properties One Apartment Buildings were built at the same time, all common areas and apartment units were grouped together. The risk assessor/inspector concluded that there were similar components (look) that had been maintained similarly.

Table 1-2 Property Addresses in Apartment Grouping for This Inspection

Property Name: Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608	
All Exterior and Interior Common Areas, and 124 Apartment Units.	

Table 1-3 Summary of Lead-Based Paint

Property Name: Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608		
Lead-Based Paint Present:	Exterior Common Areas:	YES
	Interior Common Areas:	YES
	Interior Apartment Units:	YES
LBP was Identified in all parts of the Property. Components must be maintained intact, only worked on by IDPH Licensed Abatement Contractors, and a summary list of components must be shared with tenants at lease initiation and renew.		

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

1.4 Propertywide Locations of Building Components with Lead-Based Paint

Table 1-4 below summarizes the building components coated with lead-based paint within each similar group of buildings. Details that identify positive lead-based paint findings within specific areas and on surfaces is provided in section 2.3 and section 4, Appendix C of this report. Buildings have been grouped as summarized in section 1.2.1. Detail on how buildings were grouped is provided in section 2.1.3. The “area” is the common location within a similar group of buildings (e.g., unit/apartment, office, common area, etc.). The “substrate” is the building component material directly beneath the painted surface. The location of lead-based paint identified in table 1-4 is a summary of property wide findings and is representative of all surfaces within each similar group of buildings.

Table 1-4 Components with Lead-Based Paint

Property Name: Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608		
Building/Room	Component	Substrate
Exterior Common Areas	Original Window Casings and Sills	Metal
	Lintels	Metal
	Hallway Fences	Metal
Interior Common Areas (Only Stairways)	Walls	Brick
	Support Columns and Beams	Concrete
	Window Sills	Concrete
Interior Apartments	Window Casings and Sills	Metal

1.5 Summary of Regulatory Requirements and Recommendations

Lead-based paint, as defined by EPA and IDPH, was identified on this Property.

The results of this evaluation indicate that lead in amounts greater than or equal to 1.0 mg/cm² in paint was found on the building components listed in Table 1-4, using the inspection protocol in Chapter 7 of the *HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing (2012 Revision)*. Therefore, this dwelling does not qualify for the exemption in 24 CFR part 35 and 40 CFR part 7124 for target housing being leased that is free of lead-based paint, as defined in the rule.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Because LBP was identified, the Building Owner must **maintain these components intact, only have these components worked on by IDPH Licensed Abatement Contractors, and share a list (Table 1-4) of these components with tenants at lease initiation and renew.** In addition to these components, all painted surfaces may contain levels of lead below 1.0 mg/cm², which could create lead contaminated dust or lead-contaminated soil hazards if paint dust is generated by abrasion, scraping, or sanding. A property found to be free of lead-based paint according to the Federal definition means that in the areas tested no paint was found that meets or exceeds the Federal Regulatory level. However, reasonable care should be taken during any paint disturbance to minimize dust and debris, as some paint may contain lead at lower levels.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Section 2: Lead-Based Paint Inspection (Evaluation) Report

2.1 Overview of the Process

Introduction

A Lead-Based Paint Inspection (Evaluation) was conducted on December 8 and 9, 2020, at a 124 Unit Apartment Building Complex located at 1314 and 1342 West 15th Street, Chicago, IL 60608. James W. Sundberg, who is a certified Risk Assessor/Inspector in the State of Illinois (IDPH), conducted the evaluation (Lead Based Paint Inspection). The purpose of the evaluation was to determine the presence (or absence) and location of lead-based paint.

This evaluation will help the Owner to ensure the health and safety of the residents, especially children, and the workers. As part of the inspection, a visual assessment of the entire property and all structures was performed, and an interview with the property manager was conducted. A lead-based paint inspection using an X-Ray Fluorescence (XRF) lead-in-paint analyzer was performed in each selected dwelling unit, all accessible interior common areas, and all exterior common areas. The results of the evaluation on the selected dwelling units apply to all similar buildings and dwelling units within a similar group of buildings throughout the entire property.

Description of Property

Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608, built around 1961; consist of one hundred twenty-four (124) residential apartment units within two (2) seven (7) floor apartment buildings. The two apartment buildings contains all the apartment units. The buildings have an exterior common area, several interior common area spaces including the office, stairways, and exterior hallways, and apartment units. Apartment units in the Buildings ranged from 1 to 2 bedroom units. Onsite parking, sidewalks, and turf-covered areas constitute the remainder of the site. One hundred twenty-four (124) residential apartment units within the complex and associated exterior and interior common areas were considered for this inspection.

Similar Groups of Buildings

Buildings were grouped into “similar groups of buildings” to ensure consistency during the evaluation of the property. Additionally, this ensured an accurate random selection for inspection. The buildings and exterior sites were grouped according to construction date, construction type, and/or written documentation or visual evidence of similar construction materials criteria. The characteristics that defined the similar group of buildings are as follows:

Two (2) apartment buildings with exterior and interior common areas and all apartment units were built at the same time by the same builder with similar construction techniques. All units were built around 1961 and have a similar look and layout. In addition, the complex has been managed and maintained by the same management company for the recent history. All resident accessible common areas (exterior and interior) were inspected during this inspection.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

The buildings grouped together are provided in Table 2-1.

Table 2-1 Similar Groups of Buildings

Property Name: Loomis Courts Apartments, 1314 and 1342 West 15th Street, Chicago, IL 60608
All Exterior and Interior Common Areas and 124 Apartment Units.

Random Selection Process

Selection of the specific apartment dwelling units and common areas to be tested was accomplished using the HUD-defined selection as specified in the *U.S. Department of Housing and Urban Development; Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing; Chapter 7, Lead-Based Paint Inspection (2012 revision); Section V. Inspections in Multifamily Housing*. The notes used to calculate which apartment and buildings were selected can be found in Appendix A. Detailed units were randomly selected by the Inspector based on the HUD Table 7.3 requirements.

During this evaluation, randomly sampled dwelling units were selected to statistically represent all units on the entire property. Only the randomly selected units were tested for the presence of lead-based. The lead-based paint found (or not found) in the units evaluated are presumed to be present in all similar untested dwelling units and areas within similar groups of buildings of the property unless further testing indicates otherwise. All Building Exterior and Interior Common Areas were inspected during this evaluation.

2.2 Lead Regulatory Levels

The lead regulatory levels provided below are those used when preparing this lead-based paint evaluation or when evaluating data collected. The EPA levels are the same as the State of Illinois.

Table 2-2 Lead Regulatory Levels

	EPA/IDPH Regulatory Level
Lead-Based Paint	1.0 mg/cm² or 0.5% by weight (or 5,000 ppm)

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

2.3 *Lead-Based Paint Inspection*

This lead-based paint inspection is an interior and exterior investigation to identify all lead-based paint on a surface-by-surface basis. A lead-based paint inspection conforming to HUD Guidelines was performed at twenty-six (26) randomly selected dwelling units, all exterior common areas, and all resident accessible interior common areas. One thousand seven hundred seventeen (1,717) tests were taken throughout the entire inspection of this property. An additional forty-eight (48) Calibration Readings were taken before, during, and after each day of inspection.

Lead-based paint WAS identified on certain exterior and interior components (See Table 1-4) in the apartments or exterior and interior common areas on this Property.

All of the XRF test locations exhibited lead-in-paint levels were compared to the level that EPA identifies as lead-based paint, 1.0 mg/cm². These surfaces could create lead contaminated dust or lead contaminated soil hazards if the paint is turned into dust by abrasion, scraping, or sanding. Should these or any lead containing components or surfaces be disturbed in any manner that generates dust, care should be taken to limit its spread.

Testing was performed by James W. Sundberg; an Illinois Department of Public Health (IDPH) licensed Risk Assessor/Inspector, using the Heuresis (Viken Technologies) X-Ray fluorescence analyzer (S/N 2187). The XRF analyzer is designed to measure the lead content of surface coatings on a variety of building surfaces, substrates, and components. The measurement is rapid and nondestructive and, according to the manufacturer, is capable of detecting lead concentrations that occur within numerous layers of various surface coatings.

Please refer to the XRF Testing Results section of Appendix B: XRF Sampling Data for the detailed analytical reports for each distinct area or unit inspected. The reports provide a complete overview of the testing data (Detailed Reports). Component locations throughout the report are documented on the particular wall where the reading was taken. Labeling of walls corresponds to Wall A, B, C, and D. For the exterior and interior common areas and apartment units, Wall A corresponds to the North, Wall B to the East, Wall C to the South, and Wall D to the West.

2.4 *Conditions and Limitations—DISCLAIMER*

Synergia Pure and Applied Science (Synergia) has performed the lead-based paint inspection tasks in a thorough and professional manner consistent with commonly accepted standard industry practices and using state-of-the-art practices and the best available known technology, as of the date of the evaluation. The Preparer cannot guarantee and does not warrant that this evaluation has identified all adverse environmental factors and/or conditions affecting the subject property on the date of the evaluation.

The results reported and conclusions reached by Synergia are solely for the benefit of the Owner and residents. The results and opinions in this report, based solely on the conditions found on the property as of the date of the evaluation, will be valid only as of the date of the evaluation. Synergia assumes no obligation to advise the client of any changes in any real or potential lead-based paint at this residence beyond the date of the property evaluation.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Section 3: Appendices

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix A: Random Sample Documentation

RANDOM.ORG

Random Sequence Generator

Here is your sequence:

58	105	47	44	95	30	56	120	31	68
100	39	113	61	1	60	125	74	54	76
37	103	67	115	22	48	117	3	28	102
114	66	122	46	52	97	14	43	83	87
20	96	98	90	109	73	62	111	57	119
4	29	33	34	77	18	108	45	104	63
86	55	32	99	106	12	65	16	78	88
69	10	24	123	80	79	91	17	8	41
101	107	94	5	19	116	36	42	23	71
15	13	70	81	6	121	92	26	110	84
51	9	2	85	40	82	50	75	35	118
53	93	112	21	38	124	7	72	27	11
89	49	64	25	59					

Timestamp: 2020-12-04 18:12:14 UTC

[Again!](#)

[Go Back](#)

Note: The numbers are generated left to right, i.e., across columns.

RANDOM.ORG

Random Sequence Generator

Here is your sequence:

58	105	47	44	95	30	56	120	31	68
100	39	113	61	1	60	125	74	54	76
37	103	67	115	22	48	117	3	28	102
114	64	122	40	52	97	10	43	83	87
20	96	98	90	109	73	62	1	57	119
4	29	33	34	77	18	108	45	104	63
86	55	32	99	106	12	65	16	78	88
69	10	24	123	80	79	91	17	8	41
101	107	94	5	19	116	36	42	23	71
15	13	70	81	6	121	92	26	110	84
51	9	2	85	40	82	50	75	35	118
53	63	112	21	38	124	7	72	27	11

Property	Unit	Unit	Unit	Market Charge
Charge Code	Type	Sq Ft	Resident Name	Rent Code
rentcs	Amount			
rentcs	20,348.00			
hapes	125,993.00			
tsuboc	5,848.00			
Utility Reimbursement	1,104.00			
Total	153,293.00			

Selected Apartments (26)

01-101	02-104
	02-105
01-304	
01-403	02-204
01-404	02-206
01-501	02-407
01-503	
01-508	02-503
	02-506
01-602	02-508
01-603	
01-609	02-607
	02-609
01-702	02-705
01-704	
01-706	
01-707	01-209

124 units

Table 7.3 - 26 units

01-1342 02-1314

Affordable Rent Roll with Lease Charges

Property: 1314 W 15TH ST (Iom01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Sq Ft	Resident	Name	Market Charge	Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance
1314 W 15TH ST (Iom01)	01-101	2bedlom	771	10048284	SLUGG, TAMMIE	1,310.00	rentics	204.00	0.00	0.00	3/1/2020	3/30/2007	1187.99
						1,106.00	hapcs	1,106.00					
						1,310.00	Total						
01-102		1bedlom	473	10099453	Buck, Alexandria	1,179.00	rentics	6.00	0.00	394.00	8/1/2020	8/16/2013	983.00
						1,173.00	hapcs	1,173.00					
						1,179.00	Total						
01-103		1bedlom	473	10134669	Price, Pierre	1,179.00	rentics	188.00	0.00	50.00	7/1/2020	7/30/2015	1097.98
						991.00	hapcs	991.00					
						1,179.00	Total						
01-104		1bedlom	473	10096068	Taylor, Jolessa	1,179.00	rentics	0.00	22.00	54.00	5/1/2020	10/12/2018	-52.04
						1,201.00	hapcs	1,201.00					
						1,201.00	Total						
01-105		2bedlom	721	10048277	Williams, Latisha	1,310.00	rentics	641.00	0.00	0.00	12/1/2019	11/30/2020	2979.00
						669.00	hapcs	669.00					
						1,310.00	Total						
01-106		1bedlom	473	10048209	Ramsey, Tanisha	1,179.00	rentics	153.00	0.00	0.00	4/1/2020	6/19/2015	1181.00
						1,026.00	hapcs	1,026.00					
						1,179.00	Total						
01-107		1bedlom	473	10150687	Cephas, Lenard	1,179.00	rentics	176.00	0.00	210.00	6/1/2020	5/31/2021	909.97
						1,003.00	hapcs	1,003.00					
						1,179.00	Total						
01-108		1bedlom	721	10075886	Williams, Jerome	1,179.00	rentics	213.00	0.00	219.00	12/1/2019	11/30/2020	1369.00
						966.00	hapcs	966.00					
						1,179.00	Total						
01-109		2bedlom	721	10048196	Lott, Linda	1,310.00	rentics	174.00	0.00	0.00	4/1/2020	3/31/2021	1648.98
						1,136.00	hapcs	1,136.00					
						1,310.00	Total						
01-201		2bedlom	721	10230385	SIGLE, BREONA	1,310.00	tsuboc	1,021.00	0.00	276.00	3/25/2020	3/24/2021	13522.55
						269.00	rentics	269.00					
						1,041.00	hapcs	1,041.00					
						2,331.00	Total						
01-202		1bedlom	473	10202127	MERRITT, ROBERT	1,179.00	rentics	0.00	22.00	0.00	5/1/2020	5/22/2018	1761.00
						1,201.00	hapcs	1,201.00					
						1,201.00	Total						
01-203		1bedlom	473	10048287	Johnson, Albert	1,179.00	rentics	184.00	0.00	0.00	3/1/2020	2/28/2021	1172.99
						995.00	hapcs	995.00					
						1,179.00	Total						
01-204		1bedlom	473	10135092	McDonald, Leticia	1,179.00	rentics	0.00	22.00	50.00	8/1/2020	7/31/2021	6723.98
						1,201.00	hapcs	1,201.00					
						1,201.00	Total						
01-205		2bedlom	721	c012052	BLAKLEY, TRASANDRA	1,310.00	rentics	0.00	32.00	50.00	5/15/2020	5/14/2021	1344.00
						1,342.00	hapcs	1,342.00					
						1,342.00	Total						
01-206		1bedlom	473	10048312	Thomas, Mose	1,179.00	rentics	225.00	0.00	0.00	3/1/2020	2/28/2021	1317.00
						954.00	hapcs	954.00					
						1,179.00	Total						
01-207		1bedlom	473	10072766	Watkins, Thaddeus	1,159.00	rentics	177.00	0.00	192.00	10/1/2020	9/30/2021	1116.98
						982.00	hapcs	982.00					
						1,159.00	Total						

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (l0m01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Unit Sq Ft	Resident Name	Market Charge Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance
	01-208	1bedlom	473	10054103 Parker, Kenneth	1,179.00 rents happcs	0.00 1,201.00 1,201.00	22.00	50.00 8/1/2020	7/31/2021	8/13/2010	849.84
	01-209	2bedlom	721	VACANT	Total 1,310.00	0.00	0.00	0.00			0.00
	01-301	2bedlom	721	10048214 Williams, Donyetta	Total 1,310.00 rents happcs	283.00 1,027.00 1,310.00	0.00	0.00 5/1/2020	4/30/2021	6/6/2016	2934.98
	01-302	1bedlom	473	10143193 Lane, Darius	Total 1,179.00 rents happcs	886.00 293.00 1,179.00	0.00	770.00 2/1/2020	1/31/2021	2/11/2016	-2683.15
	01-303	1bedlom	473	10048210 Watson, Jr., Robert	Total 1,179.00 rents happcs	0.00 1,201.00 1,201.00	22.00	0.00 7/1/2020	6/30/2021	4/30/2009	3088.18
	01-304	1bedlom	473	10132244 Kent, Maria	Total 1,179.00 rents happcs	1,201.00 207.00 972.00 1,179.00	0.00	99.00 6/1/2020	5/31/2021	6/4/2015	2120.97
	01-305	2bedlom	721	10048292 Kelly, Stacy	Total 1,310.00 rents happcs	0.00 1,342.00 1,342.00	32.00	0.00 3/1/2020	2/28/2021	3/30/2007	258.94
	01-306	1bedlom	473	10193875 SMITH, MARGARET	Total 1,179.00 tcsuoc rents happcs	982.00 178.00 1,001.00 2,161.00	0.00	0.00 3/24/2020	4/30/2020	3/24/2020	5479.42
	01-307	1bedlom	473	10130505 McDonald, Diane	Total 1,179.00 rents happcs	0.00 1,201.00 1,201.00	22.00	50.00 5/1/2020	4/30/2021	5/1/2015	1199.98
	01-308	1bedlom	473	10048195 Mathews, Elaine	Total 1,179.00 rents happcs	1,201.00 642.00 537.00 1,179.00	0.00	0.00 4/1/2020	3/31/2021	11/8/2018	4554.96
	01-309	2bedlom	721	10048296 Clark, Surnet	Total 1,310.00 rents happcs	162.00 1,148.00 1,310.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1171.88
	01-401	2bedlom	721	10048298 Stevenson, Corey	Total 1,310.00 rents happcs	0.00 1,342.00 1,342.00	32.00	0.00 3/1/2020	2/28/2021	4/4/2007	-1145.00
	01-402	1bedlom	473	10048297 Ivey, George	Total 1,179.00 rents happcs	1,342.00 0.00 1,201.00 1,201.00	22.00	0.00 3/1/2020	2/28/2021	3/30/2007	585.47
	01-403	1bedlom	473	10144996 Vortes, Latrice	Total 1,179.00 rents happcs	1,201.00 0.00 1,201.00	22.00	289.00 3/1/2020	2/28/2021	3/28/2016	1404.95
	01-404	1bedlom	473	10088737 Williams, Leonard	Total 1,179.00 rents happcs	1,201.00 184.00 995.00 1,179.00	0.00	205.00 11/1/2020	10/31/2021	11/5/2012	1179.00
	01-405	2bedlom	721	10048299 Parker, Gwendolyn	Total 1,310.00 rents happcs	70.00 1,240.00 1,310.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1441.97
	01-406	1bedlom	473	10170154 Mitchell, Michael	Total 1,179.00 rents	174.00	0.00	211.00 2/1/2020	1/31/2021	2/8/2017	1503.00

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (Iom01)

As of Date: 12/04/2020
 Balance Month: 12/2020

Property	Unit	Unit Type	Unit Sq Ft	Resident Name	Market Charge Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance
	01-407	1bedlom	473 0048300	Sidney, Arnold	hapos Total	1,005.00 1,179.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1141.00
	01-408	1bedlom	473 0001099	WORTHY, JOVANITA	hapos Total	147.00 1,032.00 1,179.00	0.00	5.00 3/24/2020	3/23/2021	3/24/2020	2414.42
	01-409	2bedlom	721 0048301	McDonald, Melvin	hapos Total	178.00 1,001.00 2,161.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1428.00
	01-501	2bedlom	721 0048208	Belk, Bobby	hapos Total	209.00 1,310.00 1,519.00	0.00	0.00 4/1/2020	3/31/2021	8/9/2017	2375.00
	01-502	1bedlom	473 0060677	Lewis, Kenny	hapos Total	162.00 1,148.00 1,310.00	22.00	53.00 1/1/2020	12/31/2020	1/20/2011	1344.98
	01-503	1bedlom	473 00115481	Sigler, Kenneth	hapos Total	0.00 1,201.00 1,201.00	0.00	392.00 9/1/2020	8/31/2021	9/4/2014	1286.00
	01-504	1bedlom	473 0048303	Gladney, Deon	hapos Total	810.00 1,179.00 1,989.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1649.00
	01-505	2bedlom	721 0075300	Williams, Michelle	hapos Total	503.00 676.00 1,179.00	0.00	83.00 12/2/2019	12/1/2020	5/23/2016	1269.94
	01-506	1bedlom	473 00085499	Cole, Latanya	hapos Total	112.00 1,198.00 1,310.00	0.00	260.00 8/1/2020	7/31/2021	8/15/2012	6270.76
	01-507	1bedlom	473 00015688	WALKER, ESSENCE	hapos Total	13.00 1,166.00 1,179.00	22.00	50.00 5/15/2020	5/14/2021	5/15/2020	1202.00
	01-508	1bedlom	473 0048203	Ellis, Andre	hapos Total	0.00 1,201.00 1,201.00	0.00	0.00 4/1/2020	3/31/2021	4/5/2007	1489.00
	01-509	2bedlom	721 0048316	Reed, Kenya	hapos Total	862.00 1,179.00 1,981.00	0.00	0.00 4/1/2020	3/31/2021	4/27/2007	6211.00
	01-601	2bedlom	721 00099661	Farrior, Latreace	hapos Total	154.00 1,156.00 1,310.00	0.00	467.00 8/1/2020	7/31/2021	10/21/2015	1291.00
	01-602	1bedlom	473 0048307	Hare, Anthony	hapos Total	79.00 1,231.00 1,310.00	0.00	0.00 3/1/2020	2/28/2021	3/30/2007	1155.99
	01-603	1bedlom	473 00145013	Goodwin, Lartrell	hapos Total	198.00 981.00 1,179.00	22.00	50.00 3/1/2020	2/28/2021	3/28/2016	1208.99
	01-604	1bedlom	473 00016172	GIVENS, ROMINESKA	hapos Total	0.00 1,201.00 1,201.00	0.00	48.00 6/16/2020	6/15/2021	6/16/2020	1179.00

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (l0m01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Unit Sq Ft	Resident Name	Market Charge Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance	
	01-605	2bedlom	721 VACANT	VACANT	hapcs Total	995.00						
					1,310.00	1,179.00	0.00	0.00			0.00	
	01-606	1bedlom	473 t0081224	Wales, Jr., Ukler	hapcs Total	0.00						
					1,179.00	0.00	22.00	195.00	5/1/2020	4/30/2021	5/1/2012	1197.89
					1,201.00	1,201.00						
	01-607	1bedlom	473 t0174531	Walton, Antwon	hapcs Total	0.00						
					1,179.00	0.00	22.00	0.00	5/1/2020	4/30/2021	5/1/2018	1811.00
					1,201.00	1,201.00						
	01-608	1bedlom	473 t0079312	Robertson, Vincent	hapcs Total	0.00						
					1,179.00	0.00	22.00	50.00	3/1/2020	2/28/2021	3/15/2012	1202.00
					1,201.00	1,201.00						
	01-609	2bedlom	721 t0138899	Ousley, Chanel	hapcs Total	0.00						
					1,310.00	0.00	32.00	50.00	3/1/2020	2/28/2021	9/25/2015	2650.99
					1,342.00	1,342.00						
	01-701	2bedlom	721 t0048311	Johnson, Silnova	hapcs Total	0.00						
					1,310.00	189.00	0.00	0.00	3/1/2020	2/28/2021	4/1/2009	1896.99
					1,121.00	1,121.00						
	01-702	1bedlom	473 t0211642	HILL, DEVIN	hapcs Total	0.00						
					1,179.00	0.00	22.00	50.00	10/1/2020	9/30/2021	10/26/2018	1243.00
					1,201.00	1,201.00						
	01-703	1bedlom	473 t0216414	LEE, MIRACLE	hapcs Total	0.00						
					1,179.00	858.00	0.00	50.00	1/1/2020	12/31/2020	1/23/2019	10628.00
					321.00	1,179.00						
	01-704	1bedlom	473 t0148570	Dickens, Kent	hapcs Total	0.00						
					1,179.00	0.00	22.00	56.00	5/1/2020	4/30/2021	5/25/2016	1219.99
					1,201.00	1,201.00						
	01-705	2bedlom	721 t0142861	Stevenson, Devonna	hapcs Total	0.00						
					1,310.00	1,009.00	0.00	83.00	2/1/2020	1/31/2021	5/30/2018	14448.98
					301.00	1,310.00						
	01-706	1bedlom	473 t0060682	Brim, Billy	hapcs Total	0.00						
					1,179.00	184.00	0.00	160.00	1/1/2020	12/31/2020	1/24/2011	1423.00
					995.00	1,179.00						
	01-707	1bedlom	473 g0008623	GRANT, DIANA	hapcs Total	0.00						
					1,179.00	273.00	0.00	320.00	5/1/2020	4/30/2021	5/1/2020	1172.00
					906.00	1,179.00						
	01-708	1bedlom	473 t0194039	HILL, COREY	hapcs Total	0.00						
					1,179.00	0.00	22.00	0.00	1/1/2020	12/31/2020	1/16/2018	1469.00
					1,201.00	1,201.00						
	01-709	2bedlom	721 t0105414	Rooks, Bath-Sheba	hapcs Total	0.00						
					1,310.00	0.00	32.00	304.00	1/1/2020	12/31/2020	1/17/2014	1021.97
					1,342.00	1,342.00						
	02-101	2bedlom	721 z0046073	CABASQUIN, JESSICA	hapcs Total	0.00						
					1,310.00	1,186.00	0.00	0.00	3/23/2020	3/22/2021	3/23/2020	6073.32
					104.00	1,206.00						
	02-102	1bedlom	473 t0217061	Johnson, Clara	hapcs Total	0.00						
					1,179.00	2,496.00	22.00	390.00	2/1/2020	1/31/2021	2/25/2019	1116.00
					1,201.00	1,201.00						

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (10M01)

As of Date: 12/04/2020
 Balance Month: 12/2020

Property	Unit	Unit Type	Sq Ft	Resident	Name	Unit	Market Charge	Rent Code	Amount	U.R.	Resident Lease	Lease	Move In	Balance
									Amount	Amount	Deposit From	Expiration	Date	
02-103	66	1bedlom	473	10048229	Johnson, Quincy		Total		1,201.00	0.00	0.00	11/30/2020	12/31/2007	827.88
							rentics		351.00					
							hapes		828.00					
02-104	67	1bedlom	473	10048230	HARPER Apt 104, BETTY		Total		1,179.00	0.00	0.00	11/30/2020	12/31/2007	1286.44
							rentics		689.00					
							hapes		490.00					
02-105	68	2bedlom	721	10048280	MCINTEE, ROBIN		Total		1,179.00	32.00	0.00	12/31/2020	12/28/2018	3500.98
							rentics		0.00					
							hapes		1,342.00					
02-108	69	1bedlom	473	VACANT	VACANT		Total		1,179.00	0.00	0.00			0.00
							rentics		0.00					
02-109	70	2bedlom	721	VACANT	VACANT		Total		1,310.00	0.00	0.00			0.00
							rentics		0.00					
02-201	71	2bedlom	721	20046848	DOBBS, SHANAE		Total		1,288.00	0.00	0.00	11/30/2021	12/1/2020	1501.00
							rentics		154.00					
							hapes		1,134.00					
02-202	72	1bedlom	473	10048225	LEONARD, ANITA LILLIAN		Total		1,288.00	0.00	0.00	11/30/2020	12/31/2007	1115.98
							rentics		180.00					
							hapes		999.00					
02-203	73	1bedlom	473	20034918	HANNAH-WHITEFIELD, YOLANDA		Total		1,179.00	22.00	50.00	6/30/2021	5/8/2020	1202.00
							rentics		0.00					
							hapes		1,201.00					
02-204	74	1bedlom	473	10092005	Walton, Antoinette		Total		1,201.00	0.00	426.00	1/31/2021	2/1/2013	3816.00
							rentics		178.00					
							hapes		1,001.00					
02-205	75	2bedlom	721	10048226	Parker, Glynnese		Total		1,179.00	0.00	0.00	11/30/2020	4/6/2015	1361.00
							rentics		49.00					
							hapes		1,261.00					
02-206	76	1bedlom	473	10130479	Williams, Mary		Total		1,310.00	0.00	166.00	4/30/2021	5/7/2015	1177.95
							rentics		213.00					
							hapes		966.00					
02-207	77	1bedlom	473	20021415	PICKENS, TERRI		Total		1,179.00	0.00	0.00	2/28/2021	3/23/2020	5553.10
							rentics		982.00					
							hapes		178.00					
02-208	78	1bedlom	473	10080330	Winfrey, Lafrenchie		Total		2,161.00	0.00	50.00	3/31/2021	4/16/2012	7778.99
							rentics		681.00					
							hapes		498.00					
02-209	79	2bedlom	721	10113187	Williams, Shaneka		Total		1,179.00	32.00	50.00	6/30/2021	7/26/2014	3292.97
							rentics		0.00					
							hapes		1,342.00					
02-301	80	2bedlom	721	10217537	Sanford, Dantrell		Total		1,342.00	32.00	50.00	2/28/2021	3/15/2019	1344.00
							rentics		0.00					
							hapes		1,342.00					
02-302	81	1bedlom	473	20059109	COLON, BELINDA		Total		1,179.00	0.00	322.00	3/31/2021	4/21/2020	3117.00
							rentics		236.00					
							hapes		943.00					
02-303	82	1bedlom	473	10083097	Garcia, Nicholas		Total		1,179.00	0.00	199.00	12/31/2020	6/22/2012	5892.98
							rentics		174.00					

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (10M01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Unit Sq Ft	Resident Name	Market Charge Rent Code	Amount	U.R. Amount	Resident Deposit From	Lease Expiration	Move In Date	Balance	
					hapcs	1,005.00						
					Total	1,179.00						
02-304	83	1bedlom	473	t0141685 Lane, Lonnie	1,179.00 rents	0.00	22.00	300.00	12/1/2019	11/30/2020	12/31/2015	3556.94
					hapcs	1,201.00						
					Total	1,201.00						
02-305	84	2bedlom	721	t0216615 Sanford, Dantrice	1,310.00 rents	0.00	32.00	50.00	2/1/2020	1/31/2021	2/4/2019	1294.00
					hapcs	1,342.00						
					Total	1,342.00						
02-306	85	1bedlom	473	t0197567 Sanford, Lavonna	1,179.00 rents	0.00	0.00	0.00	3/1/2020	2/28/2021	3/23/2018	4966.00
					hapcs	178.00						
					Total	1,179.00						
02-307	86	1bedlom	473	t0082030 Johnson, Phillip	1,179.00 rents	227.00	0.00	662.00	5/1/2020	4/30/2021	5/25/2012	1025.00
					hapcs	952.00						
					Total	1,179.00						
02-308	87	1bedlom	473	t0057050 Nelson, Eric	1,179.00 rents	117.00	0.00	50.00	10/1/2020	9/30/2021	10/15/2010	2446.95
					hapcs	1,062.00						
					Total	1,179.00						
02-309	88	2bedlom	721	t0048243 RILEY, SHARESE	1,310.00 rents	233.00	0.00	0.00	12/1/2019	12/1/2020	5/16/2017	2257.99
					hapcs	1,077.00						
					Total	1,310.00						
02-401	89	2bedlom	0	t0217083 Williams, Cherelle	1,310.00 rents	0.00	32.00	95.00	4/1/2020	3/31/2021	4/2/2019	1344.00
					hapcs	1,342.00						
					Total	1,342.00						
02-402	90	1bedlom	473	t0106019 Blake, Deanna	1,179.00 rents	431.00	0.00	266.00	1/1/2020	12/31/2020	1/31/2014	2215.94
					hapcs	748.00						
					Total	1,179.00						
02-403	91	1bedlom	473	t0092011 Funchess, Marques	1,179.00 rents	227.00	0.00	257.00	2/1/2020	1/31/2021	2/1/2013	1653.05
					hapcs	952.00						
					Total	1,179.00						
02-404	92	1bedlom	473	g0000079 SPEARS JR, STANLEY	1,179.00 rents	0.00	2.00	50.00	8/14/2020	8/13/2021	8/14/2020	1182.00
					hapcs	1,181.00						
					Total	1,181.00						
02-405	93	2bedlom	721	t0048253 Davis, Victoria	1,310.00 rents	0.00	32.00	0.00	12/1/2019	11/30/2020	12/31/2007	-475.04
					hapcs	1,342.00						
					Total	1,342.00						
02-406	94	1bedlom	473	t0052117 Whitfield, Iesha	1,179.00 rents	0.00	22.00	0.00	12/1/2019	11/30/2020	12/8/2009	-3813.03
					hapcs	1,201.00						
					Total	1,201.00						
02-407	95	1bedlom	473	t0159191 Miller Apt: 407, Michael	1,179.00 rents	181.00	0.00	217.00	1/1/2020	12/31/2020	1/27/2017	1108.98
					hapcs	998.00						
					Total	1,179.00						
02-408	96	1bedlom	473	t0144992 Lane, Lonesha	1,179.00 rents	0.00	22.00	378.00	3/1/2020	2/28/2021	3/28/2016	4175.00
					hapcs	1,201.00						
					Total	1,201.00						
02-409	97	2bedlom	721	VACANT	1,310.00	0.00	0.00	0.00				0.00
					Total	0.00						
02-501	98	2bedlom	0	t0219999 Palmer, Kira	1,310.00 rents	79.00	0.00	132.00	5/1/2020	4/30/2021	5/22/2019	1704.00
					hapcs	1,231.00						
					Total	1,310.00						

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (10m01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Unit Sq Ft	Resident Name	Market Charge Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance
02-502	99	1bedlom	473	10070638	Yarbrough, Marlice	1,179.00 rents hapes	0.00	192.00	9/1/2020	9/1/2011	1275.62
02-503	100	1bedlom	473	g0017610	MARTINEZ, JUAN	1,179.00 rents Total	0.00	50.00	12/31/2019	12/31/2019	1283.00
02-504	101	1bedlom	473	10137205	Faulkner, Kenneth	1,179.00 rents Total	0.00	50.00	9/1/2020	12/15/2017	1155.99
02-505	102	2bedlom	0	10048235	Mathis, Alexis	1,310.00 rents Total	0.00	0.00	12/1/2019	6/1/2019	1492.97
02-506	103	1bedlom	473	g0001196	LANE, ARTICE	1,179.00 rents Total	0.00	108.00	5/13/2020	5/13/2020	1370.00
02-507	104	1bedlom	0	10196041	Freeman, Christine	1,179.00 rents Total	8.00	50.00	2/1/2020	1/31/2021	3920.00
02-508	105	1bedlom	0	10173784	Willis, Jonnequa	1,179.00 rents Total	22.00	118.00	3/1/2020	2/28/2021	1616.99
02-509	106	2bedlom	0	10134476	King, Candace	1,310.00 rents Total	32.00	50.00	8/1/2020	7/31/2021	431.00
02-601	107	2bedlom	721	20044028	MCOLLE, CHARLOTTE	1,310.00 tsuubcc rents Total	0.00	0.00	3/24/2020	3/24/2020	8756.35
02-602	8	1bedlom	0	10136809	Faulkner, Jerome	1,179.00 rents Total	22.00	50.00	9/1/2020	8/31/2021	1203.98
02-603	9	1bedlom	0	g0007430	BONNER, DEMETRIA	1,179.00 rents Total	18.00	50.00	6/8/2020	6/8/2020	1198.00
02-604	110	1bedlom	0	10048264	Deramus, Shella	1,179.00 rents Total	0.00	0.00	12/1/2019	11/30/2020	1342.92
02-605	111	2bedlom	0	10219428	Wright, Antoinette	1,310.00 rents Total	0.00	542.00	4/1/2020	3/31/2021	2042.00
02-606	112	1bedlom	0	10150851	Walls, Vaquita	1,179.00 rents Total	22.00	50.00	6/1/2020	5/31/2021	1215.99
02-607	113	1bedlom	0	10048267	Smith, Teneltha	1,179.00 rents Total	22.00	0.00	12/1/2019	11/30/2020	1579.47
02-608	114	1bedlom	0	20044985	KANE, LEAH	1,179.00 rents Total	0.00	264.00	5/2/2020	5/1/2021	1692.00

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (10M01)

As of Date: 12/04/2020

Balance Month: 12/2020

Property	Unit	Unit Type	Sq Ft	Resident	Name	Market Charge	Rent Code	Amount	U.R. Amount	Resident Lease Deposit From	Lease Expiration	Move In Date	Balance
	02-609	2bedlom	115	0 10068649	Simmons, Denita	1,310.00	rents	295.00	0.00	271.00	8/1/2020	7/31/2021	3841.84
							hapes	1,015.00					
						Total		1,310.00					
	02-701	2bedlom	116	0 10219687	Johnson, Charlene	1,310.00	rents	436.00	0.00	489.00	5/1/2020	5/22/2019	1310.00
							hapes	874.00					
						Total		1,310.00					
	02-702	1bedlom	117	473 10159195	Perry, Samantha	1,179.00	rents	59.00	0.00	50.00	1/18/2019	1/18/2017	2605.94
							hapes	1,120.00					
						Total		1,179.00					
	02-703	1bedlom	118	0 10216539	Davis, Josiah	1,179.00	rents	0.00	22.00	50.00	1/1/2020	12/31/2020	1202.00
							hapes	1,201.00					
						Total		1,201.00					
	02-704	1bedlom	119	0 10048273	Holt, Desiree	1,179.00	rents	231.00	0.00	0.00	12/1/2019	11/30/2020	2981.68
							hapes	948.00					
						Total		1,179.00					
	02-705	2bedlom	120	0 10133386	Howard, Unique	1,310.00	rents	0.00	32.00	205.00	7/1/2020	6/30/2021	6990.45
							hapes	1,342.00					
						Total		1,342.00					
	02-706	1bedlom	121	0 10143337	Pierce, Roland	1,179.00	rents	0.00	22.00	37.00	2/1/2020	1/31/2021	1202.00
							hapes	1,201.00					
						Total		1,201.00					
	02-707	1bedlom	122	0 10150754	Pickens, Sierra	1,179.00	rents	0.00	22.00	297.00	6/1/2020	5/31/2021	-390.05
							hapes	1,201.00					
						Total		1,201.00					
	02-708	1bedlom	123	0 10158868	Long, Sherrick	1,179.00	rents	0.00	22.00	50.00	1/1/2020	12/31/2020	940.00
							hapes	1,201.00					
						Total		1,201.00					
	02-709	2bedlom	124	0 10229459	MOLLISON, SHAWNTERIA	1,310.00	rents	575.00	0.00	59.00	6/9/2020	6/8/2021	1887.00
							hapes	735.00					
						Total		1,310.00					
	01-209	2bedlom	125	721 c0011828	CALDERON, MELIA	1,310.00	rents	0.00	0.00	0.00	4/1/2020	3/31/2021	0.00
							hapes	0.00					
						Total		0.00					
(10M01) Total						151,656.00		152,189.00	1,104.00	13,137.00			264,394.17

Summary Groups	Square Footage	Market Rent	Lease Charges	Security Deposit	Other Deposits	# Of Units	% Occupancy	% SQFT	Balance
Current/Notice Residents			152,189.00	13,137.00	7,154.00				264,394.17
Future Residents/Applicants			0.00	0.00	0.00				0.00
Occupied Units	53,321.00	145,237.00				119	95.97	94.08	
Vacant Units	3,357.00	6,419.00				5	4.03	5.92	
Totals	56,678.00	151,656.00	152,189.00	13,137.00	7,154.00	124	100.00	100.00	264,394.17

Summary of Charges by Charge Code (Current/Notice residents only)

Affordable Rent Roll with Lease Charges
Property: 1314 W 15TH ST (lcm01)

As of Date: 12/04/2020
Balance Month: 12/2020

Property	Unit	Unit Type	Sq Ft	Resident	Name	Market Charge	U.R.	Resident Lease	Lease	Move In	Balance
Charge Code	Unit	Type	Amount			Rent Code	Amount	Deposit From	Expiration	Date	
rentics			20,348.00								
hapes			125,993.00								
tcsubcc			5,848.00								
Utility Reimbursement			1,104.00								
Total			153,293.00								

Selected Apartments (26)

01-101	02-104
01-304	02-105
01-403	02-204
01-404	02-206
01-501	02-407
01-503	02-503
01-508	02-506
	02-508
01-602	02-607
01-603	02-609
01-609	
	02-705
01-702	
01-704	
01-706	
01-707	01-209

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix B: XRF Sampling

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

B-1: XRF Summary Report

Summary Lead Paint Inspection Report

Synergya PAS, Inc.

INSPECTION DATE:	12/8/2020 - 12/9/2020
INSTRUMENT TYPE:	Heuresis Corp. Pb200i XRF Lead Paint Analyzer 2187
ACTION LEVEL:	1.0 mg/cm ²
STATEMENT:	Lead Paint Inspection

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1		Off	Calibration				Wood			Intact	-0.3 mg/cm ²	Action Level
2		Off	Calibration				Wood			Intact	0.0 mg/cm ²	Action Level
3		Off	Calibration				Wood			Intact	0.0 mg/cm ²	Action Level
4		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
5		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
6		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
7	Positive	Off	Exterior	1314	Lintel		Metal	A	Right	Intact	2.1 mg/cm ²	Action Level
8	Positive	Off	Exterior	1314	Lintel		Metal	A	Center	Intact	2.1 mg/cm ²	Action Level
9	Positive	Off	Exterior	1314	Lintel		Metal	A	Left	Intact	2.1 mg/cm ²	Action Level
10	Positive	Off	Exterior	1314	Lintel		Metal	C	Left	Intact	2.3 mg/cm ²	Action Level
11	Positive	Off	Exterior	1314	Lintel		Metal	C	Center	Intact	2.2 mg/cm ²	Action Level
12	Positive	Off	Exterior	1314	Lintel		Metal	C	Right	Intact	1.7 mg/cm ²	Action Level
101	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	A	UL	Deteriorated	1.0 mg/cm ²	Action Level
102	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	B	UC	Intact	1.3 mg/cm ²	Action Level
103	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	C	UC	Intact	1.4 mg/cm ²	Action Level
104	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	D	UC	Intact	1.3 mg/cm ²	Action Level
105	Positive	Off	Common	1314 NE Stair 6	Support	Beam	Concrete	A	Left	Intact	1.7 mg/cm ²	Action Level
106	Positive	Off	Common	1314 NE Stair 6	Support	Column	Concrete	A	Left	Intact	1.8 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
108	Positive	Off	Common	1314 NE Stair 6	Window	Sill	Concrete	C	Left	Intact	1.8 mg/cm ²	Action Level
119	Positive	Off	Common	1314 SW Stair 6	Window	Sill	Concrete	D	Left	Intact	1.3 mg/cm ²	Action Level
120	Positive	Off	Common	1314 SW Stair 6	Support	Beam	Concrete	C	Left	Intact	1.1 mg/cm ²	Action Level
121	Positive	Off	Common	1314 SW Stair 6	Support	Column	Concrete	C	Left	Intact	1.4 mg/cm ²	Action Level
123	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	A	UL	Intact	1.7 mg/cm ²	Action Level
124	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	B	UC	Intact	1.6 mg/cm ²	Action Level
125	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	C	UR	Intact	1.7 mg/cm ²	Action Level
126	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	D	UC	Intact	1.7 mg/cm ²	Action Level
127	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	D	LC	Intact	2.3 mg/cm ²	Action Level
128	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	C	LL	Intact	1.3 mg/cm ²	Action Level
129	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	B	LR	Intact	1.8 mg/cm ²	Action Level
130	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	A	LC	Intact	1.9 mg/cm ²	Action Level
132	Positive	Off	Common	1314 SW Stair 1	Support	Beam	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
133	Positive	Off	Common	1314 SW Stair 1	Support	Column	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
134	Positive	Off	Common	1314 SW Stair 1	Window	Sill	Concrete	D	Left	Intact	2.3 mg/cm ²	Action Level
147	Positive	Off	Common	1314 NE Stair 1	Window	Sill	Concrete	C	Left	Intact	1.2 mg/cm ²	Action Level
148	Positive	Off	Common	1314 NE Stair 1	Support	Column	Concrete	A	Right	Intact	1.3 mg/cm ²	Action Level
149	Positive	Off	Common	1314 NE Stair 1	Support	Beam	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
150	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	A	LC	Intact	1.9 mg/cm ²	Action Level
151	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	B	LL	Intact	1.8 mg/cm ²	Action Level
152	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	C	LC	Intact	1.8 mg/cm ²	Action Level
153	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	D	LL	Intact	1.7 mg/cm ²	Action Level
154	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Left	Intact	1.8 mg/cm ²	Action Level
155	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Center	Intact	1.4 mg/cm ²	Action Level
156	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Right	Intact	1.5 mg/cm ²	Action Level
157	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Right	Intact	1.5 mg/cm ²	Action Level
158	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Center	Intact	1.5 mg/cm ²	Action Level
159	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Left	Intact	1.5 mg/cm ²	Action Level
164		Off	Calibration								0.0 mg/cm ²	Action Level
165		Off	Calibration								-0.2 mg/cm ²	Action Level
166		Off	Calibration								-0.1 mg/cm ²	Action Level
167		Off	Calibration								1.1 mg/cm ²	Action Level
168		Off	Calibration								1.0 mg/cm ²	Action Level
169		Off	Calibration								1.1 mg/cm ²	Action Level
183	Positive	Off	Apartment	01-707 LR	Window	Casing	Metal	C	Right	Intact	1.6 mg/cm ²	Action Level
455		Off	Calibration								1.1 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
456		Off	Calibration								1.1 mg/cm ²	Action Level
457		Off	Calibration								1.1 mg/cm ²	Action Level
458		Off	Calibration								0.0 mg/cm ²	Action Level
459		Off	Calibration								-0.1 mg/cm ²	Action Level
460		Off	Calibration								0.0 mg/cm ²	Action Level
523	Positive	Off	Apartment	01-704 LR	Window	Casing	Metal	D	Right	Intact	1.7 mg/cm ²	Action Level
592	Positive	Off	Apartment	01-603 LR	Window	Casing	Metal	D	Left	Intact	1.1 mg/cm ²	Action Level
616	Positive	Off	Apartment	01-501 Kitchen	Window	Casing	Metal	B	Left	Intact	1.4 mg/cm ²	Action Level
684	Positive	Off	Apartment	01-503 Bathroom	Window	Casing	Metal	B	Right	Intact	1.0 mg/cm ²	Action Level
728	Positive	Off	Apartment	01-508 Kitchen	Window	Casing	Metal	A	Left	Intact	1.1 mg/cm ²	Action Level
729	Positive	Off	Apartment	01-508 Bathroom	Window	Casing	Metal	A	Center	Intact	1.1 mg/cm ²	Action Level
813	Positive	Off	Apartment	01-403 Kitchen	Window	Casing	Metal	B	Left	Intact	1.2 mg/cm ²	Action Level
840	Positive	Off	Apartment	01-403 Bedroom	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level
911	Positive	Off	Apartment	01-101 Bathroom	Window	Casing	Metal	B	Center	Intact	1.1 mg/cm ²	Action Level
938	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.2 mg/cm ²	Action Level
939	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.2 mg/cm ²	Action Level
940	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.1 mg/cm ²	Action Level
941	Positive	Off	Apartment	01-304 Bedroom	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
957	Positive	Off	Apartment	01-304 Bathroom	Window	Casing	Metal	B	Center	Intact	1.0 mg/cm ²	Action Level
963		Off	Calibration								0.0 mg/cm ²	Action Level
964		Off	Calibration								0.0 mg/cm ²	Action Level
965		Off	Calibration								0.0 mg/cm ²	Action Level
966		Off	Calibration								1.0 mg/cm ²	Action Level
967		Off	Calibration								1.0 mg/cm ²	Action Level
968		Off	Calibration								0.9 mg/cm ²	Action Level
969		Off	Calibration								1.1 mg/cm ²	Action Level
970		Off	Calibration								1.0 mg/cm ²	Action Level
971		Off	Calibration								1.1 mg/cm ²	Action Level
972		Off	Calibration								0.0 mg/cm ²	Action Level
973		Off	Calibration								0.0 mg/cm ²	Action Level
974		Off	Calibration								0.0 mg/cm ²	Action Level
991	Positive	Off	Exterior	1342	Lintel		Metal	A	Center	Intact	5.5 mg/cm ²	Action Level
992	Positive	Off	Exterior	1342	Lintel		Metal	B	Center	Intact	5.6 mg/cm ²	Action Level
993	Positive	Off	Exterior	1342	Lintel		Metal	C	Center	Intact	5.7 mg/cm ²	Action Level
994	Positive	Off	Exterior	1342	Lintel		Metal	D	Center	Intact	6.0 mg/cm ²	Action Level
995	Positive	Off	Exterior	1342	Hall Fence		Metal	D	Center	Intact	5.9 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
996	Positive	Off	Exterior	1342	Hall Fence		Metal	C	Center	Intact	5.9 mg/cm ²	Action Level
997	Positive	Off	Exterior	1342	Hall Fence		Metal	B	Center	Intact	5.8 mg/cm ²	Action Level
998	Positive	Off	Exterior	1342	Hall Fence		Metal	A	Center	Intact	6.0 mg/cm ²	Action Level
1008	Positive	Off	Common	1342 NE Stair 1	Support	Beam	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level
1009	Positive	Off	Common	1342 NE Stair 1	Support	Column	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level
1010	Positive	Off	Common	1342 NE Stair 1	Window	Sill	Concrete	C	Left	Intact	1.5 mg/cm ²	Action Level
1011	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	C	UC	Intact	1.3 mg/cm ²	Action Level
1012	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	D	UL	Intact	1.7 mg/cm ²	Action Level
1013	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	B	UC	Intact	1.2 mg/cm ²	Action Level
1014	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	A	UC	Intact	1.3 mg/cm ²	Action Level
1023	Positive	Off	Common	1342 S Stair 1	Wall		Brick	B	UC	Intact	1.8 mg/cm ²	Action Level
1024	Positive	Off	Common	1342 S Stair 1	Wall		Brick	C	UL	Intact	1.9 mg/cm ²	Action Level
1025	Positive	Off	Common	1342 S Stair 1	Wall		Brick	D	UR	Intact	1.9 mg/cm ²	Action Level
1026	Positive	Off	Common	1342 S Stair 1	Wall		Brick	A	UC	Intact	1.9 mg/cm ²	Action Level
1027	Positive	Off	Common	1342 S Stair 1	Support	Column	Concrete	B	Right	Intact	2.0 mg/cm ²	Action Level
1028	Positive	Off	Common	1342 S Stair 1	Support	Beam	Concrete	B	Right	Intact	1.8 mg/cm ²	Action Level
1029	Positive	Off	Common	1342 S Stair 1	Window	Sill	Concrete	D	Left	Intact	2.0 mg/cm ²	Action Level
1036	Positive	Off	Common	1342 S Stair 6	Window	Sill	Concrete	D	Left	Intact	2.1 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1037	Positive	Off	Common	1342 S Stair 6	Support	Column	Concrete	C	Left	Intact	2.0 mg/cm ²	Action Level
1038	Positive	Off	Common	1342 S Stair 6	Support	Beam	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
1039	Positive	Off	Common	1342 S Stair 6	Wall		Brick	C	LC	Intact	2.7 mg/cm ²	Action Level
1040	Positive	Off	Common	1342 S Stair 6	Wall		Brick	D	LL	Intact	2.1 mg/cm ²	Action Level
1041	Positive	Off	Common	1342 S Stair 6	Wall		Brick	B	LC	Intact	2.1 mg/cm ²	Action Level
1042	Positive	Off	Common	1342 S Stair 6	Wall		Brick	C	LC	Intact	2.3 mg/cm ²	Action Level
1052	Positive	Off	Common	1342 NE Stair 6	Support	Column	Concrete	B	Left	Intact	1.2 mg/cm ²	Action Level
1053	Positive	Off	Common	1342 NE Stair 6	Support	Beam	Concrete	B	Left	Intact	1.0 mg/cm ²	Action Level
1054	Positive	Off	Common	1342 NE Stair 6	Window	Sill	Concrete	C	Left	Intact	1.1 mg/cm ²	Action Level
1055	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	C	UC	Intact	1.1 mg/cm ²	Action Level
1056	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	D	LL	Intact	1.1 mg/cm ²	Action Level
1057	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	A	UC	Intact	2.6 mg/cm ²	Action Level
1058	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	B	UC	Intact	1.8 mg/cm ²	Action Level
1062	Positive	Off	Common	1342 7 Elevator	Window	Casing	Metal	C	Center	Intact	1.7 mg/cm ²	Action Level
1080	Positive	Off	Common	1342 6 Elevator	Window	Casing	Metal	C	Center	Intact	2.5 mg/cm ²	Action Level
1090	Positive	Off	Common	1342 5 Elevator	Window	Casing	Metal	C	Center	Intact	3.5 mg/cm ²	Action Level
1106	Positive	Off	Common	1342 4 Elevator	Window	Casing	Metal	C	Center	Intact	1.9 mg/cm ²	Action Level
1115	Positive	Off	Common	1342 3 Elevator	Window	Casing	Metal	C	Center	Intact	1.4 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1131	Positive	Off	Common	1342 2 Elevator	Window	Casing	Metal	C	Left	Intact	2.5 mg/cm ²	Action Level
1156		Off	Calibration								-0.1 mg/cm ²	Action Level
1157		Off	Calibration								0.0 mg/cm ²	Action Level
1158		Off	Calibration								0.1 mg/cm ²	Action Level
1159		Off	Calibration								1.0 mg/cm ²	Action Level
1160		Off	Calibration								1.0 mg/cm ²	Action Level
1161		Off	Calibration								1.1 mg/cm ²	Action Level
1175	Positive	Off	Common	Main Office Toilet	Window	Casing	Metal	A	Center	Intact	1.0 mg/cm ²	Action Level
1285	Positive	Off	Apartment	02-609 Bed 1	Window	Casing	Metal	C	Right	Intact	1.1 mg/cm ²	Action Level
1311	Positive	Off	Apartment	02-609 Bed 2	Window	Casing	Metal	C	Left	Intact	1.3 mg/cm ²	Action Level
1312	Positive	Off	Apartment	02-609 Bathroom	Window	Casing	Metal	A	Center	Intact	1.3 mg/cm ²	Action Level
1347	Positive	Off	Apartment	02-607 Bedroom	Window	Casing	Metal	C	Left	Intact	1.0 mg/cm ²	Action Level
1406	Positive	Off	Apartment	02-508 Bedroom	Window	Casing	Metal	C	Right	Intact	1.0 mg/cm ²	Action Level
1407	Positive	Off	Apartment	02-508 LR	Window	Casing	Metal	C	Right	Intact	1.0 mg/cm ²	Action Level
1430	Positive	Off	Apartment	02-506 Bathroom	Window	Casing	Metal	A	Left	Intact	1.0 mg/cm ²	Action Level
1451	Positive	Off	Apartment	02-506 Bedroom	Window	Casing	Metal	C	Right	Intact	2.5 mg/cm ²	Action Level
1452	Positive	Off	Apartment	02-506 LR	Window	Casing	Metal	C	Left	Intact	2.5 mg/cm ²	Action Level
1493	Positive	Off	Apartment	02-503 Bedroom	Window	Casing	Metal	D	Right	Intact	1.3 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1496	Positive	Off	Apartment	02-503 LR	Window	Casing	Metal	D	Left	Intact	1.4 mg/cm ²	Action Level
1517	Positive	Off	Apartment	02-407 Kitchen	Window	Casing	Metal	A	Right	Intact	1.5 mg/cm ²	Action Level
1528	NULL	Off	Apartment	02-407 LR	Window	Casing	Metal	C	Right	Intact	0.9 mg/cm ²	Action Level
1544	Positive	Off	Apartment	02-407 Bathroom	Window	Casing	Metal	A	Center	Intact	1.0 mg/cm ²	Action Level
1550		Off	Calibration								0.9 mg/cm ²	Action Level
1551		Off	Calibration								0.9 mg/cm ²	Action Level
1552		Off	Calibration								0.9 mg/cm ²	Action Level
1553		Off	Calibration								0.1 mg/cm ²	Action Level
1554		Off	Calibration								0.0 mg/cm ²	Action Level
1555		Off	Calibration								0.0 mg/cm ²	Action Level
1566	Positive	Off	Apartment	02-206 Kitchen	Window	Casing	Metal	A	Left	Intact	1.1 mg/cm ²	Action Level
1571	Positive	Off	Apartment	02-206 Bathroom	Window	Casing	Metal	A	Center	Intact	1.2 mg/cm ²	Action Level
1592	Positive	Off	Apartment	02-206 LR	Window	Casing	Metal	C	Left	Intact	1.2 mg/cm ²	Action Level
1616	Positive	Off	Apartment	02-204 LR	Window	Casing	Metal	D	Right	Intact	1.0 mg/cm ²	Action Level
1633	Positive	Off	Apartment	02-204 Bedroom	Window	Casing	Metal	D	Left	Intact	1.3 mg/cm ²	Action Level
1654	Positive	Off	Apartment	02-104 Kitchen	Window	Casing	Metal	B	Right	Intact	1.7 mg/cm ²	Action Level
1680	Positive	Off	Apartment	02-104 Bedroom	Window	Casing	Metal	D	Left	Intact	1.6 mg/cm ²	Action Level
1681	Positive	Off	Apartment	02-104 Bathroom	Window	Casing	Metal	B	Center	Intact	1.6 mg/cm ²	Action Level

Summary Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 172
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1712	Positive	Off	Apartment	02-105 Bathroom	Window	Casing	Metal	B	Center	Intact	1.0 mg/cm ²	Action Level
1738	Positive	Off	Apartment	02-105 Bed 2	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level
1739	Positive	Off	Apartment	02-105 LR	Window	Casing	Metal	D	Right	Intact	1.1 mg/cm ²	Action Level
1758	Positive	Off	Apartment	02-105 Kitchen	Window	Casing	Metal	B	Right	Intact	1.2 mg/cm ²	Action Level
1760		Off	Calibration								1.0 mg/cm ²	Action Level
1761		Off	Calibration								1.0 mg/cm ²	Action Level
1762		Off	Calibration								1.0 mg/cm ²	Action Level
1763		Off	Calibration								0.0 mg/cm ²	Action Level
1764		Off	Calibration								-0.1 mg/cm ²	Action Level
1765		Off	Calibration								-0.1 mg/cm ²	Action Level

----- END OF READINGS -----

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

B-2: XRF Detailed Report

Detailed Lead Paint Inspection Report

Synergya PAS, Inc.

INSPECTION DATE:	12/8/2020 - 12/9/2020
INSTRUMENT TYPE:	Heuresis Corp. Pb200i XRF Lead Paint Analyzer 2187
ACTION LEVEL:	1.0 mg/cm ²
Job ID:	12081016
STATEMENT:	Lead Paint Inspection

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1		Off	Calibration				Wood			Intact	-0.3 mg/cm ²	Action Level
2		Off	Calibration				Wood			Intact	0.0 mg/cm ²	Action Level
3		Off	Calibration				Wood			Intact	0.0 mg/cm ²	Action Level
4		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
5		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
6		Off	Calibration				Wood			Intact	1.1 mg/cm ²	Action Level
7	Positive	Off	Exterior	1314	Lintel		Metal	A	Right	Intact	2.1 mg/cm ²	Action Level
8	Positive	Off	Exterior	1314	Lintel		Metal	A	Center	Intact	2.1 mg/cm ²	Action Level
9	Positive	Off	Exterior	1314	Lintel		Metal	A	Left	Intact	2.1 mg/cm ²	Action Level
10	Positive	Off	Exterior	1314	Lintel		Metal	C	Left	Intact	2.3 mg/cm ²	Action Level
11	Positive	Off	Exterior	1314	Lintel		Metal	C	Center	Intact	2.2 mg/cm ²	Action Level
12	Positive	Off	Exterior	1314	Lintel		Metal	C	Right	Intact	1.7 mg/cm ²	Action Level
13	Negative	Off	Exterior	1314	Door	Panel	Metal	C	Left	Intact	0.5 mg/cm ²	Action Level
14	Negative	Off	Exterior	1314	Door	Casing	Metal	C	Left	Intact	0.5 mg/cm ²	Action Level
15	Negative	Off	Exterior	1314	Door	Casing	Metal	A	Left	Intact	0.5 mg/cm ²	Action Level
16	Negative	Off	Exterior	1314	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
17	Negative	Off	Exterior	1314	Wall		Brick	A	LL	Intact	0.6 mg/cm ²	Action Level
18	Negative	Off	Exterior	1314	Drain	Pipe	Metal	A	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
19	Negative	Off	Exterior	1314	Drain	Pipe	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
20	Negative	Off	Exterior	1314	Drain	Pipe	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
21	Negative	Off	Exterior	1314	Wall		Brick	C	LL	Intact	0.1 mg/cm ²	Action Level
22	Negative	Off	Exterior	1314	Wall		Concrete	C	LL	Intact	0.2 mg/cm ²	Action Level
23	Negative	Off	Exterior	1314	Wall		Concrete	B	UC	Intact	0.2 mg/cm ²	Action Level
24	Negative	Off	Exterior	1314	Wall		Concrete	A	UC	Intact	0.1 mg/cm ²	Action Level
25	Negative	Off	Exterior	1314	Wall		Concrete	D	UL	Intact	0.1 mg/cm ²	Action Level
26	Negative	Off	Common	1314 1 Elevator	Pipe		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
27	Negative	Off	Common	1314 1 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
28	Negative	Off	Common	1314 1 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.6 mg/cm ²	Action Level
29	Negative	Off	Common	1314 1 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.6 mg/cm ²	Action Level
30	Negative	Off	Common	1314 1 Elevator	Door	Panel	Metal	D	Right	Intact	0.6 mg/cm ²	Action Level
31	Negative	Off	Common	1314 1 Elevator	Door	Jamb	Metal	D	Right	Intact	0.6 mg/cm ²	Action Level
32	Negative	Off	Common	1314 1 Elevator	Ceiling		Concrete	D		Intact	0.2 mg/cm ²	Action Level
33	Negative	Off	Common	1314 1 Elevator	Support	Beam	Concrete	D	Right	Intact	0.3 mg/cm ²	Action Level
34	Negative	Off	Common	1314 1 Elevator	Wall		Concrete	C	LC	Intact	0.1 mg/cm ²	Action Level
35	Negative	Off	Common	1314 1 Elevator	Wall		Conc Block	B	LR	Intact	-0.1 mg/cm ²	Action Level
36	Negative	Off	Common	1314 1 Elevator	Chase		Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
37	Negative	Off	Common	1314 2 Elevator	Wall		Conc Block	B	LR	Intact	0.0 mg/cm ²	Action Level
38	Negative	Off	Common	1314 2 Elevator	Wall		Concrete	C	LL	Intact	0.0 mg/cm ²	Action Level
39	Negative	Off	Common	1314 2 Elevator	Ceiling		Concrete	C		Intact	0.3 mg/cm ²	Action Level
40	Negative	Off	Common	1314 2 Elevator	Support	Beam	Concrete	C	Center	Intact	0.2 mg/cm ²	Action Level
41	Negative	Off	Common	1314 2 Elevator	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
42	Negative	Off	Common	1314 2 Elevator	Wall		Drywall	D	LL	Intact	0.2 mg/cm ²	Action Level
43	Negative	Off	Common	1314 2 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.4 mg/cm ²	Action Level
44	Negative	Off	Common	1314 2 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.5 mg/cm ²	Action Level
45	Negative	Off	Common	1314 2 Elevator	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
46	Negative	Off	Common	1314 2 Elevator	Pipe		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
47	Negative	Off	Common	1314 2 Elevator	Wall		Concrete	C	LC	Intact	-0.2 mg/cm ²	Action Level
48	Negative	Off	Common	1314 3 Elevator	Wall		Concrete	C	LC	Intact	0.0 mg/cm ²	Action Level
49	Negative	Off	Common	1314 3 Elevator	Support	Beam	Concrete	C	Center	Intact	-0.1 mg/cm ²	Action Level
50	Negative	Off	Common	1314 3 Elevator	Ceiling		Concrete	C		Intact	-0.2 mg/cm ²	Action Level
51	Negative	Off	Common	1314 3 Elevator	Wall		Drywall	A	LL	Intact	0.2 mg/cm ²	Action Level
52	Negative	Off	Common	1314 3 Elevator	Wall		Drywall	D	LL	Intact	0.1 mg/cm ²	Action Level
53	Negative	Off	Common	1314 3 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
54	Negative	Off	Common	1314 3 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.5 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
55	Negative	Off	Common	1314 3 Elevator	Radiator	Cover	Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
56	Negative	Off	Common	1314 3 Elevator	Pipe		Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
57	Negative	Off	Common	1314 3 Elevator	Door	Panel	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
58	Negative	Off	Common	1314 3 Elevator	Door	Casing	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
59	Negative	Off	Common	1314 4 Elevator	Door	Casing	Metal	A	Center	Intact	-0.1 mg/cm ²	Action Level
60	Negative	Off	Common	1314 4 Elevator	Door	Panel	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
61	Negative	Off	Common	1314 4 Elevator	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
62	Negative	Off	Common	1314 4 Elevator	Pipe		Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
63	Negative	Off	Common	1314 4 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
64	Negative	Off	Common	1314 4 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.4 mg/cm ²	Action Level
65	Negative	Off	Common	1314 4 Elevator	Wall		Drywall	B	UL	Intact	0.2 mg/cm ²	Action Level
66	Negative	Off	Common	1314 4 Elevator	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
67	Negative	Off	Common	1314 4 Elevator	Wall		Concrete	C	LL	Intact	-0.1 mg/cm ²	Action Level
68	Negative	Off	Common	1314 4 Elevator	Support	Beam	Concrete	C	Center	Intact	-0.1 mg/cm ²	Action Level
69	Negative	Off	Common	1314 4 Elevator	Ceiling		Concrete	C		Intact	-0.1 mg/cm ²	Action Level
70	Negative	Off	Common	1314 5 Elevator	Ceiling		Concrete	C		Intact	-0.1 mg/cm ²	Action Level
71	Negative	Off	Common	1314 5 Elevator	Support	Beam	Concrete	C	Center	Intact	0.0 mg/cm ²	Action Level
72	Negative	Off	Common	1314 5 Elevator	Wall		Concrete	C	LL	Intact	-0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
73	Negative	Off	Common	1314 5 Elevator	Wall		Drywall	A	LL	Intact	0.2 mg/cm ²	Action Level
74	Negative	Off	Common	1314 5 Elevator	Wall		Metal	D	LL	Intact	0.1 mg/cm ²	Action Level
75	Negative	Off	Common	1314 5 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
76	Negative	Off	Common	1314 5 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.4 mg/cm ²	Action Level
77	Negative	Off	Common	1314 5 Elevator	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
78	Negative	Off	Common	1314 6 Elevator	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
79	Negative	Off	Common	1314 6 Elevator	Pipe		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
80	Negative	Off	Common	1314 6 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
81	Negative	Off	Common	1314 6 Elevator	Wall		Drywall	A	UL	Intact	0.5 mg/cm ²	Action Level
82	Negative	Off	Common	1314 6 Elevator	Wall		Conc Block	B	LR	Intact	0.4 mg/cm ²	Action Level
83	Negative	Off	Common	1314 6 Elevator	Wall		Conc Block	C	LC	Intact	0.1 mg/cm ²	Action Level
84	Negative	Off	Common	1314 6 Elevator	Wall		Brick	C	UC	Intact	-0.2 mg/cm ²	Action Level
85	Negative	Off	Common	1314 6 Elevator	Support	Beam	Concrete	C	Center	Intact	-0.1 mg/cm ²	Action Level
86	Negative	Off	Common	1314 6 Elevator	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
87	Negative	Off	Common	1314 6 Elevator	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
88	Negative	Off	Common	1314 6 Elevator	Door	Casing	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
89	Negative	Off	Common	1314 7 Elevator	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
90	Negative	Off	Common	1314 7 Elevator	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
91	Negative	Off	Common	1314 7 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.5 mg/cm ²	Action Level
92	Negative	Off	Common	1314 7 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
93	Negative	Off	Common	1314 7 Elevator	Radiator	Cover	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
94	Negative	Off	Common	1314 7 Elevator	Pipe		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
95	Negative	Off	Common	1314 7 Elevator	Wall		Brick	C	LL	Intact	0.2 mg/cm ²	Action Level
96	Negative	Off	Common	1314 7 Elevator	Wall		Conc Block	C	LL	Intact	0.3 mg/cm ²	Action Level
97	Negative	Off	Common	1314 7 Elevator	Wall		Conc Block	B	LR	Intact	0.4 mg/cm ²	Action Level
98	Negative	Off	Common	1314 7 Elevator	Support	Beam	Concrete	C	Left	Intact	0.2 mg/cm ²	Action Level
99	Negative	Off	Common	1314 7 Elevator	Ceiling		Concrete	C		Intact	0.2 mg/cm ²	Action Level
100	Negative	Off	Common	1314 7 Elevator	Wall		Drywall	D	LL	Intact	0.1 mg/cm ²	Action Level
101	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	A	UL	Deteriorated	1.0 mg/cm ²	Action Level
102	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	B	UC	Intact	1.3 mg/cm ²	Action Level
103	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	C	UC	Intact	1.4 mg/cm ²	Action Level
104	Positive	Off	Common	1314 NE Stair 6	Wall		Brick	D	UC	Intact	1.3 mg/cm ²	Action Level
105	Positive	Off	Common	1314 NE Stair 6	Support	Beam	Concrete	A	Left	Intact	1.7 mg/cm ²	Action Level
106	Positive	Off	Common	1314 NE Stair 6	Support	Column	Concrete	A	Left	Intact	1.8 mg/cm ²	Action Level
107	Negative	Off	Common	1314 NE Stair 6	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
108	Positive	Off	Common	1314 NE Stair 6	Window	Sill	Concrete	C	Left	Intact	1.8 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
109	Negative	Off	Common	1314 NE Stair 6	Stairs		Concrete	C	Center	Intact	0.2 mg/cm ²	Action Level
110	Negative	Off	Common	1314 NE Stair 6	Floor		Concrete	B		Intact	0.1 mg/cm ²	Action Level
111	Negative	Off	Common	1314 NE Stair 6	Railing		Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
112	Negative	Off	Common	1314 NE Stair 6	Door	Panel	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
113	Negative	Off	Common	1314 NE Stair 6	Door	Casing	Metal	D	Left	Intact	0.6 mg/cm ²	Action Level
114	Negative	Off	Common	1314 SW Stair 6	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
115	Negative	Off	Common	1314 SW Stair 6	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
116	Negative	Off	Common	1314 SW Stair 6	Railing		Metal	B	Center	Intact	0.0 mg/cm ²	Action Level
117	Negative	Off	Common	1314 SW Stair 6	Stair		Concrete	B	Center	Intact	0.3 mg/cm ²	Action Level
118	Negative	Off	Common	1314 SW Stair 6	Floor		Concrete	A		Intact	0.2 mg/cm ²	Action Level
119	Positive	Off	Common	1314 SW Stair 6	Window	Sill	Concrete	D	Left	Intact	1.3 mg/cm ²	Action Level
120	Positive	Off	Common	1314 SW Stair 6	Support	Beam	Concrete	C	Left	Intact	1.1 mg/cm ²	Action Level
121	Positive	Off	Common	1314 SW Stair 6	Support	Column	Concrete	C	Left	Intact	1.4 mg/cm ²	Action Level
122	Negative	Off	Common	1314 SW Stair 6	Ceiling		Concrete	C		Intact	0.2 mg/cm ²	Action Level
123	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	A	UL	Intact	1.7 mg/cm ²	Action Level
124	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	B	UC	Intact	1.6 mg/cm ²	Action Level
125	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	C	UR	Intact	1.7 mg/cm ²	Action Level
126	Positive	Off	Common	1314 SW Stair 6	Wall		Brick	D	UC	Intact	1.7 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
127	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	D	LC	Intact	2.3 mg/cm ²	Action Level
128	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	C	LL	Intact	1.3 mg/cm ²	Action Level
129	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	B	LR	Intact	1.8 mg/cm ²	Action Level
130	Positive	Off	Common	1314 SW Stair 1	Wall		Brick	A	LC	Intact	1.9 mg/cm ²	Action Level
131	Negative	Off	Common	1314 SW Stair 1	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
132	Positive	Off	Common	1314 SW Stair 1	Support	Beam	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
133	Positive	Off	Common	1314 SW Stair 1	Support	Column	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
134	Positive	Off	Common	1314 SW Stair 1	Window	Sill	Concrete	D	Left	Intact	2.3 mg/cm ²	Action Level
135	Negative	Off	Common	1314 SW Stair 1	Stair		Concrete	B	Center	Intact	0.1 mg/cm ²	Action Level
136	Negative	Off	Common	1314 SW Stair 1	Floor		Concrete	C		Intact	0.3 mg/cm ²	Action Level
137	Negative	Off	Common	1314 SW Stair 1	Railing		Metal	B	Center	Intact	0.0 mg/cm ²	Action Level
138	Negative	Off	Common	1314 SW Stair 1	Door	Casing	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
139	Negative	Off	Common	1314 SW Stair 1	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
140	Negative	Off	Common	1314 SW Stair 1	Door	Panel	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
141	Negative	Off	Common	1314 NE Stair 1	Door	Panel	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
142	Negative	Off	Common	1314 NE Stair 1	Door	Casing	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
143	Negative	Off	Common	1314 NE Stair 1	Railing		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
144	Negative	Off	Common	1314 NE Stair 1	Stairs		Concrete	A	Center	Intact	0.3 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
145	Negative	Off	Common	1314 NE Stair 1	Floor		Concrete	D		Intact	0.1 mg/cm ²	Action Level
146	Negative	Off	Common	1314 NE Stair 1	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
147	Positive	Off	Common	1314 NE Stair 1	Window	Sill	Concrete	C	Left	Intact	1.2 mg/cm ²	Action Level
148	Positive	Off	Common	1314 NE Stair 1	Support	Column	Concrete	A	Right	Intact	1.3 mg/cm ²	Action Level
149	Positive	Off	Common	1314 NE Stair 1	Support	Beam	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level
150	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	A	LC	Intact	1.9 mg/cm ²	Action Level
151	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	B	LL	Intact	1.8 mg/cm ²	Action Level
152	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	C	LC	Intact	1.8 mg/cm ²	Action Level
153	Positive	Off	Common	1314 NE Stair 1	Wall		Brick	D	LL	Intact	1.7 mg/cm ²	Action Level
154	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Left	Intact	1.8 mg/cm ²	Action Level
155	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Center	Intact	1.4 mg/cm ²	Action Level
156	Positive	Off	Exterior	1314	Hall Fence		Metal	A	Right	Intact	1.5 mg/cm ²	Action Level
157	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Right	Intact	1.5 mg/cm ²	Action Level
158	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Center	Intact	1.5 mg/cm ²	Action Level
159	Positive	Off	Exterior	1314	Hall Fence		Metal	B	Left	Intact	1.5 mg/cm ²	Action Level
160	Negative	Off	Exterior	1314	Perimeter	Fence	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
161	Negative	Off	Exterior	1342	Perimeter	Fence	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
162	Negative	Off	Exterior	1342	Perimeter	Fence	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
163	Negative	Off	Exterior		Perimeter	Fence	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
164		Off	Calibration								0.0 mg/cm ²	Action Level
165		Off	Calibration								-0.2 mg/cm ²	Action Level
166		Off	Calibration								-0.1 mg/cm ²	Action Level
167		Off	Calibration								1.1 mg/cm ²	Action Level
168		Off	Calibration								1.0 mg/cm ²	Action Level
169		Off	Calibration								1.1 mg/cm ²	Action Level
170	Negative	Off	Apartment	01-707 Kitchen	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
171	Negative	Off	Apartment	01-707 Kitchen	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
172	Negative	Off	Apartment	01-707 Kitchen	Radiator	Cover	Metal	A	Center	Intact	0.3 mg/cm ²	Action Level
173	Negative	Off	Apartment	01-707 Kitchen	Ceiling		Concrete	A		Intact	0.4 mg/cm ²	Action Level
174	Negative	Off	Apartment	01-707 Kitchen	Ceiling		Concrete	A	UC	Intact	0.2 mg/cm ²	Action Level
175	Negative	Off	Apartment	01-707 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
176	Negative	Off	Apartment	01-707 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
177	Negative	Off	Apartment	01-707 Kitchen	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
178	Negative	Off	Apartment	01-707 Kitchen	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
179	Negative	Off	Apartment	01-707 Kitchen	Closet	Wall	Drywall	D	Right	Intact	0.1 mg/cm ²	Action Level
180	Negative	Off	Apartment	01-707 Kitchen	Closet	Ceiling	Concrete	D	Right	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
181	Negative	Off	Apartment	01-707 Kitchen	Closet	Shelf Support	Wood	D	Right	Intact	0.1 mg/cm ²	Action Level
182	Negative	Off	Apartment	01-707 LR	Radiator	Cover	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
183	Positive	Off	Apartment	01-707 LR	Window	Casing	Metal	C	Right	Intact	1.6 mg/cm ²	Action Level
184	Negative	Off	Apartment	01-707 LR	A/C Housing		Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
185	Negative	Off	Apartment	01-707 LR	A/C Housing		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
186	Negative	Off	Apartment	01-707 LR	A/C Housing		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
187	Negative	Off	Apartment	01-707 LR	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
188	Negative	Off	Apartment	01-707 LR	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
189	Negative	Off	Apartment	01-707 LR	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
190	Negative	Off	Apartment	01-707 LR	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
191	Negative	Off	Apartment	01-707 LR	Ceiling		Concrete	D		Intact	0.3 mg/cm ²	Action Level
192	Negative	Off	Apartment	01-707 Bedroom	Ceiling		Concrete	A		Intact	0.3 mg/cm ²	Action Level
193	Negative	Off	Apartment	01-707 Bedroom	Closet	Ceiling	Concrete	A	Left	Intact	0.1 mg/cm ²	Action Level
194	Negative	Off	Apartment	01-707 Bedroom	Closet	Wall	Drywall	A	Left	Intact	0.2 mg/cm ²	Action Level
195	Negative	Off	Apartment	01-707 Bedroom	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
196	Negative	Off	Apartment	01-707 Bedroom	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
197	Negative	Off	Apartment	01-707 Bedroom	Wall		Drywall	C	LL	Intact	0.1 mg/cm ²	Action Level
198	Negative	Off	Apartment	01-707 Bedroom	Wall		Drywall	D	LR	Intact	0.3 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
199	Negative	Off	Apartment	01-707 Bedroom	Radiator	Cover	Metal	C	Left	Intact	0.3 mg/cm ²	Action Level
200	Negative	Off	Apartment	01-707 Bedroom	Window	Casing	Drywall		Left	Intact	0.3 mg/cm ²	Action Level
201	Negative	Off	Apartment	01-707 Bedroom	Wall		Concrete	C	UL	Intact	0.6 mg/cm ²	Action Level
202	Negative	Off	Apartment	01-707 Bedroom	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
203	Negative	Off	Apartment	01-707 Bathroom	Ceiling		Concrete	D		Intact	0.3 mg/cm ²	Action Level
204	Negative	Off	Apartment	01-707 Bathroom	Wall		Drywall	D	UR	Intact	0.0 mg/cm ²	Action Level
205	Negative	Off	Apartment	01-707 Bathroom	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
206	Negative	Off	Apartment	01-707 Bathroom	Wall		Drywall	B	UL	Intact	0.2 mg/cm ²	Action Level
207	Negative	Off	Apartment	01-707 Bathroom	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
208	Negative	Off	Apartment	01-707 Bathroom	Window	Casing	Metal	A	Center	Intact	0.8 mg/cm ²	Action Level
209	Negative	Off	Apartment	01-707 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
210	Negative	Off	Apartment	01-707 Bathroom	Cabinet		Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
211	Negative	Off	Apartment	01-707 Bathroom	Door	Jamb	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
212	Negative	Off	Apartment	01-707 Bathroom	Door	Panel	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
213	Negative	Off	Apartment	01-707 Bedroom	Door	Panel	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
214	Negative	Off	Apartment	01-707 Bedroom	Door	Casing	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
215	Negative	Off	Apartment	01-707 Bedroom	Electric	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
216	Negative	Off	Apartment	01-707 Bedroom	Electric	Panel	Metal	A	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
217	Negative	Off	Apartment	01-707 Bedroom	Electric	Panel	Metal	A	Left	Intact	0.2 mg/cm ²	Action Level
218	Negative	Off	Apartment	01-706 Kitchen	Electric	Panel	Metal	A	Right	Intact	0.2 mg/cm ²	Action Level
219	Negative	Off	Apartment	01-706 Kitchen	Electric	Panel	Metal	A	Right	Intact	0.2 mg/cm ²	Action Level
220	Negative	Off	Apartment	01-706 Kitchen	Electric	Panel	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
221	Negative	Off	Apartment	01-706 Kitchen	Door	Panel	Drywall	A	Right	Intact	0.0 mg/cm ²	Action Level
222	Negative	Off	Apartment	01-706 Kitchen	Radiator	Cover	Metal	A	Center	Intact	0.3 mg/cm ²	Action Level
223	Negative	Off	Apartment	01-706 Kitchen	Window	Casing	Metal	A	Left	Intact	0.9 mg/cm ²	Action Level
224	Negative	Off	Apartment	01-706 Kitchen	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
225	Negative	Off	Apartment	01-706 Kitchen	Closet	Ceiling	Concrete	B	Left	Intact	0.2 mg/cm ²	Action Level
226	Negative	Off	Apartment	01-706 Kitchen	Closet	Wall	Drywall	B	Left	Intact	0.2 mg/cm ²	Action Level
227	Negative	Off	Apartment	01-706 Kitchen	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
228	Negative	Off	Apartment	01-706 Kitchen	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
229	Negative	Off	Apartment	01-706 Kitchen	Wall		Drywall	D	UC	Intact	-0.1 mg/cm ²	Action Level
230	Negative	Off	Apartment	01-706 Kitchen	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
231	Negative	Off	Apartment	01-706 Kitchen	Door	Panel	Wood	B	Center	Intact	0.0 mg/cm ²	Action Level
232	Negative	Off	Apartment	01-706 Kitchen	Door	Casing	Wood	B	Center	Intact	0.0 mg/cm ²	Action Level
233	Negative	Off	Apartment	01-706 Kitchen	Cabinet		Wood	A	Center	Intact	0.0 mg/cm ²	Action Level
234	Negative	Off	Apartment	01-706 Bathroom	Door	Panel	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
235	Negative	Off	Apartment	01-706 Bathroom	Door	Jamb	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
236	Negative	Off	Apartment	01-706 Bathroom	Door	Casing	Metal	A	Center	Intact	0.5 mg/cm ²	Action Level
237	Negative	Off	Apartment	01-706 Bathroom	Radiator	Cover	Metal	B	Center	Intact	0.3 mg/cm ²	Action Level
238	Negative	Off	Apartment	01-706 Bathroom	Cabinet		Metal	B	Center	Intact	0.2 mg/cm ²	Action Level
239	Negative	Off	Apartment	01-706 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
240	Negative	Off	Apartment	01-706 Bathroom	Wall		Drywall	A	LL	Intact	-0.2 mg/cm ²	Action Level
241	Negative	Off	Apartment	01-706 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
242	Negative	Off	Apartment	01-706 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
243	Negative	Off	Apartment	01-706 Bathroom	Ceiling		Concrete	D		Intact	0.0 mg/cm ²	Action Level
244	Negative	Off	Apartment	01-706 Bedroom	Ceiling		Concrete	A		Intact	0.3 mg/cm ²	Action Level
245	Negative	Off	Apartment	01-706 Bedroom	Closet	Ceiling	Concrete	A	Right	Intact	0.1 mg/cm ²	Action Level
246	Negative	Off	Apartment	01-706 Bedroom	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
247	Negative	Off	Apartment	01-706 Bedroom	Wall		Drywall	A	LC	Intact	0.1 mg/cm ²	Action Level
248	Negative	Off	Apartment	01-706 Bedroom	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
249	Negative	Off	Apartment	01-706 Bedroom	Wall		Drywall	D	LC	Intact	0.1 mg/cm ²	Action Level
250	Negative	Off	Apartment	01-706 Bedroom	Wall		Drywall	C	LC	Intact	0.0 mg/cm ²	Action Level
251	Negative	Off	Apartment	01-706 Bedroom	Window	Casing	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
252	Negative	Off	Apartment	01-706 Bedroom	Radiator	Cover	Metal	C	Right	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
253	Negative	Off	Apartment	01-706 Bedroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
254	Negative	Off	Apartment	01-706 Bedroom	Door	Casing	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
255	Negative	Off	Apartment	01-706 Bedroom	Closet	Shelf	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
256	Negative	Off	Apartment	01-706 LR	Door	Panel	Wood	C	Left	Intact	0.1 mg/cm ²	Action Level
257	Negative	Off	Apartment	01-706 LR	Door	Jamb	Wood	C	Left	Intact	0.2 mg/cm ²	Action Level
258	Negative	Off	Apartment	01-706 LR	Window	Casing	Metal	C	Center	Intact	0.2 mg/cm ²	Action Level
259	Negative	Off	Apartment	01-706 LR	Radiator	Cover	Metal	C	Center	Intact	0.3 mg/cm ²	Action Level
260	Negative	Off	Apartment	01-706 LR	A/C Housing		Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
261	Negative	Off	Apartment	01-706 LR	A/C Housing		Metal	C	Right	Intact	-0.1 mg/cm ²	Action Level
262	Negative	Off	Apartment	01-706 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
263	Negative	Off	Apartment	01-706 LR	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
264	Negative	Off	Apartment	01-706 LR	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
265	Negative	Off	Apartment	01-706 LR	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
266	Negative	Off	Apartment	01-706 LR	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
267	Negative	Off	Apartment	01-706 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
268	Negative	Off	Apartment	01-602 Kitchen	Ceiling		Concrete	A		Intact	0.3 mg/cm ²	Action Level
269	Negative	Off	Apartment	01-602 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
270	Negative	Off	Apartment	01-602 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
271	Negative	Off	Apartment	01-602 Kitchen	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
272	Negative	Off	Apartment	01-602 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
273	Negative	Off	Apartment	01-602 Kitchen	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
274	Negative	Off	Apartment	01-602 Kitchen	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
275	Negative	Off	Apartment	01-602 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.4 mg/cm ²	Action Level
276	Negative	Off	Apartment	01-602 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.3 mg/cm ²	Action Level
277	Negative	Off	Apartment	01-602 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.3 mg/cm ²	Action Level
278	Negative	Off	Apartment	01-602 Kitchen	Radiator	Cover	Metal	B	Center	Intact	0.3 mg/cm ²	Action Level
279	Negative	Off	Apartment	01-602 Kitchen	Window	Casing	Metal	B	Right	Intact	0.8 mg/cm ²	Action Level
280	Negative	Off	Apartment	01-602 Kitchen	Cabinet		Wood	D	Center	Intact	0.1 mg/cm ²	Action Level
281	Negative	Off	Apartment	01-602 Kitchen	Door	Panel	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
282	Negative	Off	Apartment	01-602 Kitchen	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
283	Negative	Off	Apartment	01-602 Kitchen	Door	Casing	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
284	Negative	Off	Apartment	01-602 Kitchen	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
285	Negative	Off	Apartment	01-602 LR	A/C Housing		Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
286	Negative	Off	Apartment	01-602 LR	A/C Housing		Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
287	Negative	Off	Apartment	01-602 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
288	Negative	Off	Apartment	01-602 LR	Window	Casing	Metal	D	Right	Intact	0.5 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
289	Negative	Off	Apartment	01-602 LR	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
290	Negative	Off	Apartment	01-602 LR	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
291	Negative	Off	Apartment	01-602 LR	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
292	Negative	Off	Apartment	01-602 LR	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
293	Negative	Off	Apartment	01-602 LR	Wall		Drywall	A	UR	Intact	0.0 mg/cm ²	Action Level
294	Negative	Off	Apartment	01-602 LR	Radiator	Cover	Metal	D	Right	Intact	0.3 mg/cm ²	Action Level
295	Negative	Off	Apartment	01-602 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
296	Negative	Off	Apartment	01-602 Bedroom	Window	Casing	Metal	D	Left	Intact	0.9 mg/cm ²	Action Level
297	Negative	Off	Apartment	01-602 Bedroom	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
298	Negative	Off	Apartment	01-602 Bedroom	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
299	Negative	Off	Apartment	01-602 Bedroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
300	Negative	Off	Apartment	01-602 Bedroom	Wall		Drywall	A	UR	Intact	0.3 mg/cm ²	Action Level
301	Negative	Off	Apartment	01-602 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.4 mg/cm ²	Action Level
302	Negative	Off	Apartment	01-602 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.2 mg/cm ²	Action Level
303	Negative	Off	Apartment	01-602 Bedroom	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
304	Negative	Off	Apartment	01-602 Bedroom	Closet	Shelf Support	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
305	Negative	Off	Apartment	01-602 Bedroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
306	Negative	Off	Apartment	01-602 Bedroom	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
307	Negative	Off	Apartment	01-602 Bathroom	Door	Jamb	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level
308	Negative	Off	Apartment	01-602 Bathroom	Door	Panel	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level
309	Negative	Off	Apartment	01-602 Bathroom	Cabinet		Wood	A	Center	Intact	0.2 mg/cm ²	Action Level
310	Negative	Off	Apartment	01-602 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.2 mg/cm ²	Action Level
311	Negative	Off	Apartment	01-602 Bathroom	Window	Casing	Metal	B	Center	Intact	0.4 mg/cm ²	Action Level
312	Negative	Off	Apartment	01-602 Bathroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
313	Negative	Off	Apartment	01-602 Bathroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
314	Negative	Off	Apartment	01-602 Bathroom	Wall		Drywall	C	UL	Intact	0.3 mg/cm ²	Action Level
315	Negative	Off	Apartment	01-602 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
316	Negative	Off	Apartment	01-602 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
317	Negative	Off	Apartment	01-609 Entry	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
318	Negative	Off	Apartment	01-609 Entry	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
319	Negative	Off	Apartment	01-609 Entry	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
320	Negative	Off	Apartment	01-609 Entry	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
321	Negative	Off	Apartment	01-609 Entry	Closet	Wall	Drywall	B	Center	Intact	0.1 mg/cm ²	Action Level
322	Negative	Off	Apartment	01-609 Entry	Closet	Ceiling	Concrete	B	Center	Intact	0.1 mg/cm ²	Action Level
323	Negative	Off	Apartment	01-609 Entry	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
324	Negative	Off	Apartment	01-609 Entry	Door	Jamb	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
325	Negative	Off	Apartment	01-609 Entry	Radiator	Cover	Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
326	Negative	Off	Apartment	01-609 Entry	Door	Panel	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
327	Negative	Off	Apartment	01-609 Entry	Door	Casing	Wood	D	Left	Intact	-0.1 mg/cm ²	Action Level
328	Negative	Off	Apartment	01-609 Kitchen	Cabinet		Wood	C	Center	Intact	0.1 mg/cm ²	Action Level
329	Negative	Off	Apartment	01-609 Kitchen	Radiator	Cover	Metal	A	Left	Intact	0.3 mg/cm ²	Action Level
330	Negative	Off	Apartment	01-609 Kitchen	Wall		Concrete	A	UC	Intact	0.8 mg/cm ²	Action Level
331	Negative	Off	Apartment	01-609 Kitchen	Wall		Drywall	B	UR	Intact	0.3 mg/cm ²	Action Level
332	Negative	Off	Apartment	01-609 Kitchen	Wall		Drywall	C	UL	Intact	-0.2 mg/cm ²	Action Level
333	Negative	Off	Apartment	01-609 Kitchen	Wall		Drywall	D	UC	Intact	-0.2 mg/cm ²	Action Level
334	Negative	Off	Apartment	01-609 Kitchen	Ceiling		Concrete	D		Intact	0.4 mg/cm ²	Action Level
335	Negative	Off	Apartment	01-609 LR	Ceiling		Concret	B		Intact	0.1 mg/cm ²	Action Level
336	Negative	Off	Apartment	01-609 LR	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
337	Negative	Off	Apartment	01-609 LR	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
338	Negative	Off	Apartment	01-609 LR	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
339	Negative	Off	Apartment	01-609 LR	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
340	Negative	Off	Apartment	01-609 LR	Radiator	Cover	Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
341	Negative	Off	Apartment	01-609 LR	Window	Casing	Metal	C	Left	Intact	0.7 mg/cm ²	Action Level
342	Negative	Off	Apartment	01-609 LR	A/C Housing		Metal	C	Right	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
343	Negative	Off	Apartment	01-609 LR	A/C Housing		Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
344	Negative	Off	Apartment	01-609 LR	A/C Housing		Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
345	Negative	Off	Apartment	01-609 Bed 1	Radiator	Cover	Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
346	Negative	Off	Apartment	01-609 Bed 1	Window	Casing	Metal	C	Left	Intact	0.3 mg/cm ²	Action Level
347	Negative	Off	Apartment	01-609 Bed 1	Door	Panel	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
348	Negative	Off	Apartment	01-609 Bed 1	Door	Jamb	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
349	Negative	Off	Apartment	01-609 Bed 1	Closet	Shelf Support	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
350	Negative	Off	Apartment	01-609 Bed 1	Closet	Ceiling	Concrete	A	Right	Intact	0.0 mg/cm ²	Action Level
351	Negative	Off	Apartment	01-609 Bed 1	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
352	Negative	Off	Apartment	01-609 Bed 1	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
353	Negative	Off	Apartment	01-609 Bed 1	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
354	Negative	Off	Apartment	01-609 Bed 1	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
355	Negative	Off	Apartment	01-609 Bed 1	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
356	Negative	Off	Apartment	01-609 Bed 1	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
357	Negative	Off	Apartment	01-609 Bed 2	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
358	Negative	Off	Apartment	01-609 Bed 2	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
359	Negative	Off	Apartment	01-609 Bed 2	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
360	Negative	Off	Apartment	01-609 Bed 2	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
361	Negative	Off	Apartment	01-609 Bed 2	Closet	Wall	Drywall	A	Left	Intact	0.0 mg/cm ²	Action Level
362	Negative	Off	Apartment	01-609 Bed 2	Closet	Ceiling	Concrete	A	Left	Intact	0.1 mg/cm ²	Action Level
363	Negative	Off	Apartment	01-609 Bed 2	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
364	Negative	Off	Apartment	01-609 Bed 2	Closet	Shelf Support Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
365	Negative	Off	Apartment	01-609 Bed 2	Door		Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
366	Negative	Off	Apartment	01-609 Bed 2	Door	Jamb	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
367	Negative	Off	Apartment	01-609 Bed 2	Radiator	Cover	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
368	Negative	Off	Apartment	01-609 Bed 2	Window	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
369	Negative	Off	Apartment	01-609 Bed 2	A/C Housing		Metal	A	Right	Intact	-0.1 mg/cm ²	Action Level
370	Negative	Off	Apartment	01-609 Bed 2	A/C Housing		Metal	A	Right	Intact	-0.1 mg/cm ²	Action Level
371	Negative	Off	Apartment	01-609 Bed 2	A/C Housing		Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
372	Negative	Off	Apartment	01-609 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
373	Negative	Off	Apartment	01-609 Bathroom	Cabinet		Metal	D	Center	Intact	-0.1 mg/cm ²	Action Level
374	Negative	Off	Apartment	01-609 Bathroom	Door	Panel	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
375	Negative	Off	Apartment	01-609 Bathroom	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
376	Negative	Off	Apartment	01-609 Bathroom	Wall		Drywall	B	UR	Intact	0.0 mg/cm ²	Action Level
377	Negative	Off	Apartment	01-609 Bathroom	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
378	Negative	Off	Apartment	01-609 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
379	Negative	Off	Apartment	01-609 Bathroom	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
380	Negative	Off	Apartment	01-609 Bathroom	Window	Casing	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
381	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
382	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.2 mg/cm ²	Action Level
383	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
384	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
385	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
386	Negative	Off	Apartment	01-209 Entry	Electric	Panel	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
387	Negative	Off	Apartment	01-209 Entry	Door	Panel	Metal	A	Left	Intact	-0.1 mg/cm ²	Action Level
388	Negative	Off	Apartment	01-209 Entry	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
389	Negative	Off	Apartment	01-209 Entry	Radiator	Cover	Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
390	Negative	Off	Apartment	01-209 Entry	Door	Panel	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
391	Negative	Off	Apartment	01-209 Entry	Door	Casing	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
392	Negative	Off	Apartment	01-209 Entry	Closet	Shelf Support	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
393	Negative	Off	Apartment	01-209 Entry	Closet	Wall	Drywall	B	Left	Intact	0.2 mg/cm ²	Action Level
394	Negative	Off	Apartment	01-209 Entry	Closet	Ceiling	Concrete	B	Left	Intact	0.2 mg/cm ²	Action Level
395	Negative	Off	Apartment	01-209 Entry	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
396	Negative	Off	Apartment	01-209 Entry	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
397	Negative	Off	Apartment	01-209 Entry	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
398	Negative	Off	Apartment	01-209 Entry	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
399	Negative	Off	Apartment	01-209 Entry	Wall		Drywall	D	LR	Intact	0.1 mg/cm ²	Action Level
400	Negative	Off	Apartment	01-209 Kitchen	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
401	Negative	Off	Apartment	01-209 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
402	Negative	Off	Apartment	01-209 Kitchen	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
403	Negative	Off	Apartment	01-209 Kitchen	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
404	Negative	Off	Apartment	01-209 Kitchen	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
405	Negative	Off	Apartment	01-209 Kitchen	Window	Casing	Metal	A	Left	Intact	0.3 mg/cm ²	Action Level
406	Negative	Off	Apartment	01-209 Kitchen	Radiator	Cover	Metal	A	Center	Intact	0.3 mg/cm ²	Action Level
407	Negative	Off	Apartment	01-209 Kitchen	Cabinet		Metal	C	Center	Intact	0.0 mg/cm ²	Action Level
408	Negative	Off	Apartment	01-209 LR	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
409	Negative	Off	Apartment	01-209 LR	Window	Casing	Metal	C	Left	Intact	0.3 mg/cm ²	Action Level
410	Negative	Off	Apartment	01-209 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
411	Negative	Off	Apartment	01-209 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
412	Negative	Off	Apartment	01-209 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
413	Negative	Off	Apartment	01-209 LR	Ceiling		Concrete	C		Intact	0.3 mg/cm ²	Action Level
414	Negative	Off	Apartment	01-209 LR	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
415	Negative	Off	Apartment	01-209 LR	Wall		Drywall	D	LC	Intact	0.1 mg/cm ²	Action Level
416	Negative	Off	Apartment	01-209 LR	Wall		Drywall	B	LL	Intact	0.0 mg/cm ²	Action Level
417	Negative	Off	Apartment	01-209 LR	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
418	Negative	Off	Apartment	01-209 Bed 1	Wal		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
419	Negative	Off	Apartment	01-209 Bed 1	Wall		Drywall	B	UR	Intact	-0.1 mg/cm ²	Action Level
420	Negative	Off	Apartment	01-209 Bed 1	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
421	Negative	Off	Apartment	01-209 Bed 1	Wall		Drywall	D	UL	Intact	0.0 mg/cm ²	Action Level
422	Negative	Off	Apartment	01-209 Bed 1	Closet	Wall	Drywall	A	Right	Intact	-0.1 mg/cm ²	Action Level
423	Negative	Off	Apartment	01-209 Bed 1	Closet	Ceiling	Concrete	A	Right	Intact	0.1 mg/cm ²	Action Level
424	Negative	Off	Apartment	01-209 Bed 1	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
425	Negative	Off	Apartment	01-209 Bed 1	Closet	Shelf Support Panel	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
426	Negative	Off	Apartment	01-209 Bed 1	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
427	Negative	Off	Apartment	01-209 Bed 1	Door	Jamb	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
428	Negative	Off	Apartment	01-209 Bed 1	Radiator	Cover	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
429	Negative	Off	Apartment	01-209 Bed 1	Window	Casing	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
430	Negative	Off	Apartment	01-209 Bed 2	Window	Casing	Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
431	Negative	Off	Apartment	01-209 Bed 2	Radiator	Cover	Metal	C	Left	Intact	0.3 mg/cm ²	Action Level
432	Negative	Off	Apartment	01-209 Bed 2	Door	Panel	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
433	Negative	Off	Apartment	01-209 Bed 2	Door	Casing	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
434	Negative	Off	Apartment	01-209 Bed 2	Closet	Shelf Support	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
435	Negative	Off	Apartment	01-209 Bed 2	Closet	Ceiling	Concrete	A	Left	Intact	0.3 mg/cm ²	Action Level
436	Negative	Off	Apartment	01-209 Bed 2	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
437	Negative	Off	Apartment	01-209 Bed 2	Closet	Wall	Drywall	A	Left	Intact	0.2 mg/cm ²	Action Level
438	Negative	Off	Apartment	01-209 Bed 2	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
439	Negative	Off	Apartment	01-209 Bed 2	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
440	Negative	Off	Apartment	01-209 Bed 2	Wall		Drywall	C	LR	Intact	0.0 mg/cm ²	Action Level
441	Negative	Off	Apartment	01-209 Bed 2	Wall		Drywall	D	LL	Intact	0.0 mg/cm ²	Action Level
442	Negative	Off	Apartment	01-209 Bed 2	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
443	Negative	Off	Apartment	01-209 Bed 2	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
444	Negative	Off	Apartment	01-209 Bed 2	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
445	Negative	Off	Apartment	01-209 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
446	Negative	Off	Apartment	01-209 Bathroom	Cabinet		Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
447	Negative	Off	Apartment	01-209 Bathroom	Window	Casing	Metal	A	Left	Intact	0.4 mg/cm ²	Action Level
448	Negative	Off	Apartment	01-209 Bathroom	Wall		Drywall	A	UL	Intact	0.3 mg/cm ²	Action Level
449	Negative	Off	Apartment	01-209 Bathroom	Wall		Drywall	B	UC	Intact	0.3 mg/cm ²	Action Level
450	Negative	Off	Apartment	01-209 Bathroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
451	Negative	Off	Apartment	01-209 Bathroom	Wall		Drywall	D	UR	Intact	0.0 mg/cm ²	Action Level
452	Negative	Off	Apartment	01-209 Bathroom	Ceiling		Concrete	B		Intact	0.3 mg/cm ²	Action Level
453	Negative	Off	Apartment	01-209 Bathroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
454	Negative	Off	Apartment	01-209 Bathroom	Door	Casing	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
455		Off	Calibration								1.1 mg/cm ²	Action Level
456		Off	Calibration								1.1 mg/cm ²	Action Level
457		Off	Calibration								1.1 mg/cm ²	Action Level
458		Off	Calibration								0.0 mg/cm ²	Action Level
459		Off	Calibration								-0.1 mg/cm ²	Action Level
460		Off	Calibration								0.0 mg/cm ²	Action Level
461	Negative	Off	Apartment	01-702 Kitchen	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
462	Negative	Off	Apartment	01-702 Kitchen	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
463	Negative	Off	Apartment	01-702 Kitchen	Wall		Drywall	C	LL	Intact	0.1 mg/cm ²	Action Level
464	Negative	Off	Apartment	01-702 Kitchen	Wall		Drywall	D	LL	Intact	0.1 mg/cm ²	Action Level
465	Negative	Off	Apartment	01-702 Kitchen	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
466	Negative	Off	Apartment	01-702 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.1 mg/cm ²	Action Level
467	Negative	Off	Apartment	01-702 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
468	Negative	Off	Apartment	01-702 Kitchen	Closet	Shelf Support	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
469	Negative	Off	Apartment	01-702 Kitchen	Door	Panel	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
470	Negative	Off	Apartment	01-702 Kitchen	Door	Panel	Metal	B	Left	Intact	0.0 mg/cm ²	Action Level
471	Negative	Off	Apartment	01-702 Kitchen	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
472	Negative	Off	Apartment	01-702 Kitchen	Window	Casing	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
473	Negative	Off	Apartment	01-702 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
474	Negative	Off	Apartment	01-702 Kitchen	Cabinet		Wood	D	Right	Intact	0.0 mg/cm ²	Action Level
475	Negative	Off	Apartment	01-702 LR	Window	Casing	Metal	D	Left	Intact	0.8 mg/cm ²	Action Level
476	Negative	Off	Apartment	01-702 LR	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
477	Negative	Off	Apartment	01-702 LR	A/C Housing		Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
478	Negative	Off	Apartment	01-702 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
479	Negative	Off	Apartment	01-702 LR	A/C Housing		Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
480	Negative	Off	Apartment	01-702 LR	Ceiling		Concrete	D	Left	Intact	0.0 mg/cm ²	Action Level
481	Negative	Off	Apartment	01-702 LR	Wall		Drywall	D	LL	Intact	0.0 mg/cm ²	Action Level
482	Negative	Off	Apartment	01-702 LR	Wall		Drywall	C	LL	Intact	0.1 mg/cm ²	Action Level
483	Negative	Off	Apartment	01-702 LR	Wall		Drywall	B	LC	Intact	0.0 mg/cm ²	Action Level
484	Negative	Off	Apartment	01-702 LR	Wall		Drywall	A	LR	Intact	0.1 mg/cm ²	Action Level
485	Negative	Off	Apartment	01-702 Bedroom	Wall		Drywall	A	LC	Intact	0.1 mg/cm ²	Action Level
486	Negative	Off	Apartment	01-702 Bedroom	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
487	Negative	Off	Apartment	01-702 Bedroom	Wall		Drywall	C	LL	Intact	0.3 mg/cm ²	Action Level
488	Negative	Off	Apartment	01-702 Bedroom	Wall		Drywall	D	LC	Intact	0.1 mg/cm ²	Action Level
489	Negative	Off	Apartment	01-702 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.2 mg/cm ²	Action Level
490	Negative	Off	Apartment	01-702 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.3 mg/cm ²	Action Level
491	Negative	Off	Apartment	01-702 Bedroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
492	Negative	Off	Apartment	01-702 Bedroom	Closet	Shelf Support Panel	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
493	Negative	Off	Apartment	01-702 Bedroom	Door		Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
494	Negative	Off	Apartment	01-702 Bedroom	Door	Jamb	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
495	Negative	Off	Apartment	01-702 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
496	Negative	Off	Apartment	01-702 Bedroom	Window	Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
497	Negative	Off	Apartment	01-702 Bathroom	Cabinet		Metal	A	Center	Intact	0.4 mg/cm ²	Action Level
498	Negative	Off	Apartment	01-702 Bathroom	Radiator	Cover	Metal	A	Center	Intact	-0.2 mg/cm ²	Action Level
499	Negative	Off	Apartment	01-702 Bathroom	Window	Casing	Metal	B	Center	Intact	0.0 mg/cm ²	Action Level
500	Negative	Off	Apartment	01-702 Bathroom	Ceiling		Concrete	B		Intact	0.4 mg/cm ²	Action Level
501	Negative	Off	Apartment	01-702 Bathroom	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
502	Negative	Off	Apartment	01-702 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
503	Negative	Off	Apartment	01-702 Bathroom	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
504	Negative	Off	Apartment	01-702 Bathroom	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
505	Negative	Off	Apartment	01-704 Kitchen	Wall		Drywall	A	UR	Intact	0.2 mg/cm ²	Action Level
506	Negative	Off	Apartment	01-704 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
507	Negative	Off	Apartment	01-704 Kitchen	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
508	Negative	Off	Apartment	01-704 Kitchen	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
509	Negative	Off	Apartment	01-704 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.2 mg/cm ²	Action Level
510	Negative	Off	Apartment	01-704 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.3 mg/cm ²	Action Level
511	Negative	Off	Apartment	01-704 Kitchen	Closet	Shelf Support	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
512	Negative	Off	Apartment	01-704 Kitchen	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
513	Negative	Off	Apartment	01-704 Kitchen	Door	Casing	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
514	Negative	Off	Apartment	01-704 Kitchen	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
515	Negative	Off	Apartment	01-704 Kitchen	Door	Panel	Metal	B	Left	Intact	0.0 mg/cm ²	Action Level
516	Negative	Off	Apartment	01-704 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
517	Negative	Off	Apartment	01-704 Kitchen	Window	Casing	Metal	B	Right	Intact	0.5 mg/cm ²	Action Level
518	Negative	Off	Apartment	01-704 Kitchen	Cabinet		Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
519	Negative	Off	Apartment	01-704 LR	Window	Casing	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
520	Negative	Off	Apartment	01-704 LR	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
521	Negative	Off	Apartment	01-704 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
522	Negative	Off	Apartment	01-704 LR	A/C Housing		Metal	D	Left	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
523	Positive	Off	Apartment	01-704 LR	Window	Casing	Metal	D	Right	Intact	1.7 mg/cm ²	Action Level
524	Negative	Off	Apartment	01-704 LR	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
525	Negative	Off	Apartment	01-704 LR	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
526	Negative	Off	Apartment	01-704 LR	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
527	Negative	Off	Apartment	01-704 LR	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
528	Negative	Off	Apartment	01-704 LR	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
529	Negative	Off	Apartment	01-704 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
530	Negative	Off	Apartment	01-704 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
531	Negative	Off	Apartment	01-704 Kitchen	Electric	Panel	Metal	B	Left	Intact	0.3 mg/cm ²	Action Level
532	Negative	Off	Apartment	01-704 Bedroom	Window	Casing	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
533	Negative	Off	Apartment	01-704 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
534	Negative	Off	Apartment	01-704 Bedroom	Wall		Concrete	D	UL	Intact	0.1 mg/cm ²	Action Level
535	Negative	Off	Apartment	01-704 Bedroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
536	Negative	Off	Apartment	01-704 Bedroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
537	Negative	Off	Apartment	01-704 Bedroom	Wall		Drywall	B	LL	Intact	0.1 mg/cm ²	Action Level
538	Negative	Off	Apartment	01-704 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
539	Negative	Off	Apartment	01-704 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.1 mg/cm ²	Action Level
540	Negative	Off	Apartment	01-704 Bedroom	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
541	Negative	Off	Apartment	01-704 Bedroom	Closet	Shelf Support	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
542	Negative	Off	Apartment	01-704 Bedroom	Door	Panel	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
543	Negative	Off	Apartment	01-704 Bedroom	Door	Casing	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
544	Negative	Off	Apartment	01-704 Bathroom	Door	Jamb	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
545	Negative	Off	Apartment	01-704 Bathroom	Door	Panel	Wood	C	Right	Intact	-0.2 mg/cm ²	Action Level
546	Negative	Off	Apartment	01-704 Bathroom	Cabinet		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
547	Negative	Off	Apartment	01-704 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
548	Negative	Off	Apartment	01-704 Bathroom	Window	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
549	Negative	Off	Apartment	01-704 Bathroom	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
550	Negative	Off	Apartment	01-704 Bathroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
551	Negative	Off	Apartment	01-704 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
552	Negative	Off	Apartment	01-704 Bathroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
553	Negative	Off	Apartment	01-704 Bathroom	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
554	Negative	Off	Apartment	01-603 Kitchen	Wall		Drywall	A	UL	Intact	0.0 mg/cm ²	Action Level
555	Negative	Off	Apartment	01-603 Kitchen	Wall		Drywall	B	UC	Intact	-0.2 mg/cm ²	Action Level
556	Negative	Off	Apartment	01-603 Kitchen	Wall		Drywall	C	UC	Intact	-0.1 mg/cm ²	Action Level
557	Negative	Off	Apartment	01-603 Kitchen	Wall		Drywall	D	UR	Intact	-0.2 mg/cm ²	Action Level
558	Negative	Off	Apartment	01-603 Kitchen	Closet	Wall	Drywall	C	Left	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
559	Negative	Off	Apartment	01-603 Kitchen	Closet	Ceiling	Concrete	C	Left	Intact	-0.1 mg/cm ²	Action Level
560	Negative	Off	Apartment	01-603 Kitchen	Ceiling		Concrete	C		Intact	-0.2 mg/cm ²	Action Level
561	Negative	Off	Apartment	01-603 Kitchen	Closet	Shelf Support Panel	Wood	C	Left	Intact	0.1 mg/cm ²	Action Level
562	Negative	Off	Apartment	01-603 Kitchen	Door		Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
563	Negative	Off	Apartment	01-603 Kitchen	Door	Casing	Wood	C	Right	Intact	0.1 mg/cm ²	Action Level
564	Negative	Off	Apartment	01-603 Kitchen	Door	Jamb	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
565	Negative	Off	Apartment	01-603 Kitchen	Door	Panel	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
566	Negative	Off	Apartment	01-603 Kitchen	Window	Casing	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
567	Negative	Off	Apartment	01-603 Kitchen	Radiator	Cover	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
568	Negative	Off	Apartment	01-603 Kitchen	Cabinet		Wood	D	Right	Intact	0.1 mg/cm ²	Action Level
569	Negative	Off	Apartment	01-603 Bathroom	Cabinet		Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
570	Negative	Off	Apartment	01-603 Bathroom	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
571	Negative	Off	Apartment	01-603 Bathroom	Door	Jamb	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
572	Negative	Off	Apartment	01-603 Bathroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
573	Negative	Off	Apartment	01-603 Bathroom	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
574	Negative	Off	Apartment	01-603 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
575	Negative	Off	Apartment	01-603 Bathroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
576	Negative	Off	Apartment	01-603 Bathroom	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
577	Negative	Off	Apartment	01-603 Bathroom	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
578	Negative	Off	Apartment	01-603 Bathroom	Window	Casing	Metal	B	Right	Intact	-0.1 mg/cm ²	Action Level
579	Negative	Off	Apartment	01-603 Bedroom	Window	Casing	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
580	Negative	Off	Apartment	01-603 Bedroom	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
581	Negative	Off	Apartment	01-603 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
582	Negative	Off	Apartment	01-603 Bedroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
583	Negative	Off	Apartment	01-603 Bedroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
584	Negative	Off	Apartment	01-603 Bedroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
585	Negative	Off	Apartment	01-603 Bedroom	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
586	Negative	Off	Apartment	01-603 Bedroom	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
587	Negative	Off	Apartment	01-603 Bedroom	Ceiling		Concrete	B		Intact	-0.1 mg/cm ²	Action Level
588	Negative	Off	Apartment	01-603 Bedroom	Closet	Shelf Support	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
589	Negative	Off	Apartment	01-603 Bedroom	Door	Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
590	Negative	Off	Apartment	01-603 Bedroom	Door	Jamb	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
591	Negative	Off	Apartment	01-603 LR	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
592	Positive	Off	Apartment	01-603 LR	Window	Casing	Metal	D	Left	Intact	1.1 mg/cm ²	Action Level
593	Negative	Off	Apartment	01-603 LR	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
594	Negative	Off	Apartment	01-603 LR	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
595	Negative	Off	Apartment	01-603 LR	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
596	Negative	Off	Apartment	01-603 LR	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
597	Negative	Off	Apartment	01-603 LR	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
598	Negative	Off	Apartment	01-603 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
599	Negative	Off	Apartment	01-603 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
600	Negative	Off	Apartment	01-603 LR	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
601	Negative	Off	Apartment	01-501 Entry	Door	Panel	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
602	Negative	Off	Apartment	01-501 Entry	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
603	Negative	Off	Apartment	01-501 Entry	Radiator	Cover	Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
604	Negative	Off	Apartment	01-501 Entry	Ceiling		Concrete	C		Intact	0.3 mg/cm ²	Action Level
605	Negative	Off	Apartment	01-501 Entry	Closet	Ceiling	Concrete	C	Left	Intact	0.2 mg/cm ²	Action Level
606	Negative	Off	Apartment	01-501 Entry	Closet	Wall	Drywall	C	Left	Intact	0.0 mg/cm ²	Action Level
607	Negative	Off	Apartment	01-501 Entry	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
608	Negative	Off	Apartment	01-501 Entry	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
609	Negative	Off	Apartment	01-501 Entry	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
610	Negative	Off	Apartment	01-501 Entry	Wall		Drywall	A	UL	Intact	0.0 mg/cm ²	Action Level
611	Negative	Off	Apartment	01-501 Entry	Closet	Shelf Support	Wood	C	Left	Intact	0.0 mg/cm ²	Action Level
612	Negative	Off	Apartment	01-501 Entry	Door	Panel	Wood	C	Left	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
613	Negative	Off	Apartment	01-501 Entry	Door	Casing	Wood	C	Left	Intact	0.1 mg/cm ²	Action Level
614	Negative	Off	Apartment	01-501 Kitchen	Cabinet		Wood	D	Center	Intact	0.0 mg/cm ²	Action Level
615	Negative	Off	Apartment	01-501 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
616	Positive	Off	Apartment	01-501 Kitchen	Window	Casing	Metal	B	Left	Intact	1.4 mg/cm ²	Action Level
617	Negative	Off	Apartment	01-501 Kitchen	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
618	Negative	Off	Apartment	01-501 Kitchen	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
619	Negative	Off	Apartment	01-501 Kitchen	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
620	Negative	Off	Apartment	01-501 Kitchen	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
621	Negative	Off	Apartment	01-501 Kitchen	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
622	Negative	Off	Apartment	01-501 LR	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
623	Negative	Off	Apartment	01-501 LR	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
624	Negative	Off	Apartment	01-501 LR	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
625	Negative	Off	Apartment	01-501 LR	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
626	Negative	Off	Apartment	01-501 LR	Ceiling		Concrete	D		Intact	0.0 mg/cm ²	Action Level
627	Negative	Off	Apartment	01-501 LR	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
628	Negative	Off	Apartment	01-501 LR	Window	Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
629	Negative	Off	Apartment	01-501 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
630	Negative	Off	Apartment	01-501 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
631	Negative	Off	Apartment	01-501 LR	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
632	Negative	Off	Apartment	01-501 Bed 1	Radiator	Cover	Metal	C	Center	Intact	0.2 mg/cm ²	Action Level
633	Negative	Off	Apartment	01-501 Bed 1	Window	Casing	Metal	C	Center	Intact	0.3 mg/cm ²	Action Level
634	Negative	Off	Apartment	01-501 Bed 1	Door	Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
635	Negative	Off	Apartment	01-501 Bed 1	Door	Jamb	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
636	Negative	Off	Apartment	01-501 Bed 1	Closet	Shelf Support	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
637	Negative	Off	Apartment	01-501 Bed 1	Closet	Ceiling	Concrete	B	Right	Intact	-0.1 mg/cm ²	Action Level
638	Negative	Off	Apartment	01-501 Bed 1	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
639	Negative	Off	Apartment	01-501 Bed 1	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
640	Negative	Off	Apartment	01-501 Bed 1	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
641	Negative	Off	Apartment	01-501 Bed 1	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
642	Negative	Off	Apartment	01-501 Bed 1	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
643	Negative	Off	Apartment	01-501 Bed 1	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
644	Negative	Off	Apartment	01-501 Bed 2	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
645	Negative	Off	Apartment	01-501 Bed 2	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
646	Negative	Off	Apartment	01-501 Bed 2	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
647	Negative	Off	Apartment	01-501 Bed 2	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
648	Negative	Off	Apartment	01-501 Bed 2	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
649	Negative	Off	Apartment	01-501 Bed 2	Closet	Ceiling	Concrete	B	Left	Intact	0.0 mg/cm ²	Action Level
650	Negative	Off	Apartment	01-501 Bed 2	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
651	Negative	Off	Apartment	01-501 Bed 2	Closet	Shelf Support Panel	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
652	Negative	Off	Apartment	01-501 Bed 2	Door		Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
653	Negative	Off	Apartment	01-501 Bed 2	Door	Jamb	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level
654	Negative	Off	Apartment	01-501 Bed 2	Window	Casing	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
655	Negative	Off	Apartment	01-501 Bed 2	Radiator	Cover	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
656	Negative	Off	Apartment	01-501 Bed 2	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
657	Negative	Off	Apartment	01-501 Bed 2	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
658	Negative	Off	Apartment	01-501 Bed 2	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
659	Negative	Off	Apartment	01-501 Bathroom	Cabinet		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
660	Negative	Off	Apartment	01-501 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
661	Negative	Off	Apartment	01-501 Bathroom	Window	Casing	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
662	Negative	Off	Apartment	01-501 Bathroom	Door	Panel	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level
663	Negative	Off	Apartment	01-501 Bathroom	Door	Casing	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
664	Negative	Off	Apartment	01-501 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
665	Negative	Off	Apartment	01-501 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
666	Negative	Off	Apartment	01-501 Bathroom	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
667	Negative	Off	Apartment	01-501 Bathroom	Wall		Drywall	A	UL	Intact	0.2 mg/cm ²	Action Level
668	Negative	Off	Apartment	01-501 Bathroom	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
669	Negative	Off	Apartment	01-503 Kitchen	Ceiling		Concrete	A		Intact	0.5 mg/cm ²	Action Level
670	Negative	Off	Apartment	01-503 Kitchen	Wall		Drywall	A	UC	Intact	-0.1 mg/cm ²	Action Level
671	Negative	Off	Apartment	01-503 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
672	Negative	Off	Apartment	01-503 Kitchen	Wall		Drywall	C	UC	Intact	-0.1 mg/cm ²	Action Level
673	Negative	Off	Apartment	01-503 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
674	Negative	Off	Apartment	01-503 Kitchen	Window	Casing	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
675	Negative	Off	Apartment	01-503 Kitchen	Radiator	Cover	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
676	Negative	Off	Apartment	01-503 Kitchen	Door	Panel	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
677	Negative	Off	Apartment	01-503 Kitchen	Door	Casing	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
678	Negative	Off	Apartment	01-503 Kitchen	Door	Jamb	Wood	C	Center	Intact	0.0 mg/cm ²	Action Level
679	Negative	Off	Apartment	01-503 Kitchen	Door	Panel	Wood	C	Center	Intact	0.1 mg/cm ²	Action Level
680	Negative	Off	Apartment	01-503 Kitchen	Cabinet		Wood	D	Center	Intact	0.0 mg/cm ²	Action Level
681	Negative	Off	Apartment	01-503 Bathroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
682	Negative	Off	Apartment	01-503 Bathroom	Door	Casing	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
683	Negative	Off	Apartment	01-503 Bathroom	Cabinet		Metal	C	Center	Intact	-0.1 mg/cm ²	Action Level
684	Positive	Off	Apartment	01-503 Bathroom	Window	Casing	Metal	B	Right	Intact	1.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
685	Negative	Off	Apartment	01-503 Bathroom	Radiator	Cover	Metal	C	Center	Intact	0.0 mg/cm ²	Action Level
686	Negative	Off	Apartment	01-503 Bathroom	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
687	Negative	Off	Apartment	01-503 Bathrrom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
688	Negative	Off	Apartment	01-503 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
689	Negative	Off	Apartment	01-503 Bathroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
690	Negative	Off	Apartment	01-503 Bathroom	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
691	Negative	Off	Apartment	01-503 Bedroom	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
692	Negative	Off	Apartment	01-503 Bedroom	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
693	Negative	Off	Apartment	01-503 Bedroom	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
694	Negative	Off	Apartment	01-503 Bedroom	Wall		Drywall	D	UR	Intact	0.2 mg/cm ²	Action Level
695	Negative	Off	Apartment	01-503 Bedroom	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
696	Negative	Off	Apartment	01-503 Bedroom	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
697	Negative	Off	Apartment	01-503 Bedroom	Closet	Wall	Drywall	B	Right	Intact	-0.2 mg/cm ²	Action Level
698	Negative	Off	Apartment	01-503 Bedroom	Closet	Shelf Support	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
699	Negative	Off	Apartment	01-503 Bedroom	Door	Panel	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
700	Negative	Off	Apartment	01-503 Bedroom	Door	Jamb	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
701	Negative	Off	Apartment	01-503 Bedroom	Radiator	Cover	Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
702	Negative	Off	Apartment	01-503 Bedroom	Window	Casing	Metal	D	Right	Intact	0.8 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
703	Negative	Off	Apartment	01-503 LR	Window	Casing	Metal	D	Left	Intact	0.7 mg/cm ²	Action Level
704	Negative	Off	Apartment	01-503 LR	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
705	Negative	Off	Apartment	01-503 LR	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
706	Negative	Off	Apartment	01-503 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
707	Negative	Off	Apartment	01-503 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
708	Negative	Off	Apartment	01-503 LR	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
709	Negative	Off	Apartment	01-503 LR	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
710	Negative	Off	Apartment	01-503 LR	Wall		Drywall	B	UC	Intact	0.3 mg/cm ²	Action Level
711	Negative	Off	Apartment	01-503 LR	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
712	Negative	Off	Apartment	01-503 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
713	Negative	Off	Apartment	01-508 Kitchen	Ceiling		Concrete	B		Intact	0.4 mg/cm ²	Action Level
714	Negative	Off	Apartment	01-508 Kitchen	Closet	Ceiling	Concrete	B	Center	Intact	0.4 mg/cm ²	Action Level
715	Negative	Off	Apartment	01-508 Kitchen	Closet	Wall	Drywall	B	Center	Intact	0.1 mg/cm ²	Action Level
716	Negative	Off	Apartment	01-508 Kitchen	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
717	Negative	Off	Apartment	01-508 Kitchen	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
718	Negative	Off	Apartment	01-508 Kitchen	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
719	Negative	Off	Apartment	01-508 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
720	Negative	Off	Apartment	01-508 Kitchen	Closet	Wall	Drywall	B	Center	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
721	Negative	Off	Apartment	01-508 Kitchen	Closet	Shelf Support	Wood	B	Center	Intact	0.1 mg/cm ²	Action Level
722	Negative	Off	Apartment	01-508 Kitchen	Cabinet		Wood	C	Right	Intact	0.2 mg/cm ²	Action Level
723	Negative	Off	Apartment	01-508 Kitchen	Door	Panel	Wood	D	Right	Intact	0.0 mg/cm ²	Action Level
724	Negative	Off	Apartment	01-508 Kitchen	Door	Jamb	Wood	D	Right	Intact	0.0 mg/cm ²	Action Level
725	Negative	Off	Apartment	01-508 Kitchen	Door	Casing	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
726	Negative	Off	Apartment	01-508 Kitchen	Door	Panel	Metal	A	Right	Intact	0.0 mg/cm ²	Action Level
727	Negative	Off	Apartment	01-508 Kitchen	Radiator	Cover	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
728	Positive	Off	Apartment	01-508 Kitchen	Window	Casing	Metal	A	Left	Intact	1.1 mg/cm ²	Action Level
729	Positive	Off	Apartment	01-508 Bathroom	Window	Casing	Metal	A	Center	Intact	1.1 mg/cm ²	Action Level
730	Negative	Off	Apartment	01-508 Bathroom	Cabinet		Metal	B	Center	Intact	-0.1 mg/cm ²	Action Level
731	Negative	Off	Apartment	01-508 Bathroom	Radiator	Cover	Metal	B	Center	Intact	-0.1 mg/cm ²	Action Level
732	Negative	Off	Apartment	01-508 Bathroom	Door	Jamb	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
733	Negative	Off	Apartment	01-508 Bathroom	Door	Panel	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
734	Negative	Off	Apartment	01-508 Bathroom	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
735	Negative	Off	Apartment	01-508 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
736	Negative	Off	Apartment	01-508 Bathroom	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
737	Negative	Off	Apartment	01-508 Bathroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
738	Negative	Off	Apartment	01-508 Bathroom	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
739	Negative	Off	Apartment	01-508 Bedroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
740	Negative	Off	Apartment	01-508 Bedroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
741	Negative	Off	Apartment	01-508 Bedroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
742	Negative	Off	Apartment	01-508 Bedroom	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
743	Negative	Off	Apartment	01-508 Bedroom	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
744	Negative	Off	Apartment	01-508 Bedroom	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
745	Negative	Off	Apartment	01-508 Bedroom	Ceiling		Concrete	A		Intact	-0.1 mg/cm ²	Action Level
746	Negative	Off	Apartment	01-508 Bedroom	Closet	Shelf Support	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
747	Negative	Off	Apartment	01-508 Bedroom	Door	Casing	Wood	A	Left	Intact	-0.2 mg/cm ²	Action Level
748	Negative	Off	Apartment	01-508 Bedroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
749	Negative	Off	Apartment	01-508 Bedroom	Radiator	Cover	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
750	Negative	Off	Apartment	01-508 Bedroom	Window	Casing	Metal	C	Right	Intact	0.4 mg/cm ²	Action Level
751	Negative	Off	Apartment	01-508 LR	Window	Casing	Metal	C	Left	Intact	0.6 mg/cm ²	Action Level
752	Negative	Off	Apartment	01-508 LR	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
753	Negative	Off	Apartment	01-508 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
754	Negative	Off	Apartment	01-508 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
755	Negative	Off	Apartment	01-508 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
756	Negative	Off	Apartment	01-508 LR	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
757	Negative	Off	Apartment	01-508 LR	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
758	Negative	Off	Apartment	01-508 LR	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
759	Negative	Off	Apartment	01-508 LR	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
760	Negative	Off	Apartment	01-508 LR	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
761	Negative	Off	Apartment	01-404 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
762	Negative	Off	Apartment	01-404 Kitchen	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
763	Negative	Off	Apartment	01-404 Kitchen	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
764	Negative	Off	Apartment	01-404 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
765	Negative	Off	Apartment	01-404 Kitchen	Ceiling		Concrete	D		Intact	0.2 mg/cm ²	Action Level
766	Negative	Off	Apartment	01-404 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
767	Negative	Off	Apartment	01-404 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
768	Negative	Off	Apartment	01-404 Kitchen	Closet	Shelf Support	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
769	Negative	Off	Apartment	01-404 Kitchen	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
770	Negative	Off	Apartment	01-404 Kitchen	Door	Casing	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
771	Negative	Off	Apartment	01-404 Kitchen	Door	Casing	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
772	Negative	Off	Apartment	01-404 Kitchen	Door	Panel	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
773	Negative	Off	Apartment	01-404 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
774	Negative	Off	Apartment	01-404 Kitchen	Window	Casing	Metal	B	Right	Intact	0.6 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
775	Negative	Off	Apartment	01-404 Kitchen	Cabinet		Wood	C	Left	Intact	0.0 mg/cm ²	Action Level
776	Negative	Off	Apartment	01-404 LR	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
777	Negative	Off	Apartment	01-404 LR	Window	Casing	Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
778	Negative	Off	Apartment	01-404 LR	A/C Housing		Metal	D	Left	Intact	0.6 mg/cm ²	Action Level
779	Negative	Off	Apartment	01-404 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
780	Negative	Off	Apartment	01-404 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
781	Negative	Off	Apartment	01-404 LR	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
782	Negative	Off	Apartment	01-404 LR	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
783	Negative	Off	Apartment	01-404 LR	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
784	Negative	Off	Apartment	01-404 LR	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
785	Negative	Off	Apartment	01-404 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
786	Negative	Off	Apartment	01-404 Bedroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
787	Negative	Off	Apartment	01-404 Bedroom	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
788	Negative	Off	Apartment	01-404 Bedroom	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
789	Negative	Off	Apartment	01-404 Bedroom	Closet	Shelf Support	Wood	B	Right	Intact	0.2 mg/cm ²	Action Level
790	Negative	Off	Apartment	01-404 Bedroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
791	Negative	Off	Apartment	01-404 Bedroom	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
792	Negative	Off	Apartment	01-404 Bedroom	Window	Casing	Metal	C	Left	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
793	Negative	Off	Apartment	01-404 Bedroom	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
794	Negative	Off	Apartment	01-404 Bedroom	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
795	Negative	Off	Apartment	01-404 Bedroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
796	Negative	Off	Apartment	01-404 Bedroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
797	Negative	Off	Apartment	01-404 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
798	Negative	Off	Apartment	01-404 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
799	Negative	Off	Apartment	01-404 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
800	Negative	Off	Apartment	01-404 Bathroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
801	Negative	Off	Apartment	01-404 Bathroom	Wall		Drywall	D	UC	Intact	-0.3 mg/cm ²	Action Level
802	Negative	Off	Apartment	01-404 Bathroom	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
803	Negative	Off	Apartment	01-404 Bathroom	Window	Casing	Metal	B	Center	Intact	0.5 mg/cm ²	Action Level
804	Negative	Off	Apartment	01-404 Bathroom	Cabinet		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
805	Negative	Off	Apartment	01-404 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
806	Negative	Off	Apartment	01-404 Bathroom	Door	Panel	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level
807	Negative	Off	Apartment	01-404 Bathroom	Door	Jamb	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level
808	Negative	Off	Apartment	01-403 Kitchen	Door	Casing	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
809	Negative	Off	Apartment	01-403 Kitchen	Door	Panel	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
810	Negative	Off	Apartment	01-403 Kitchen	Door	Panel	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
811	Negative	Off	Apartment	01-403 Kitchen	Door	Casing	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
812	Negative	Off	Apartment	01-403 Kitchen	Radiator	Cover	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
813	Positive	Off	Apartment	01-403 Kitchen	Window	Casing	Metal	B	Left	Intact	1.2 mg/cm ²	Action Level
814	Negative	Off	Apartment	01-403 Kitchen	Wall		Drywall	B	UL	Intact	-0.2 mg/cm ²	Action Level
815	Negative	Off	Apartment	01-403 Kitchen	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
816	Negative	Off	Apartment	01-403 Kitchen	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
817	Negative	Off	Apartment	01-403 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
818	Negative	Off	Apartment	01-403 Kitchen	Ceiling		Drywall	A		Intact	0.3 mg/cm ²	Action Level
819	Negative	Off	Apartment	01-403 Bathroom	Ceiling		Drywall	A		Intact	0.3 mg/cm ²	Action Level
820	Negative	Off	Apartment	01-403 Bathroom	Wall		Drywall	A	UL	Intact	0.0 mg/cm ²	Action Level
821	Negative	Off	Apartment	01-403 Bathroom	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
822	Negative	Off	Apartment	01-403 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
823	Negative	Off	Apartment	01-403 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
824	Negative	Off	Apartment	01-403 Bathroom	Window	Casing	Metal	B	Center	Intact	0.3 mg/cm ²	Action Level
825	Negative	Off	Apartment	01-403 Bathroom	Cabinet		Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
826	Negative	Off	Apartment	01-403 Bathroom	Radiator	Cover	Metal	C	Center	Intact	0.2 mg/cm ²	Action Level
827	Negative	Off	Apartment	01-403 Bathroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
828	Negative	Off	Apartment	01-403 Bathroom	Door	Jamb	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
829	Negative	Off	Apartment	01-403 Bedroom	Door	Casing	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
830	Negative	Off	Apartment	01-403 Bedroom	Door	Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
831	Negative	Off	Apartment	01-403 Bedroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
832	Negative	Off	Apartment	01-403 Bedroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
833	Negative	Off	Apartment	01-403 Bedroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
834	Negative	Off	Apartment	01-403 Bedroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
835	Negative	Off	Apartment	01-403 Bedroom	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
836	Negative	Off	Apartment	01-403 Bedroom	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
837	Negative	Off	Apartment	01-403 Bedroom	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
838	Negative	Off	Apartment	01-403 Bedroom	Closet	Shelf Support	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
839	Negative	Off	Apartment	01-403 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
840	Positive	Off	Apartment	01-403 Bedroom	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level
841	Negative	Off	Apartment	01-403 LR	Window	Casing	Metal	D	Left	Intact	0.9 mg/cm ²	Action Level
842	Negative	Off	Apartment	01-403 LR	Radiator	Cover	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
843	Negative	Off	Apartment	01-403 LR	A/C Housing		Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
844	Negative	Off	Apartment	01-403 LR	A/C Housing		Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
845	Negative	Off	Apartment	01-403 LR	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
846	Negative	Off	Apartment	01-403 LR	Wall		Drywall	D	LR	Intact	0.3 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
847	Negative	Off	Apartment	01-403 LR	Wall		Drywall	C	LL	Intact	0.1 mg/cm ²	Action Level
848	Negative	Off	Apartment	01-403 LR	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
849	Negative	Off	Apartment	01-403 LR	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
850	Negative	Off	Apartment	01-403 LR	Ceiling		Concrete	D		Intact	0.0 mg/cm ²	Action Level
851	Negative	Off	Apartment	01-101 Entry	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
852	Negative	Off	Apartment	01-101 Entry	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
853	Negative	Off	Apartment	01-101 Entry	Wall		Drywall	B	UR	Intact	0.0 mg/cm ²	Action Level
854	Negative	Off	Apartment	01-101 Entry	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
855	Negative	Off	Apartment	01-101 Entry	Wall		Drywall	D	UR	Intact	0.0 mg/cm ²	Action Level
856	Negative	Off	Apartment	01-101 Entry	Closet	Wall	Drywall	C	Center	Intact	-0.1 mg/cm ²	Action Level
857	Negative	Off	Apartment	01-101 Entry	Closet	Ceiling	Concrete	C	Center	Intact	-0.1 mg/cm ²	Action Level
858	Negative	Off	Apartment	01-101 Entry	Door	Panel	Metal	B	Left	Intact	-0.1 mg/cm ²	Action Level
859	Negative	Off	Apartment	01-101 Entry	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
860	Negative	Off	Apartment	01-101 Entry	Radiator	Cover	Metal	A	Right	Intact	0.0 mg/cm ²	Action Level
861	Negative	Off	Apartment	01-101 Entry	Door	Panel	Wood	A	Center	Intact	0.0 mg/cm ²	Action Level
862	Negative	Off	Apartment	01-101 Entry	Door	Casing	Wood	A	Center	Intact	-0.1 mg/cm ²	Action Level
863	Negative	Off	Apartment	01-101 Entry	Closet	Shelf Support	Wood	C	Left	Intact	0.2 mg/cm ²	Action Level
864	Negative	Off	Apartment	01-101 Kitchen	Cabinet		Wood	D	Center	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
865	Negative	Off	Apartment	01-101 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
866	Negative	Off	Apartment	01-101 Kitchen	Window	Casing	Metal	B	Left	Intact	0.7 mg/cm ²	Action Level
867	Negative	Off	Apartment	01-101 Kitchen	Ceiling		Concrete	B		Intact	0.4 mg/cm ²	Action Level
868	Negative	Off	Apartment	01-101 Kitchen	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
869	Negative	Off	Apartment	01-101 Kitchen	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
870	Negative	Off	Apartment	01-101 Kitchen	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
871	Negative	Off	Apartment	01-101 Kitchen	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
872	Negative	Off	Apartment	01-101 LR	Wall		Drywall	A	UL	Intact	0.0 mg/cm ²	Action Level
873	Negative	Off	Apartment	01-101 LR	Wall		Drywall	B	UR	Intact	0.0 mg/cm ²	Action Level
874	Negative	Off	Apartment	01-101 LR	Wall		Drywall	C	UR	Intact	0.0 mg/cm ²	Action Level
875	Negative	Off	Apartment	01-101 LR	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
876	Negative	Off	Apartment	01-101 LR	Ceiling		Concrete	D		Intact	0.3 mg/cm ²	Action Level
877	Negative	Off	Apartment	01-101 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
878	Negative	Off	Apartment	01-101 LR	A/C Housing		Metal	D	Right	Intact	0.3 mg/cm ²	Action Level
879	Negative	Off	Apartment	01-101 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
880	Negative	Off	Apartment	01-101 LR	Radiator	Cover	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
881	Negative	Off	Apartment	01-101 LR	Window	Sill	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
882	Negative	Off	Apartment	01-101 Bed 1	Window	Sill	Metal	D	Right	Intact	0.5 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
883	Negative	Off	Apartment	01-101 Bed 1	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
884	Negative	Off	Apartment	01-101 Bed 1	Closet	Shelf Support Panel	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
885	Negative	Off	Apartment	01-101 Bed 1	Door	Jamb	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
886	Negative	Off	Apartment	01-101 Bed 1	Door	Jamb	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
887	Negative	Off	Apartment	01-101 Bed 1	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
888	Negative	Off	Apartment	01-101 Bed 1	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
889	Negative	Off	Apartment	01-101 Bed 1	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
890	Negative	Off	Apartment	01-101 Bed 1	Wall		Drywall	A	UR	Intact	0.0 mg/cm ²	Action Level
891	Negative	Off	Apartment	01-101 Bed 1	Closet	Wall	Drywall	B	Right	Intact	0.0 mg/cm ²	Action Level
892	Negative	Off	Apartment	01-101 Bed 1	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
893	Negative	Off	Apartment	01-101 Bed 2	Closet	Ceiling	Concrete	B	Left	Intact	0.1 mg/cm ²	Action Level
894	Negative	Off	Apartment	01-101 Bed 2	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
895	Negative	Off	Apartment	01-101 Bed 2	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
896	Negative	Off	Apartment	01-101 Bed 2	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
897	Negative	Off	Apartment	01-101 Bed 2	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
898	Negative	Off	Apartment	01-101 Bed 2	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
899	Negative	Off	Apartment	01-101 Bed 2	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
900	Negative	Off	Apartment	01-101 Bed 2	Window	Casing	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
901	Negative	Off	Apartment	01-101 Bed 2	A/C Housing		Metal	D	Right	Intact	0.4 mg/cm ²	Action Level
902	Negative	Off	Apartment	01-101 Bed 2	A/C Housing		Meta	D	Right	Intact	0.3 mg/cm ²	Action Level
903	Negative	Off	Apartment	01-101 Bed 2	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
904	Negative	Off	Apartment	01-101 Bed 2	Closet	Shelf Support Panel	Wood	B	Left	Intact	0.2 mg/cm ²	Action Level
905	Negative	Off	Apartment	01-101 Bed 2	Door		Wood	B	Right	Intact	0.2 mg/cm ²	Action Level
906	Negative	Off	Apartment	01-101 Bed 2	Door	Jamb	Wood	B	Right	Intact	0.2 mg/cm ²	Action Level
907	Negative	Off	Apartment	01-101 Bathroom	Door	Casing	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
908	Negative	Off	Apartment	01-101 Bathroom	Door	Panel	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
909	Negative	Off	Apartment	01-101 Bathroom	Cabinet		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
910	Negative	Off	Apartment	01-101 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
911	Positive	Off	Apartment	01-101 Bathroom	Window	Casing	Metal	B	Center	Intact	1.1 mg/cm ²	Action Level
912	Negative	Off	Apartment	01-101 Bathroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
913	Negative	Off	Apartment	01-101 Bathroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
914	Negative	Off	Apartment	01-101 Bathroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
915	Negative	Off	Apartment	01-101 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
916	Negative	Off	Apartment	01-101 Bathroom	Wall		Drywall	A	UR	Intact	0.0 mg/cm ²	Action Level
917	Negative	Off	Apartment	01-304 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
918	Negative	Off	Apartment	01-304 Kitchen	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
919	Negative	Off	Apartment	01-304 Kitchen	Wall		Drywall	C	UR	Intact	0.0 mg/cm ²	Action Level
920	Negative	Off	Apartment	01-304 Kitchen	Wall		Drywall	D	UL	Intact	0.0 mg/cm ²	Action Level
921	Negative	Off	Apartment	01-304 Kitchen	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
922	Negative	Off	Apartment	01-304 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
923	Negative	Off	Apartment	01-304 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
924	Negative	Off	Apartment	01-304 Kitchen	Window	Casing	Metal	B	Center	Intact	0.5 mg/cm ²	Action Level
925	Negative	Off	Apartment	01-304 Kitchen	Radiator	Cover	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
926	Negative	Off	Apartment	01-304 Kitchen	Door	Jamb	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
927	Negative	Off	Apartment	01-304 Kitchen	Door	Panel	Metal	B	Left	Intact	0.0 mg/cm ²	Action Level
928	Negative	Off	Apartment	01-304 Kitchen	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
929	Negative	Off	Apartment	01-304 Kitchen	Door	Casing	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
930	Negative	Off	Apartment	01-304 Kitchen	Cabinet		Wood	D	Center	Intact	0.0 mg/cm ²	Action Level
931	Negative	Off	Apartment	01-304 LR	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
932	Negative	Off	Apartment	01-304 LR	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level
933	Negative	Off	Apartment	01-304 LR	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
934	Negative	Off	Apartment	01-304 LR	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
935	Negative	Off	Apartment	01-304 LR	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
936	Negative	Off	Apartment	01-304 LR	A/C Housing		Metal	D	Center	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
937	Negative	Off	Apartment	01-304 LR	Radiator	Cover	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
938	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.2 mg/cm ²	Action Level
939	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.2 mg/cm ²	Action Level
940	Positive	Off	Apartment	01-304 LR	Window	Casing	Metal	D	Left	Intact	1.1 mg/cm ²	Action Level
941	Positive	Off	Apartment	01-304 Bedroom	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level
942	Negative	Off	Apartment	01-304 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
943	Negative	Off	Apartment	01-304 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
944	Negative	Off	Apartment	01-304 Bedroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
945	Negative	Off	Apartment	01-304 Bedroom	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
946	Negative	Off	Apartment	01-304 Bedroom	Wall		Drywall	A	UL	Intact	0.0 mg/cm ²	Action Level
947	Negative	Off	Apartment	01-304 Bedroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
948	Negative	Off	Apartment	01-304 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.3 mg/cm ²	Action Level
949	Negative	Off	Apartment	01-304 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.1 mg/cm ²	Action Level
950	Negative	Off	Apartment	01-304 Bedroom	Closet	Shelf Support	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
951	Negative	Off	Apartment	01-304 Bedroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
952	Negative	Off	Apartment	01-304 Bedroom	Door	Jamb	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level
953	Negative	Off	Apartment	01-304 Bathroom	Door	Casing	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
954	Negative	Off	Apartment	01-304 Bathroom	Door	Panel	Wood	C	Right	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
955	Negative	Off	Apartment	01-304 Bathroom	Cabinet		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
956	Negative	Off	Apartment	01-304 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
957	Positive	Off	Apartment	01-304 Bathroom	Window	Casing	Metal	B	Center	Intact	1.0 mg/cm ²	Action Level
958	Negative	Off	Apartment	01-304 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
959	Negative	Off	Apartment	01-304 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
960	Negative	Off	Apartment	01-304 Bathroom	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
961	Negative	Off	Apartment	01-304 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
962	Negative	Off	Apartment	01-304 Bathroom	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
963		Off	Calibration								0.0 mg/cm ²	Action Level
964		Off	Calibration								0.0 mg/cm ²	Action Level
965		Off	Calibration								0.0 mg/cm ²	Action Level
966		Off	Calibration								1.0 mg/cm ²	Action Level
967		Off	Calibration								1.0 mg/cm ²	Action Level
968		Off	Calibration								0.9 mg/cm ²	Action Level
969		Off	Calibration								1.1 mg/cm ²	Action Level
970		Off	Calibration								1.0 mg/cm ²	Action Level
971		Off	Calibration								1.1 mg/cm ²	Action Level
972		Off	Calibration								0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
973		Off	Calibration								0.0 mg/cm ²	Action Level
974		Off	Calibration								0.0 mg/cm ²	Action Level
975	Negative	Off	Exterior	Play Area	Play	Support	Metal	A	Center	Intact	0.2 mg/cm ²	Action Level
976	Negative	Off	Exterior	Play Area	Play	Support	Metal	B	Center	Intact	0.2 mg/cm ²	Action Level
977	Negative	Off	Exterior	Play Area	Play	Support	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
978	Negative	Off	Exterior	Play Area	Play	Support	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
979	Negative	Off	Exterior	Play Area	Railing		Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
980	Negative	Off	Exterior	Play Area	Railing		Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
981	Negative	Off	Exterior	Play Area	Railing		Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
982	Negative	Off	Exterior	Play Area	Railing		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
983	Negative	Off	Exterior	Play Area	Swing	Supports	Metal	B	Center	Intact	0.2 mg/cm ²	Action Level
984	Negative	Off	Exterior	Play Area	Swing	Supports	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
985	Negative	Off	Exterior	Play Area	Swing	Supports	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
986	Negative	Off	Exterior	Play Area	Swing	Supports	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
987	Negative	Off	Exterior	1342	Door	Panel	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
988	Negative	Off	Exterior	1342	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
989	Negative	Off	Exterior	1342	Door	Casing	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
990	Negative	Off	Exterior	1342	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
991	Positive	Off	Exterior	1342	Lintel		Metal	A	Center	Intact	5.5 mg/cm ²	Action Level
992	Positive	Off	Exterior	1342	Lintel		Metal	B	Center	Intact	5.6 mg/cm ²	Action Level
993	Positive	Off	Exterior	1342	Lintel		Metal	C	Center	Intact	5.7 mg/cm ²	Action Level
994	Positive	Off	Exterior	1342	Lintel		Metal	D	Center	Intact	6.0 mg/cm ²	Action Level
995	Positive	Off	Exterior	1342	Hall Fence		Metal	D	Center	Intact	5.9 mg/cm ²	Action Level
996	Positive	Off	Exterior	1342	Hall Fence		Metal	C	Center	Intact	5.9 mg/cm ²	Action Level
997	Positive	Off	Exterior	1342	Hall Fence		Metal	B	Center	Intact	5.8 mg/cm ²	Action Level
998	Positive	Off	Exterior	1342	Hall Fence		Metal	A	Center	Intact	6.0 mg/cm ²	Action Level
999	Negative	Off	Exterior	1342	Drain Pipe		Metal	A	Center	Intact	0.2 mg/cm ²	Action Level
1000	Negative	Off	Exterior	1342	Drain Pipe		Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
1001	Negative	Off	Exterior	1342	Wall		Concrete	A	UL	Intact	0.2 mg/cm ²	Action Level
1002	Negative	Off	Exterior	1342	Wall		Concrete	B	UR	Intact	0.0 mg/cm ²	Action Level
1003	Negative	Off	Exterior	1342	Wall		Concrete	C	UR	Intact	0.1 mg/cm ²	Action Level
1004	Negative	Off	Exterior	1342	Wall		Concrete	D	UC	Intact	0.1 mg/cm ²	Action Level
1005	Negative	Off	Common	1342 NE Stair 1	Floor		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1006	Negative	Off	Common	1342 NE Stair 1	Stair		Concrete	A	Center	Intact	0.3 mg/cm ²	Action Level
1007	Negative	Off	Common	1342 NE Stair 1	Ceiling		Concrete	A		Intact	0.3 mg/cm ²	Action Level
1008	Positive	Off	Common	1342 NE Stair 1	Support	Beam	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1009	Positive	Off	Common	1342 NE Stair 1	Support	Column	Concrete	A	Right	Intact	1.4 mg/cm ²	Action Level
1010	Positive	Off	Common	1342 NE Stair 1	Window	Sill	Concrete	C	Left	Intact	1.5 mg/cm ²	Action Level
1011	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	C	UC	Intact	1.3 mg/cm ²	Action Level
1012	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	D	UL	Intact	1.7 mg/cm ²	Action Level
1013	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	B	UC	Intact	1.2 mg/cm ²	Action Level
1014	Positive	Off	Common	1342 NE Stair 1	Wall		Brick	A	UC	Intact	1.3 mg/cm ²	Action Level
1015	Negative	Off	Common	1342 NE Stair 1	Railing		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1016	Negative	Off	Common	1342 NE Stair 1	Door	Panel	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1017	Negative	Off	Common	1342 NE Stair 1	Door	Panel	Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1018	Negative	Off	Common	1342 NE Stair 1	Door	Casing	Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1019	Negative	Off	Common	1342 NE Stair 1	Door	Casing	Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
1020	Negative	Off	Common	1342 NE Stair 1	Door	Panel	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1021	Negative	Off	Common	1342 S Stair 1	Door	Panel	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1022	Negative	Off	Common	1342 S Stair 1	Railing		Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1023	Positive	Off	Common	1342 S Stair 1	Wall		Brick	B	UC	Intact	1.8 mg/cm ²	Action Level
1024	Positive	Off	Common	1342 S Stair 1	Wall		Brick	C	UL	Intact	1.9 mg/cm ²	Action Level
1025	Positive	Off	Common	1342 S Stair 1	Wall		Brick	D	UR	Intact	1.9 mg/cm ²	Action Level
1026	Positive	Off	Common	1342 S Stair 1	Wall		Brick	A	UC	Intact	1.9 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1027	Positive	Off	Common	1342 S Stair 1	Support	Column	Concrete	B	Right	Intact	2.0 mg/cm ²	Action Level
1028	Positive	Off	Common	1342 S Stair 1	Support	Beam	Concrete	B	Right	Intact	1.8 mg/cm ²	Action Level
1029	Positive	Off	Common	1342 S Stair 1	Window	Sill	Concrete	D	Left	Intact	2.0 mg/cm ²	Action Level
1030	Negative	Off	Common	1342 S Stair 1	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1031	Negative	Off	Common	1342 S Stair 1	Floor		Concrete	C		Intact	0.1 mg/cm ²	Action Level
1032	Negative	Off	Common	1342 S Stair 1	Stairs		Concrete	B	Center	Intact	0.2 mg/cm ²	Action Level
1033	Negative	Off	Common	1342 S Stair 6	Stairs		Concrete	B	Center	Intact	0.2 mg/cm ²	Action Level
1034	Negative	Off	Common	1342 S Stair 6	Floor		Concrete	C	Center	Intact	0.1 mg/cm ²	Action Level
1035	Negative	Off	Common	1342 S Stair 6	Ceiling		Concrete	C	Center	Intact	0.3 mg/cm ²	Action Level
1036	Positive	Off	Common	1342 S Stair 6	Window	Sill	Concrete	D	Left	Intact	2.1 mg/cm ²	Action Level
1037	Positive	Off	Common	1342 S Stair 6	Support	Column	Concrete	C	Left	Intact	2.0 mg/cm ²	Action Level
1038	Positive	Off	Common	1342 S Stair 6	Support	Beam	Concrete	C	Left	Intact	2.4 mg/cm ²	Action Level
1039	Positive	Off	Common	1342 S Stair 6	Wall		Brick	C	LC	Intact	2.7 mg/cm ²	Action Level
1040	Positive	Off	Common	1342 S Stair 6	Wall		Brick	D	LL	Intact	2.1 mg/cm ²	Action Level
1041	Positive	Off	Common	1342 S Stair 6	Wall		Brick	B	LC	Intact	2.1 mg/cm ²	Action Level
1042	Positive	Off	Common	1342 S Stair 6	Wall		Brick	C	LC	Intact	2.3 mg/cm ²	Action Level
1043	Negative	Off	Common	1342 S Stair 6	Railing		Metal	B	Center	Intact	0.0 mg/cm ²	Action Level
1044	Negative	Off	Common	1342 S Stair 6	Door	Panel	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1045	Negative	Off	Common	1342 S Stair 6	Door	Casing	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1046	Negative	Off	Common	1342 S Stair 6	Door	Casing	Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1047	Negative	Off	Common	1342 NE Stair 6	Door	Panel	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1048	Negative	Off	Common	1342 NE Stair 6	Railing		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1049	Negative	Off	Common	1342 NE Stair 6	Floor		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1050	Negative	Off	Common	1342 NE Stair 6	Stair		Concrete	A	Center	Intact	0.1 mg/cm ²	Action Level
1051	Negative	Off	Common	1342 NE Stair 6	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1052	Positive	Off	Common	1342 NE Stair 6	Support	Column	Concrete	B	Left	Intact	1.2 mg/cm ²	Action Level
1053	Positive	Off	Common	1342 NE Stair 6	Support	Beam	Concrete	B	Left	Intact	1.0 mg/cm ²	Action Level
1054	Positive	Off	Common	1342 NE Stair 6	Window	Sill	Concrete	C	Left	Intact	1.1 mg/cm ²	Action Level
1055	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	C	UC	Intact	1.1 mg/cm ²	Action Level
1056	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	D	LL	Intact	1.1 mg/cm ²	Action Level
1057	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	A	UC	Intact	2.6 mg/cm ²	Action Level
1058	Positive	Off	Common	1342 NE Stair 6	Wall		Brick	B	UC	Intact	1.8 mg/cm ²	Action Level
1059	Negative	Off	Common	1342 7 Elevator	Wall		Concrete	C	LL	Intact	-0.2 mg/cm ²	Action Level
1060	Negative	Off	Common	1342 7 Elevator	Support	Beam	Concrete	C	Left	Intact	0.1 mg/cm ²	Action Level
1061	Negative	Off	Common	1342 7 Elevator	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
1062	Positive	Off	Common	1342 7 Elevator	Window	Casing	Metal	C	Center	Intact	1.7 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1063	Negative	Off	Common	1342 7 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.3 mg/cm ²	Action Level
1064	Negative	Off	Common	1342 7 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.7 mg/cm ²	Action Level
1065	Negative	Off	Common	1342 7 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.6 mg/cm ²	Action Level
1066	Negative	Off	Common	1342 7 Elevator	Door	Panel	Metal	B	Left	Intact	0.6 mg/cm ²	Action Level
1067	Negative	Off	Common	1342 7 Elevator	Door	Casing	Metal	B	Left	Intact	-0.2 mg/cm ²	Action Level
1068	Negative	Off	Common	1342 7 Elevator	Wall		Drywal	A	UC	Intact	0.2 mg/cm ²	Action Level
1069	Negative	Off	Common	1342 7 Elevator	Wall		Drywall	B	LR	Intact	0.2 mg/cm ²	Action Level
1070	Negative	Off	Common	1342 7 Elevator	Wall		Drywall	D	LL	Intact	0.3 mg/cm ²	Action Level
1071	Negative	Off	Common	1342 7 Elevator	Wall		Glazed Tile	D	LR	Intact	0.1 mg/cm ²	Action Level
1072	Negative	Off	Common	1342 7 Elevator	Wall		Glazed Tile	B	LL	Intact	0.0 mg/cm ²	Action Level
1073	Negative	Off	Common	1342 6 Elevator	Wall		Drywall	A	LL	Intact	0.2 mg/cm ²	Action Level
1074	Negative	Off	Common	1342 6 Elevator	Wall		Drywall	B	LR	Intact	0.1 mg/cm ²	Action Level
1075	Negative	Off	Common	1342 6 Elevator	Wall		Drywall	D	LL	Intact	0.2 mg/cm ²	Action Level
1076	Negative	Off	Common	1342 6 Elevator	Wall		Concrete	C	LL	Intact	-0.3 mg/cm ²	Action Level
1077	Negative	Off	Common	1342 6 Elevator	Support	Beam	Concrete	C	Left	Intact	-0.2 mg/cm ²	Action Level
1078	Negative	Off	Common	1342 6 Elevator	Ceiling		Concrete	C		Intact	-0.3 mg/cm ²	Action Level
1079	Negative	Off	Common	1342 6 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
1080	Positive	Off	Common	1342 6 Elevator	Window	Casing	Metal	C	Center	Intact	2.5 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1081	Negative	Off	Common	1342 6 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.5 mg/cm ²	Action Level
1082	Negative	Off	Common	1342 6 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.4 mg/cm ²	Action Level
1083	Negative	Off	Common	1342 6 Elevator	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1084	Negative	Off	Common	1342 6 Elevator	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1085	Negative	Off	Common	1342 5 Elevator	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1086	Negative	Off	Common	1342 5 Elevator	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1087	Negative	Off	Common	1342 5 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.3 mg/cm ²	Action Level
1088	Negative	Off	Common	1342 5 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.6 mg/cm ²	Action Level
1089	Negative	Off	Common	1342 5 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
1090	Positive	Off	Common	1342 5 Elevator	Window	Casing	Metal	C	Center	Intact	3.5 mg/cm ²	Action Level
1091	Negative	Off	Common	1342 5 Elevator	Pipe		Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1092	Negative	Off	Common	1342 5 Elevator	Wall		Concrete	C	LL	Intact	0.0 mg/cm ²	Action Level
1093	Negative	Off	Common	1342 5 Elevator	Support	Beam	Concrete	C	Left	Intact	-0.2 mg/cm ²	Action Level
1094	Negative	Off	Common	1342 5 Elevator	Ceiling		Concrete	C		Intact	-0.2 mg/cm ²	Action Level
1095	Negative	Off	Common	1342 5 Elevator	Wall		Drywall	D	LL	Intact	0.1 mg/cm ²	Action Level
1096	Negative	Off	Common	1342 5 Elevator	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1097	Negative	Off	Common	1342 5 Elevator	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
1098	Negative	Off	Common	1342 4 Elevator	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1099	Negative	Off	Common	1342 4 Elevator	Wall		Drywall	B	UR	Intact	0.2 mg/cm ²	Action Level
1100	Negative	Off	Common	1342 4 Elevator	Wall		Drywall	D	LL	Intact	0.2 mg/cm ²	Action Level
1101	Negative	Off	Common	1342 4 Elevator	Wall		Concrete	C	LL	Intact	0.0 mg/cm ²	Action Level
1102	Negative	Off	Common	1342 4 Elevator	Support	Beam	Concrete	C	Left	Intact	0.0 mg/cm ²	Action Level
1103	Negative	Off	Common	1342 4 Elevator	Ceiling		Concrete	C		Intact	-0.1 mg/cm ²	Action Level
1104	Negative	Off	Common	1342 4 Elevator	Pipe		Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1105	Negative	Off	Common	1342 4 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.2 mg/cm ²	Action Level
1106	Positive	Off	Common	1342 4 Elevator	Window	Casing	Metal	C	Center	Intact	1.9 mg/cm ²	Action Level
1107	Negative	Off	Common	1342 4 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
1108	Negative	Off	Common	1342 4 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.5 mg/cm ²	Action Level
1109	Negative	Off	Common	1342 4 Elevator	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1110	Negative	Off	Common	1342 4 Elevator	Door	Casing	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1111	Negative	Off	Common	1342 3 Elevator	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1112	Negative	Off	Common	1342 3 Elevator	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1113	Negative	Off	Common	1342 3 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.5 mg/cm ²	Action Level
1114	Negative	Off	Common	1342 3 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.4 mg/cm ²	Action Level
1115	Positive	Off	Common	1342 3 Elevator	Window	Casing	Metal	C	Center	Intact	1.4 mg/cm ²	Action Level
1116	Negative	Off	Common	1342 3 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1117	Negative	Off	Common	1342 3 Elevator	Pipe		Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1118	Negative	Off	Common	1342 3 Elevator	Wall		Concrete	C	LL	Intact	-0.1 mg/cm ²	Action Level
1119	Negative	Off	Common	1342 3 Elevator	Support	Beam	Concrete	C	Left	Intact	-0.1 mg/cm ²	Action Level
1120	Negative	Off	Common	1342 3 Elevator	Ceiling		Concrete	C		Intact	-0.2 mg/cm ²	Action Level
1121	Negative	Off	Common	1342 3 Elevator	Wall		Drywall	B	UR	Intact	-0.2 mg/cm ²	Action Level
1122	Negative	Off	Common	1342 3 Elevator	Wall		Drywall	D	LL	Intact	0.2 mg/cm ²	Action Level
1123	Negative	Off	Common	1342 3 Elevator	Wall		Drywall	A	LL	Intact	0.2 mg/cm ²	Action Level
1124	Negative	Off	Common	1342 2 Elevator	Wall		Drywall	A	LL	Intact	0.1 mg/cm ²	Action Level
1125	Negative	Off	Common	1342 2 Elevator	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1126	Negative	Off	Common	1342 2 Elevator	Wall		Drywall	D	LL	Intact	0.0 mg/cm ²	Action Level
1127	Negative	Off	Common	1342 2 Elevator	Wall		Concrete	C	LL	Intact	0.1 mg/cm ²	Action Level
1128	Negative	Off	Common	1342 2 Elevator	Support	Beam	Concrete	C	Left	Intact	-0.1 mg/cm ²	Action Level
1129	Negative	Off	Common	1342 2 Elevator	Ceiling		Concrete	C		Intact	-0.2 mg/cm ²	Action Level
1130	Negative	Off	Common	1342 2 Elevator	Radiator	Cover	Metal	C	Right	Intact	0.3 mg/cm ²	Action Level
1131	Positive	Off	Common	1342 2 Elevator	Window	Casing	Metal	C	Left	Intact	2.5 mg/cm ²	Action Level
1132	Negative	Off	Common	1342 2 Elevator	Pipe		Metal	B	Right	Intact	0.2 mg/cm ²	Action Level
1133	Negative	Off	Common	1342 2 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
1134	Negative	Off	Common	1342 2 Elevator	Elevator	Door Casing	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1135	Negative	Off	Common	1342 2 Elevator	Door	Panel	Metal	A	Left	Intact	0.3 mg/cm ²	Action Level
1136	Negative	Off	Common	1342 2 Elevator	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1137	Negative	Off	Common	1342 1 Elevator	Door	Casing	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1138	Negative	Off	Common	1342 1 Elevator	Door	Panel	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1139	Negative	Off	Common	1342 1 Elevator	Elevator	Door Casing	Brick	B	Left	Intact	0.1 mg/cm ²	Action Level
1140	Negative	Off	Common	1342 1 Elevator	Elevator	Door Casing	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
1141	Negative	Off	Common	1342 1 Elevator	Pipe		Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
1142	Negative	Off	Common	1342 1 Elevator	Window	Casing	Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
1143	Negative	Off	Common	1342 1 Elevator	Radiator	Cover	Metal	C	Center	Intact	0.4 mg/cm ²	Action Level
1144	Negative	Off	Common	1342 1 Elevator	Window	Sill	Metal	C	Center	Intact	0.4 mg/cm ²	Action Level
1145	Negative	Off	Common	1342 1 Elevator	Wall		Drywall	C	LR	Intact	0.2 mg/cm ²	Action Level
1146	Negative	Off	Common	1342 1 Elevator	Wall		Drywall	B	LR	Intact	0.1 mg/cm ²	Action Level
1147	Negative	Off	Common	1342 1 Elevator	Support	Beam	Concrete	D	Center	Intact	0.4 mg/cm ²	Action Level
1148	Negative	Off	Common	1342 1 Elevator	Ceiling		Concrete	D		Intact	0.3 mg/cm ²	Action Level
1149	Negative	Off	Common	1342 1 Elevator	Wall		Glazed Tile	D	LL	Intact	0.0 mg/cm ²	Action Level
1150	Negative	Off	Common	1342 1 Elevator	Wall		Glazed Tile	B	LL	Intact	-0.1 mg/cm ²	Action Level
1151	Negative	Off	Common	1314 1 Elevator	Wall		Glazed Tile	B	LL	Intact	0.0 mg/cm ²	Action Level
1152	Negative	Off	Common	1314 1 Elevator	Wall		Glazed Tile	D	LL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1153	Negative	Off	Common	1314 7 Elevator	Wall		Glazed Tile	D	LL	Intact	0.0 mg/cm ²	Action Level
1154	Negative	Off	Common	1314 7 Elevator	Wall		Glazed Tile	B	LL	Intact	0.0 mg/cm ²	Action Level
1155	Negative	Off	Exterior	1342	Bollard		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1156		Off	Calibration								-0.1 mg/cm ²	Action Level
1157		Off	Calibration								0.0 mg/cm ²	Action Level
1158		Off	Calibration								0.1 mg/cm ²	Action Level
1159		Off	Calibration								1.0 mg/cm ²	Action Level
1160		Off	Calibration								1.0 mg/cm ²	Action Level
1161		Off	Calibration								1.1 mg/cm ²	Action Level
1162	Negative	Off	Common	Main Office	Radiator	Cover	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1163	Negative	Off	Common	Main Office	Window	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1164	Negative	Off	Common	Main Office	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1165	Negative	Off	Common	Main Office	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1166	Negative	Off	Common	Main Office	Ceiling		Concrete	A		Intact	0.4 mg/cm ²	Action Level
1167	Negative	Off	Common	Main Office	Wall		Concrete	A	LL	Intact	0.1 mg/cm ²	Action Level
1168	Negative	Off	Common	Main Office	Wall		Drywall	B	LL	Intact	0.1 mg/cm ²	Action Level
1169	Negative	Off	Common	Main Office	Wall		Drwyall	C	LC	Intact	0.1 mg/cm ²	Action Level
1170	Negative	Off	Common	Main Office	Wall		Drywall	D	LL	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1171	Negative	Off	Common	Main Office	Door	Panel	Wood	D	Center	Intact	0.0 mg/cm ²	Action Level
1172	Negative	Off	Common	Main Office	Door	Jamb	Wood	C	Center	Intact	-0.1 mg/cm ²	Action Level
1173	Negative	Off	Common	Main Office	Door	Casing	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1174	Negative	Off	Common	Main Office Toilet	Door	Panel	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1175	Positive	Off	Common	Main Office Toilet	Window	Casing	Metal	A	Center	Intact	1.0 mg/cm ²	Action Level
1176	Negative	Off	Common	Main Office Toilet	Cabinet		Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
1177	Negative	Off	Common	Main Office Toilet	Radiator	Cover	Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
1178	Negative	Off	Common	Main Office Toilet	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
1179	Negative	Off	Common	Main Office Toilet	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
1180	Negative	Off	Common	Main Office Toilet	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
1181	Negative	Off	Common	Main Office Toilet	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1182	Negative	Off	Common	Main Office Toilet	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1183	Negative	Off	Apartment	02-705 Entry	Door	Panel	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1184	Negative	Off	Apartment	02-705 Entry	Door	Casing	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1185	Negative	Off	Apartment	02-705 Entry	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1186	Negative	Off	Apartment	02-705 Entry	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
1187	Negative	Off	Apartment	02-705 Entry	Wall		Drywall	C	UL	Intact	0.0 mg/cm ²	Action Level
1188	Negative	Off	Apartment	02-705 Entry	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1189	Negative	Off	Apartment	02-705 Entry	Wall		Drywall	A	LC	Intact	0.1 mg/cm ²	Action Level
1190	Negative	Off	Apartment	02-705 Entry	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
1191	Negative	Off	Apartment	02-705 Entry	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
1192	Negative	Off	Apartment	02-705 Entry	Closet	Ceiling	Concrete	A	Right	Intact	0.1 mg/cm ²	Action Level
1193	Negative	Off	Apartment	02-705 Entry	Closet	Shelf Support Panel	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
1194	Negative	Off	Apartment	02-705 Entry	Door		Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
1195	Negative	Off	Apartment	02-705 Entry	Door	Casing	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
1196	Negative	Off	Apartment	02-705 Bathroom	Door	Jamb	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1197	Negative	Off	Apartment	02-705 Bathroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1198	Negative	Off	Apartment	02-705 Bathroom	Cabinet		Metal	C	Center	Intact	0.0 mg/cm ²	Action Level
1199	Negative	Off	Apartment	02-705 Bathroom	Radiator	Cover	Metal	C	Center	Intact	0.0 mg/cm ²	Action Level
1200	Negative	Off	Apartment	02-705 Bathroom	Window	Casing	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1201	Negative	Off	Apartment	02-705 Bathroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1202	Negative	Off	Apartment	02-705 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1203	Negative	Off	Apartment	02-705 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1204	Negative	Off	Apartment	02-705 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1205	Negative	Off	Apartment	02-705 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1206	Negative	Off	Apartment	02-705 Bed 1	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1207	Negative	Off	Apartment	02-705 Bed 1	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1208	Negative	Off	Apartment	02-705 Bed 1	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1209	Negative	Off	Apartment	02-705 Bed 1	Wall		Drywall	D	UC	Intact	0.3 mg/cm ²	Action Level
1210	Negative	Off	Apartment	02-705 Bed 1	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
1211	Negative	Off	Apartment	02-705 Bed 1	Closet	Ceiling	Concrete	B	Right	Intact	0.1 mg/cm ²	Action Level
1212	Negative	Off	Apartment	02-705 Bed 1	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1213	Negative	Off	Apartment	02-705 Bed 1	Closet	Shelf Support	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1214	Negative	Off	Apartment	02-705 Bed 1	Door	Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
1215	Negative	Off	Apartment	02-705 Bed 1	Door	Jamb	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
1216	Negative	Off	Apartment	02-705 Bed 1	A/C Housing		Metal	B	Left	Intact	0.0 mg/cm ²	Action Level
1217	Negative	Off	Apartment	02-705 Bed 1	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1218	Negative	Off	Apartment	02-705 Bed 1	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1219	Negative	Off	Apartment	02-705 Bed 1	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
1220	Negative	Off	Apartment	02-705 Bed 1	Window	Casing	Metal	D	Right	Intact	-0.4 mg/cm ²	Action Level
1221	Negative	Off	Apartment	02-705 Bed 2	Window	Casing	Metal	D	Left	Intact	-0.3 mg/cm ²	Action Level
1222	Negative	Off	Apartment	02-705 Bed 2	Radiator	Cover	Metal	D	Left	Intact	-0.3 mg/cm ²	Action Level
1223	Negative	Off	Apartment	02-705 Bed 2	Door	Panel	Wood	B	Right	Intact	-0.3 mg/cm ²	Action Level
1224	Negative	Off	Apartment	02-705 Bed 2	Door	Jamb	Wood	B	Right	Intact	-0.3 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1225	Negative	Off	Apartment	02-705 Bed 2	Closet	Shelf Support	Wood	B	Left	Intact	-0.4 mg/cm ²	Action Level
1226	Negative	Off	Apartment	02-705 Bed 2	Closet	Ceiling	Concrete	B	Left	Intact	-0.3 mg/cm ²	Action Level
1227	Negative	Off	Apartment	02-705 Bed 2	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1228	Negative	Off	Apartment	02-705 Bed 2	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
1229	Negative	Off	Apartment	02-705 Bed 2	Wall		Drywall	B	LL	Intact	0.1 mg/cm ²	Action Level
1230	Negative	Off	Apartment	02-705 Bed 2	Wall		Drywall	C	LL	Intact	0.1 mg/cm ²	Action Level
1231	Negative	Off	Apartment	02-705 Bed 2	Wall		Drywall	D	LC	Intact	-0.1 mg/cm ²	Action Level
1232	Negative	Off	Apartment	02-705 Bed 2	Wall		Drywall	A	LC	Intact	0.0 mg/cm ²	Action Level
1233	Negative	Off	Apartment	02-705 LR	Wall		Drywall	A	UC	Intact	-0.1 mg/cm ²	Action Level
1234	Negative	Off	Apartment	02-705 LR	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
1235	Negative	Off	Apartment	02-705 LR	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1236	Negative	Off	Apartment	02-705 LR	Wall		Drywall	D	UL	Intact	0.0 mg/cm ²	Action Level
1237	Negative	Off	Apartment	02-705 LR	Ceiling		Concrete	D		Intact	0.0 mg/cm ²	Action Level
1238	Negative	Off	Apartment	02-705 LR	A/C Housing		Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
1239	Negative	Off	Apartment	02-705 LR	A/C Housing		Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
1240	Negative	Off	Apartment	02-705 LR	A/C Housing		Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
1241	Negative	Off	Apartment	02-705 LR	Radiator	Cover	Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
1242	Negative	Off	Apartment	02-705 LR	Window	Casing	Metal	D	Right	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1243	Negative	Off	Apartment	02-705 Kitchen	Window	Casing	Metal	B	Center	Intact	0.7 mg/cm ²	Action Level
1244	Negative	Off	Apartment	02-705 Kitchen	Radiator	Cover	Drywall	B	Center	Intact	0.3 mg/cm ²	Action Level
1245	Negative	Off	Apartment	02-705 Kitchen	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1246	Negative	Off	Apartment	02-705 Kitchen	Wall		Drywall	B	UL	Intact	0.3 mg/cm ²	Action Level
1247	Negative	Off	Apartment	02-705 Kitchen	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1248	Negative	Off	Apartment	02-705 Kitchen	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
1249	Negative	Off	Apartment	02-705 Kitchen	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1250	Negative	Off	Apartment	02-705 Kitchen	Cabinet		Wood	D	Center	Intact	0.1 mg/cm ²	Action Level
1251	Negative	Off	Apartment	02-609 Entry	Door	Panel	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
1252	Negative	Off	Apartment	02-609 Entry	Door	Casing	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
1253	Negative	Off	Apartment	02-609 Entry	Closet	Shelf Support	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
1254	Negative	Off	Apartment	02-609 Entry	Closet	Ceiling	Concrete	B	Left	Intact	0.1 mg/cm ²	Action Level
1255	Negative	Off	Apartment	02-609 Entry	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1256	Negative	Off	Apartment	02-609 Entry	Closet	Wall	Drywall	B	Left	Intact	0.1 mg/cm ²	Action Level
1257	Negative	Off	Apartment	02-609 Entry	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
1258	Negative	Off	Apartment	02-609 Entry	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1259	Negative	Off	Apartment	02-609 Entry	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
1260	Negative	Off	Apartment	02-609 Entry	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1261	Negative	Off	Apartment	02-609 Entry	Radiator	Cover	Metal	D	Right	Intact	0.0 mg/cm ²	Action Level
1262	Negative	Off	Apartment	02-609 Entry	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1263	Negative	Off	Apartment	02-609 Entry	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1264	Negative	Off	Apartment	02-609 Entry	Electric	Panel	Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
1265	Negative	Off	Apartment	02-609 Entry	Electric	Panel	Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
1266	Negative	Off	Apartment	02-609 Entry	Electric	Panel	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1267	Negative	Off	Apartment	02-609 Kitchen	Radiator	Cover	Metal	B	Center	Intact	0.7 mg/cm ²	Action Level
1268	Negative	Off	Apartment	02-609 Kitchen	Window	Casing	Metal	B	Center	Intact	0.6 mg/cm ²	Action Level
1269	Negative	Off	Apartment	02-609 Kitchen	Cabinet		Wood	C	Center	Intact	0.1 mg/cm ²	Action Level
1270	Negative	Off	Apartment	02-609 Kitchen	Ceiling		Concrete	C		Intact	0.1 mg/cm ²	Action Level
1271	Negative	Off	Apartment	02-609 Kitchen	Wall		Drywall	C	UC	Intact	0.4 mg/cm ²	Action Level
1272	Negative	Off	Apartment	02-609 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1273	Negative	Off	Apartment	02-609 Kitchen	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
1274	Negative	Off	Apartment	02-609 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1275	Negative	Off	Apartment	02-609 LR	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1276	Negative	Off	Apartment	20-609 LR	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1277	Negative	Off	Apartment	20-609 LR	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1278	Negative	Off	Apartment	20-609 LR	Wall		Drywall	D	UR	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1279	Negative	Off	Apartment	02-609 LR	Ceiling		Concrete	D		Intact	0.0 mg/cm ²	Action Level
1280	Negative	Off	Apartment	02-609 LR	Window	Casing	Metal	C	Left	Intact	0.9 mg/cm ²	Action Level
1281	Negative	Off	Apartment	02-609 LR	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1282	Negative	Off	Apartment	02-609 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1283	Negative	Off	Apartment	02-609 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1284	Negative	Off	Apartment	02-609 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1285	Positive	Off	Apartment	02-609 Bed 1	Window	Casing	Metal	C	Right	Intact	1.1 mg/cm ²	Action Level
1286	Negative	Off	Apartment	02-609 Bed 1	Radiator	Cover	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
1287	Negative	Off	Apartment	02-609 Bed 1	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
1288	Negative	Off	Apartment	02-609 Bed 1	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1289	Negative	Off	Apartment	02-609 Bed 1	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1290	Negative	Off	Apartment	02-609 Bed 1	Wall		Drywall	A	UR	Intact	0.2 mg/cm ²	Action Level
1291	Negative	Off	Apartment	02-609 Bed 1	Closet	Wall	Drywall	A	Right	Intact	0.2 mg/cm ²	Action Level
1292	Negative	Off	Apartment	02-609 Bed 1	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
1293	Negative	Off	Apartment	02-609 Bed 1	Ceiling		Concrete	A		Intact	0.3 mg/cm ²	Action Level
1294	Negative	Off	Apartment	02-609 Bed 1	Closet	Shelf Support	Wood	A	Right	Intact	0.3 mg/cm ²	Action Level
1295	Negative	Off	Apartment	02-609 Bed 1	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1296	Negative	Off	Apartment	02-609 Bed 1	Door	Jamb	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1297	Negative	Off	Apartment	02-609 Bed 2	Door	Casing	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
1298	Negative	Off	Apartment	02-609 Bed 2	Door	Panel	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
1299	Negative	Off	Apartment	02-609 Bed 2	Closet	Shelf Support Ceiling	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1300	Negative	Off	Apartment	02-609 Bed 2	Closet		Concrete	A	Left	Intact	0.0 mg/cm ²	Action Level
1301	Negative	Off	Apartment	02-609 Bed 2	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1302	Negative	Off	Apartment	02-609 Bed 2	Closet	Wall	Drywall	A	Left	Intact	0.1 mg/cm ²	Action Level
1303	Negative	Off	Apartment	02-609 Bed 2	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1304	Negative	Off	Apartment	02-609 Bed 2	Wall		Drywall	B	UC	Intact	0.3 mg/cm ²	Action Level
1305	Negative	Off	Apartment	02-609 Bed 2	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
1306	Negative	Off	Apartment	02-609 Bed 2	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1307	Negative	Off	Apartment	02-609 Bed 2	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1308	Negative	Off	Apartment	02-609 Bed 2	A/C Housing		Metal	c	Right	Intact	0.1 mg/cm ²	Action Level
1309	Negative	Off	Apartment	02-609 Bed 2	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1310	Negative	Off	Apartment	02-609 Bed 2	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1311	Positive	Off	Apartment	02-609 Bed 2	Window	Casing	Metal	C	Left	Intact	1.3 mg/cm ²	Action Level
1312	Positive	Off	Apartment	02-609 Bathroom	Window	Casing	Metal	A	Center	Intact	1.3 mg/cm ²	Action Level
1313	Negative	Off	Apartment	02-609 Bathroom	Cabinet		Metal	C	Center	Intact	0.1 mg/cm ²	Action Level
1314	Negative	Off	Apartment	02-609 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1315	Negative	Off	Apartment	02-609 Bathroom	Ceiling		Concrete	D		Intact	0.1 mg/cm ²	Action Level
1316	Negative	Off	Apartment	02-609 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
1317	Negative	Off	Apartment	02-609 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1318	Negative	Off	Apartment	02-609 Bathroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1319	Negative	Off	Apartment	02-609 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1320	Negative	Off	Apartment	02-609 Bathroom	Door	Panel	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level
1321	Negative	Off	Apartment	02-609 Bathroom	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1322	Negative	Off	Apartment	02-607 Kitchen	Door	Casing	Wood	D	Left	Intact	0.1 mg/cm ²	Action Level
1323	Negative	Off	Apartment	02-607 Kitchen	Door	Panel	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
1324	Negative	Off	Apartment	02-607 Kitchen	Door	Panel	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1325	Negative	Off	Apartment	02-607 Kitchen	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1326	Negative	Off	Apartment	02-607 Kitchen	Radiator	Cover	Metal	A	Right	Intact	0.4 mg/cm ²	Action Level
1327	Negative	Off	Apartment	02-607 Kitchen	Window	Casing	Metal	A	Right	Intact	0.9 mg/cm ²	Action Level
1328	Negative	Off	Apartment	02-607 Kitchen	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
1329	Negative	Off	Apartment	02-607 Kitchen	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1330	Negative	Off	Apartment	02-607 Kitchen	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1331	Negative	Off	Apartment	02-607 Kitchen	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1332	Negative	Off	Apartment	02-607 Kitchen	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1333	Negative	Off	Apartment	02-607 Kitchen	Closet	Wall	Drywall	D	Right	Intact	0.3 mg/cm ²	Action Level
1334	Negative	Off	Apartment	02-607 Kitchen	Closet	Ceiling	Drywall	D	Right	Intact	-0.3 mg/cm ²	Action Level
1335	Negative	Off	Apartment	02-607 Kitchen	Closet	Shelf Support	Wood	D	Right	Intact	-0.1 mg/cm ²	Action Level
1336	Negative	Off	Apartment	02-607 LR	Wall		Drywall	D	UC	Intact	0.3 mg/cm ²	Action Level
1337	Negative	Off	Apartment	02-607 LR	Wall		Drywall	C	UC	Intact	0.3 mg/cm ²	Action Level
1338	Negative	Off	Apartment	02-607 LR	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
1339	Negative	Off	Apartment	02-607 LR	Wall		Drywall	A	UL	Intact	0.2 mg/cm ²	Action Level
1340	Negative	Off	Apartment	02-607 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1341	Negative	Off	Apartment	02-607 LR	Window	Casing	Metal	C	Right	Intact	0.7 mg/cm ²	Action Level
1342	Negative	Off	Apartment	02-607 LR	Radiator	Cover	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
1343	Negative	Off	Apartment	02-607 LR	A/C Housing		Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
1344	Negative	Off	Apartment	02-607 LR	A/C Housing		Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
1345	Negative	Off	Apartment	02-607 LR	A/C Housing		Metal	C	Left	Intact	-0.1 mg/cm ²	Action Level
1346	Negative	Off	Apartment	02-607 Bedroom	Radiator	Cover	Metal	C	Left	Intact	0.0 mg/cm ²	Action Level
1347	Positive	Off	Apartment	02-607 Bedroom	Window	Casing	Metal	C	Left	Intact	1.0 mg/cm ²	Action Level
1348	Negative	Off	Apartment	02-607 Bedroom	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
1349	Negative	Off	Apartment	02-607 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1350	Negative	Off	Apartment	02-607 Bedroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1351	Negative	Off	Apartment	02-607 Bedroom	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1352	Negative	Off	Apartment	02-607 Bedroom	Closet	Wall	Drywall	A	Left	Intact	0.1 mg/cm ²	Action Level
1353	Negative	Off	Apartment	02-607 Bedroom	Closet	Ceiling	Concrete	A	Left	Intact	0.1 mg/cm ²	Action Level
1354	Negative	Off	Apartment	02-607 Bedroom	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
1355	Negative	Off	Apartment	02-607 Bedroom	Closet	Shelf Support Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
1356	Negative	Off	Apartment	02-607 Bedroom	Door		Wood	A	Right	Intact	-0.2 mg/cm ²	Action Level
1357	Negative	Off	Apartment	02-607 Bedroom	Door	Jamb	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
1358	Negative	Off	Apartment	02-607 Bathroom	Door	Casing	Drywall	B	Right	Intact	0.0 mg/cm ²	Action Level
1359	Negative	Off	Apartment	02-607 Bathroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1360	Negative	Off	Apartment	02-607 Bathroom	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
1361	Negative	Off	Apartment	02-607 Bathroom	Wall		Drywall	B	UR	Intact	-0.1 mg/cm ²	Action Level
1362	Negative	Off	Apartment	02-607 Bathroom	Wall		Drywall	C	LC	Intact	-0.1 mg/cm ²	Action Level
1363	Negative	Off	Apartment	02-607 Bathroom	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1364	Negative	Off	Apartment	02-607 Bathroom	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1365	Negative	Off	Apartment	02-607 Bathroom	Cabinet		Metal	D	Center	Intact	0.2 mg/cm ²	Action Level
1366	Negative	Off	Apartment	02-607 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.2 mg/cm ²	Action Level
1367	Negative	Off	Apartment	02-607 Bathroom	Window	Casing	Metal	A	Center	Intact	0.4 mg/cm ²	Action Level
1368	Negative	Off	Apartment	02-607 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1369	Negative	Off	Apartment	02-607 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1370	Negative	Off	Apartment	02-607 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1371	Negative	Off	Apartment	02-508 Kitchen	Radiator	Cover	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1372	Negative	Off	Apartment	02-508 Kitchen	Window	Casing	Metal	A	Left	Intact	0.8 mg/cm ²	Action Level
1373	Negative	Off	Apartment	02-508 Kitchen	Door	Panel	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
1374	Negative	Off	Apartment	02-508 Kitchen	Door	Casing	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
1375	Negative	Off	Apartment	02-508 Kitchen	Door	Jamb	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level
1376	Negative	Off	Apartment	02-508 Kitchen	Door	Panel	Wood	B	Right	Intact	0.2 mg/cm ²	Action Level
1377	Negative	Off	Apartment	02-508 Kitchen	Cabinet		Wood	C	Center	Intact	0.1 mg/cm ²	Action Level
1378	Negative	Off	Apartment	02-508 Kitchen	Closet	Shelf Support	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
1379	Negative	Off	Apartment	02-508 Kitchen	Closet	Ceiling	Concrete	B	Left	Intact	0.3 mg/cm ²	Action Level
1380	Negative	Off	Apartment	02-508 Kitchen	Ceiling		Concrete	B		Intact	0.3 mg/cm ²	Action Level
1381	Negative	Off	Apartment	02-508 Kitchen	Closet	Wall	Drywall	B	Left	Intact	0.1 mg/cm ²	Action Level
1382	Negative	Off	Apartment	02-508 Kitchen	Wall		Drywall	A	LL	Intact	0.2 mg/cm ²	Action Level
1383	Negative	Off	Apartment	02-508 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1384	Negative	Off	Apartment	02-508 Kitchen	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1385	Negative	Off	Apartment	02-508 Kitchen	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1386	Negative	Off	Apartment	02-508 Bathroom	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1387	Negative	Off	Apartment	02-508 Bathroom	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1388	Negative	Off	Apartment	02-508 Bathroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1389	Negative	Off	Apartment	02-508 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1390	Negative	Off	Apartment	02-508 Bathroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1391	Negative	Off	Apartment	02-508 Bathroom	Cabinet		Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1392	Negative	Off	Apartment	02-508 Bathroom	Radiator	Cover	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1393	Negative	Off	Apartment	02-508 Bathroom	Window	Casing	Metal	A	Center	Intact	0.8 mg/cm ²	Action Level
1394	Negative	Off	Apartment	02-508 Bathroom	Door	Panel	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
1395	Negative	Off	Apartment	02-508 Bathroom	Door	Jamb	Wood	D	Left	Intact	-0.1 mg/cm ²	Action Level
1396	Negative	Off	Apartment	02-508 Bedroom	Door	Casing	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
1397	Negative	Off	Apartment	02-508 Bedroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1398	Negative	Off	Apartment	02-508 Bedroom	Closet	Shelf Support	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
1399	Negative	Off	Apartment	02-508 Bedroom	Closet	Ceiling	Concrete	A	Right	Intact	-0.2 mg/cm ²	Action Level
1400	Negative	Off	Apartment	02-508 Bedroom	Ceiling		Concrete	A		Intact	-0.2 mg/cm ²	Action Level
1401	Negative	Off	Apartment	02-508 Bedroom	Closet	Wall	Drywall	A	Right	Intact	0.0 mg/cm ²	Action Level
1402	Negative	Off	Apartment	02-508 Bedroom	Wall		Drywall	A	UC	Intact	-0.1 mg/cm ²	Action Level
1403	Negative	Off	Apartment	02-508 Bedroom	Wall		Drywall	B	UC	Intact	-0.1 mg/cm ²	Action Level
1404	Negative	Off	Apartment	02-508 Bedroom	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1405	Negative	Off	Apartment	02-508 Bedroom	Wall		Drywall	D	UC	Intact	-0.1 mg/cm ²	Action Level
1406	Positive	Off	Apartment	02-508 Bedroom	Window	Casing	Metal	C	Right	Intact	1.0 mg/cm ²	Action Level
1407	Positive	Off	Apartment	02-508 LR	Window	Casing	Metal	C	Right	Intact	1.0 mg/cm ²	Action Level
1408	Negative	Off	Apartment	02-508 LR	Radiator	Cover	Metal	C	Left	Intact	-0.2 mg/cm ²	Action Level
1409	Negative	Off	Apartment	02-508 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1410	Negative	Off	Apartment	02-508 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
1411	Negative	Off	Apartment	02-508 LR	A/C Housing		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
1412	Negative	Off	Apartment	02-508 LR	Ceiling		Concrete	C		Intact	0.0 mg/cm ²	Action Level
1413	Negative	Off	Apartment	02-508 LR	Wall		Drywall	C	LR	Intact	0.2 mg/cm ²	Action Level
1414	Negative	Off	Apartment	02-508 LR	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1415	Negative	Off	Apartment	02-508 LR	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1416	Negative	Off	Apartment	02-508 LR	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
1417	Negative	Off	Apartment	02-506 Kitchen	Wall		Drywall	A	UL	Intact	0.2 mg/cm ²	Action Level
1418	Negative	Off	Apartment	02-506 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1419	Negative	Off	Apartment	02-506 Kitchen	Wall		Drywall	C	UC	Intact	0.3 mg/cm ²	Action Level
1420	Negative	Off	Apartment	02-506 Kitchen	Wall		Drywall	B	UL	Intact	0.2 mg/cm ²	Action Level
1421	Negative	Off	Apartment	02-506 Kitchen	Closet	Wall	Drywall	B	Left	Intact	0.2 mg/cm ²	Action Level
1422	Negative	Off	Apartment	02-506 Kitchen	Closet	Ceiling	Concrete	B	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1423	Negative	Off	Apartment	02-506 Kitchen	Ceiling		Concrete	B		Intact	0.3 mg/cm ²	Action Level
1424	Negative	Off	Apartment	02-506 Kitchen	Closet	Shelf Support Panel	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
1425	Negative	Off	Apartment	02-506 Kitchen	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1426	Negative	Off	Apartment	02-506 Kitchen	Door	Jamb	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1427	Negative	Off	Apartment	02-506 Kitchen	Cabinet		Metal	C	Right	Intact	0.0 mg/cm ²	Action Level
1428	Negative	Off	Apartment	02-506 Kitchen	Radiator	Cover	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1429	Negative	Off	Apartment	02-506 Kitchen	Window	Casing	Metal	A	Left	Intact	0.2 mg/cm ²	Action Level
1430	Positive	Off	Apartment	02-506 Bathroom	Window	Casing	Metal	A	Left	Intact	1.0 mg/cm ²	Action Level
1431	Negative	Off	Apartment	02-506 Bathroom	Cabinet		Metal	B	Center	Intact	0.0 mg/cm ²	Action Level
1432	Negative	Off	Apartment	02-506 Bathroom	Radiator	Cover	Metal	B	Center	Intact	-0.1 mg/cm ²	Action Level
1433	Negative	Off	Apartment	02-506 Bathroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1434	Negative	Off	Apartment	02-506 Bathroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1435	Negative	Off	Apartment	02-506 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1436	Negative	Off	Apartment	02-506 Bathroom	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
1437	Negative	Off	Apartment	02-506 Bathroom	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1438	Negative	Off	Apartment	02-506 Bathroom	Door	Panel	Wood	D	Left	Intact	0.2 mg/cm ²	Action Level
1439	Negative	Off	Apartment	02-506 Bathroom	Door	Jamb	Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
1440	Negative	Off	Apartment	02-506 Bedroom	Door	Casing	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1441	Negative	Off	Apartment	02-506 Bedroom	Door	Panel	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1442	Negative	Off	Apartment	02-506 Bedroom	Closet	Shelf Support	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
1443	Negative	Off	Apartment	02-506 Bedroom	Closet	Ceiling	Concrete	A	Right	Intact	0.0 mg/cm ²	Action Level
1444	Negative	Off	Apartment	02-506 Bedroom	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
1445	Negative	Off	Apartment	02-506 Bedroom	Closet	Wall	Drywall	A	Right	Intact	0.2 mg/cm ²	Action Level
1446	Negative	Off	Apartment	02-506 Bedroom	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
1447	Negative	Off	Apartment	02-506 Bedroom	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1448	Negative	Off	Apartment	02-506 Bedroom	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1449	Negative	Off	Apartment	02-506 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1450	Negative	Off	Apartment	02-506 Bedroom	Radiator	Cover	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1451	Positive	Off	Apartment	02-506 Bedroom	Window	Casing	Metal	C	Right	Intact	2.5 mg/cm ²	Action Level
1452	Positive	Off	Apartment	02-506 LR	Window	Casing	Metal	C	Left	Intact	2.5 mg/cm ²	Action Level
1453	Negative	Off	Apartment	02-506 LR	Radiator	Cover	Metal	C	Left	Intact	0.3 mg/cm ²	Action Level
1454	Negative	Off	Apartment	02-506 LR	A/C Housing		Metal	C	Right	Intact	0.3 mg/cm ²	Action Level
1455	Negative	Off	Apartment	02-506 LR	A/C Housing		Metal	C	Right	Intact	0.3 mg/cm ²	Action Level
1456	Negative	Off	Apartment	02-506 LR	Wall		Drywall	C	UR	Intact	-0.1 mg/cm ²	Action Level
1457	Negative	Off	Apartment	02-506 LR	Wall		Drywall	D	UL	Intact	-0.1 mg/cm ²	Action Level
1458	Negative	Off	Apartment	02-506 LR	Wall		Drywall	B	UC	Intact	-0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1459	Negative	Off	Apartment	02-506 LR	Wall		Drywall	A	UR	Intact	0.0 mg/cm ²	Action Level
1460	Negative	Off	Apartment	02-506 LR	Ceiling		Concrete	A		Intact	-0.1 mg/cm ²	Action Level
1461	Negative	Off	Apartment	02-503 Kitchen	Ceiling		Concrete	C		Intact	0.3 mg/cm ²	Action Level
1462	Negative	Off	Apartment	02-503 Kitchen	Closet	Ceiling	Concrete	C	Left	Intact	0.3 mg/cm ²	Action Level
1463	Negative	Off	Apartment	02-503 Kitchen	Closet	Wall	Drywall	C	Left	Intact	0.1 mg/cm ²	Action Level
1464	Negative	Off	Apartment	02-503 Kitchen	Wall		Drywall	C	UL	Intact	-0.1 mg/cm ²	Action Level
1465	Negative	Off	Apartment	02-503 Kitchen	Wall		Drywall	B	UC	Intact	-0.1 mg/cm ²	Action Level
1466	Negative	Off	Apartment	02-503 Kitchen	Wall		Drywall	D	UL	Intact	-0.1 mg/cm ²	Action Level
1467	Negative	Off	Apartment	02-503 Kitchen	Wall		Drywall	A	LC	Intact	-0.1 mg/cm ²	Action Level
1468	Negative	Off	Apartment	02-503 Kitchen	Radiator	Cover	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1469	Negative	Off	Apartment	02-503 Kitchen	Window	Casing	Metal	B	Center	Intact	0.4 mg/cm ²	Action Level
1470	Negative	Off	Apartment	02-503 Kitchen	Door	Panel	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
1471	Negative	Off	Apartment	02-503 Kitchen	Door	Casing	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
1472	Negative	Off	Apartment	02-503 Kitchen	Door	Jamb	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
1473	Negative	Off	Apartment	02-503 Kitchen	Door	Panel	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
1474	Negative	Off	Apartment	02-503 Bathroom	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
1475	Negative	Off	Apartment	02-503 Bathroom	Door	Casing	Wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1476	Negative	Off	Apartment	02-503 Bathroom	Radiator	Cover	Metal	C	Center	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1477	Negative	Off	Apartment	02-503 Bathroom	Cabinet		Metal	C	Center	Intact	0.0 mg/cm ²	Action Level
1478	Negative	Off	Apartment	02-503 Bathroom	Window	Casing	Metal	B	Center	Intact	0.9 mg/cm ²	Action Level
1479	Negative	Off	Apartment	02-503 Bathroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1480	Negative	Off	Apartment	02-503 Bathroom	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1481	Negative	Off	Apartment	02-503 Bathroom	Wall		Drywall	C	UR	Intact	0.2 mg/cm ²	Action Level
1482	Negative	Off	Apartment	02-503 Bathroom	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1483	Negative	Off	Apartment	02-503 Bedroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
1484	Negative	Off	Apartment	02-503 Bedroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1485	Negative	Off	Apartment	02-503 Bedroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1486	Negative	Off	Apartment	02-503 Bedroom	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
1487	Negative	Off	Apartment	02-503 Bedroom	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
1488	Negative	Off	Apartment	02-503 Bedroom	Closet	Ceiling	Concrete	B	Right	Intact	0.0 mg/cm ²	Action Level
1489	Negative	Off	Apartment	02-503 Bedroom	Ceiling		Concrete	B		Intact	0.1 mg/cm ²	Action Level
1490	Negative	Off	Apartment	02-503 Bedroom	Closet	Shelf Support	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level
1491	Negative	Off	Apartment	02-503 Bedroom	Door	Panel	Wood	B	Left	Intact	0.1 mg/cm ²	Action Level
1492	Negative	Off	Apartment	02-503 Bedroom	Door	Jamb	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
1493	Positive	Off	Apartment	02-503 Bedroom	Window	Casing	Metal	D	Right	Intact	1.3 mg/cm ²	Action Level
1494	Negative	Off	Apartment	02-503 Bedroom	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1495	Negative	Off	Apartment	02-503 LR	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1496	Positive	Off	Apartment	02-503 LR	Window	Casing	Metal	D	Left	Intact	1.4 mg/cm ²	Action Level
1497	Negative	Off	Apartment	02-503 LR	A/C Housing		Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
1498	Negative	Off	Apartment	02-503 LR	A/C Housing		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
1499	Negative	Off	Apartment	02-503 LR	Wall		Drywall	D	LR	Intact	0.1 mg/cm ²	Action Level
1500	Negative	Off	Apartment	02-503 LR	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1501	Negative	Off	Apartment	02-503 LR	Wall		Drywall	B	LL	Intact	0.1 mg/cm ²	Action Level
1502	Negative	Off	Apartment	02-503 LR	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1503	Negative	Off	Apartment	02-503 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1504	Negative	Off	Apartment	02-407 Kitchen	Ceiling		Concrete	D		Intact	0.2 mg/cm ²	Action Level
1505	Negative	Off	Apartment	02-407 Kitchen	Closet	Ceiling	Concrete	D	Right	Intact	0.0 mg/cm ²	Action Level
1506	Negative	Off	Apartment	02-407 Kitchen	Closet	Wall	Drywall	D	Right	Intact	0.1 mg/cm ²	Action Level
1507	Negative	Off	Apartment	02-407 Kitchen	Wall		Drywall	D	UR	Intact	0.3 mg/cm ²	Action Level
1508	Negative	Off	Apartment	02-407 Kitchen	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level
1509	Negative	Off	Apartment	02-407 Kitchen	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1510	Negative	Off	Apartment	02-407 Kitchen	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
1511	Negative	Off	Apartment	02-407 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
1512	Negative	Off	Apartment	02-407 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1513	Negative	Off	Apartment	02-407 Kitchen	Electric	Panel	Metal	D	Left	Intact	0.3 mg/cm ²	Action Level
1514	Negative	Off	Apartment	02-407 Kitchen	Door	Panel	Metal	A	Left	Intact	0.0 mg/cm ²	Action Level
1515	Negative	Off	Apartment	02-407 Kitchen	Door	Casing	Metal	A	Left	Intact	0.1 mg/cm ²	Action Level
1516	Negative	Off	Apartment	02-407 Kitchen	Radiator	Cover	Metal	A	Right	Intact	0.1 mg/cm ²	Action Level
1517	Positive	Off	Apartment	02-407 Kitchen	Window	Casing	Metal	A	Right	Intact	1.5 mg/cm ²	Action Level
1518	Negative	Off	Apartment	02-407 Kitchen	Cabinet		Wood	C	Left	Intact	0.1 mg/cm ²	Action Level
1519	Negative	Off	Apartment	02-407 LR	Wall		Drywall	A	LR	Intact	0.2 mg/cm ²	Action Level
1520	Negative	Off	Apartment	02-407 LR	Wall		Drywall	B	LL	Intact	0.2 mg/cm ²	Action Level
1521	Negative	Off	Apartment	02-407 LR	Wall		Drywall	D	LC	Intact	0.2 mg/cm ²	Action Level
1522	Negative	Off	Apartment	02-407 LR	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
1523	Negative	Off	Apartment	02-407 LR	Ceiling		Concrete	C		Intact	0.3 mg/cm ²	Action Level
1524	Negative	Off	Apartment	02-407 LR	A/C Housing		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1525	Negative	Off	Apartment	02-407 LR	A/C Housing		Metal	C	Left	Intact	0.2 mg/cm ²	Action Level
1526	Negative	Off	Apartment	02-407 LR	A/C Housing		Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1527	Negative	Off	Apartment	02-407 LR	Radiator	Cover	Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
1528	NULL	Off	Apartment	02-407 LR	Window	Casing	Metal	C	Right	Intact	0.9 mg/cm ²	Action Level
1529	Negative	Off	Apartment	02-407 Bedroom	Window	Casing	Metal	C	Left	Intact	0.9 mg/cm ²	Action Level
1530	Negative	Off	Apartment	02-407 Bedroom	Radiator	Cover	Metal	C	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1531	Negative	Off	Apartment	02-407 Bedroom	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
1532	Negative	Off	Apartment	02-407 Bedroom	Wall		Drywall	D	UC	Intact	0.3 mg/cm ²	Action Level
1533	Negative	Off	Apartment	02-407 Bedroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1534	Negative	Off	Apartment	02-407 Bedroom	Wall		Drywall	A	UR	Intact	0.3 mg/cm ²	Action Level
1535	Negative	Off	Apartment	02-407 Bedroom	Closet	Wall	Drywall	A	Left	Intact	0.0 mg/cm ²	Action Level
1536	Negative	Off	Apartment	02-407 Bedroom	Closet	Ceiling	Concrete	A	Left	Intact	0.1 mg/cm ²	Action Level
1537	Negative	Off	Apartment	02-407 Bedroom	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1538	Negative	Off	Apartment	02-407 Bedroom	Closet	Shelf Support	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1539	Negative	Off	Apartment	02-407 Bedroom	Door	Panel	Wood	A	Right	Intact	-0.2 mg/cm ²	Action Level
1540	Negative	Off	Apartment	02-407 Bedroom	Door	Jamb	Wood	A	Right	Intact	0.0 mg/cm ²	Action Level
1541	Negative	Off	Apartment	02-407 Bathroom	Door	Panel	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1542	Negative	Off	Apartment	02-407 Bathroom	Door	Casing	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1543	Negative	Off	Apartment	02-407 Bathroom	Radiator	Cover	Metal	D	Center	Intact	0.0 mg/cm ²	Action Level
1544	Positive	Off	Apartment	02-407 Bathroom	Window	Casing	Metal	A	Center	Intact	1.0 mg/cm ²	Action Level
1545	Negative	Off	Apartment	02-407 Bathroom	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1546	Negative	Off	Apartment	02-407 Bathroom	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
1547	Negative	Off	Apartment	02-407 Bathroom	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
1548	Negative	Off	Apartment	02-407 Bathroom	Wall		Drywall	C	UC	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1549	Negative	Off	Apartment	02-407 Bathroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1550		Off	Calibration								0.9 mg/cm ²	Action Level
1551		Off	Calibration								0.9 mg/cm ²	Action Level
1552		Off	Calibration								0.9 mg/cm ²	Action Level
1553		Off	Calibration								0.1 mg/cm ²	Action Level
1554		Off	Calibration								0.0 mg/cm ²	Action Level
1555		Off	Calibration								0.0 mg/cm ²	Action Level
1556	Negative	Off	Apartment	02-206 Kitchen	Wall		Drywall	A	UC	Intact	0.3 mg/cm ²	Action Level
1557	Negative	Off	Apartment	02-206 Kitchen	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
1558	Negative	Off	Apartment	02-206 Kitchen	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1559	Negative	Off	Apartment	02-206 Kitchen	Wall		Drywall	B	UR	Intact	0.0 mg/cm ²	Action Level
1560	Negative	Off	Apartment	02-206 Kitchen	Closet	Wall	Drywall	B	Left	Intact	-0.2 mg/cm ²	Action Level
1561	Negative	Off	Apartment	02-206 Kitchen	Closet	Ceiling	Concrete	B	Left	Intact	-0.1 mg/cm ²	Action Level
1562	Negative	Off	Apartment	02-206 Kitchen	Ceiling		Concrete	B		Intact	-0.2 mg/cm ²	Action Level
1563	Negative	Off	Apartment	02-206 Kitchen	Closet	Shelf Support	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
1564	Negative	Off	Apartment	02-206 Kitchen	Cabinet		Wood	C	Center	Intact	0.1 mg/cm ²	Action Level
1565	Negative	Off	Apartment	02-206 Kitchen	Radiator	Cover	Metal		Left	Intact	0.1 mg/cm ²	Action Level
1566	Positive	Off	Apartment	02-206 Kitchen	Window	Casing	Metal	A	Left	Intact	1.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1567	Negative	Off	Apartment	02-206 Kitchen	Door	Panel	Metal	A	Right	Intact	0.2 mg/cm ²	Action Level
1568	Negative	Off	Apartment	02-206 Kitchen	Door	Casing	Metal	A	Right	Intact	0.2 mg/cm ²	Action Level
1569	Negative	Off	Apartment	02-206 Bathroom	Cabinet		Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1570	Negative	Off	Apartment	02-206 Bathroom	Radiator	Cover	Metal	B	Center	Intact	0.1 mg/cm ²	Action Level
1571	Positive	Off	Apartment	02-206 Bathroom	Window	Casing	Metal	A	Center	Intact	1.2 mg/cm ²	Action Level
1572	Negative	Off	Apartment	02-206 Bathroom	Door	Panel	Wood	D	Left	Intact	-0.1 mg/cm ²	Action Level
1573	Negative	Off	Apartment	02-206 Bathroom	Door	Casing	Wood	D	Left	Intact	-0.1 mg/cm ²	Action Level
1574	Negative	Off	Apartment	02-206 Bathroom	Wall		Drywall	D	UL	Intact	0.0 mg/cm ²	Action Level
1575	Negative	Off	Apartment	02-206 Bathroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1576	Negative	Off	Apartment	02-206 Bathroom	Wall		Drywall	B	UL	Intact	0.2 mg/cm ²	Action Level
1577	Negative	Off	Apartment	02-206 Bathroom	Wall		Drywall	A	UR	Intact	0.2 mg/cm ²	Action Level
1578	Negative	Off	Apartment	02-206 Bathroom	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1579	Negative	Off	Apartment	02-206 Bedroom	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1580	Negative	Off	Apartment	02-206 Bedroom	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1581	Negative	Off	Apartment	02-206 Bedroom	Closet	Ceiling	Concrete	A	Right	Intact	0.1 mg/cm ²	Action Level
1582	Negative	Off	Apartment	02-206 Bedroom	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
1583	Negative	Off	Apartment	02-206 Bedroom	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
1584	Negative	Off	Apartment	02-206 Bedroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1585	Negative	Off	Apartment	02-206 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1586	Negative	Off	Apartment	02-206 Bedroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1587	Negative	Off	Apartment	02-206 Bedroom	Closet	Shelf Support Panel	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
1588	Negative	Off	Apartment	02-206 Bedroom	Door		Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1589	Negative	Off	Apartment	02-206 Bedroom	Door	Jamb	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
1590	Negative	Off	Apartment	02-206 Bedroom	Radiator	Cover	Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1591	Negative	Off	Apartment	02-206 Bedroom	Window	Casing	Metal	C	Right	Intact	0.8 mg/cm ²	Action Level
1592	Positive	Off	Apartment	02-206 LR	Window	Casing	Metal	C	Left	Intact	1.2 mg/cm ²	Action Level
1593	Negative	Off	Apartment	02-206 LR	Radiator	Cover	Metal	C	Left	Intact	0.1 mg/cm ²	Action Level
1594	Negative	Off	Apartment	02-206 LR	A/C Housing		Metal	C	Right	Intact	0.1 mg/cm ²	Action Level
1595	Negative	Off	Apartment	02-206 LR	A/C Housing		Metal	C	Right	Intact	0.2 mg/cm ²	Action Level
1596	Negative	Off	Apartment	02-206 LR	Ceiling		Concrete	C		Intact	0.2 mg/cm ²	Action Level
1597	Negative	Off	Apartment	02-206 LR	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
1598	Negative	Off	Apartment	02-206 LR	Wall		Drywall	D	LC	Intact	0.1 mg/cm ²	Action Level
1599	Negative	Off	Apartment	02-206 LR	Wall		Drywall	B	UC	Intact	0.1 mg/cm ²	Action Level
1600	Negative	Off	Apartment	02-206 LR	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1601	Negative	Off	Apartment	02-204 Kitchen	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1602	Negative	Off	Apartment	02-204 Kitchen	Wall		Drywall	C	UC	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1603	Negative	Off	Apartment	02-204 Kitchen	Wall		Drywall	B	UC	Intact	0.2 mg/cm ²	Action Level
1604	Negative	Off	Apartment	02-204 Kitchen	Wall		Drywall	A	UC	Intact	0.0 mg/cm ²	Action Level
1605	Negative	Off	Apartment	02-204 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.2 mg/cm ²	Action Level
1606	Negative	Off	Apartment	02-204 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.3 mg/cm ²	Action Level
1607	Negative	Off	Apartment	02-204 Kitchen	Ceiling		Concrete	A		Intact	0.2 mg/cm ²	Action Level
1608	Negative	Off	Apartment	02-204 Kitchen	Closet	Shelf Support	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
1609	Negative	Off	Apartment	02-204 Kitchen	Cabinet		Wood	D	Left	Intact	0.1 mg/cm ²	Action Level
1610	Negative	Off	Apartment	02-204 Kitchen	Door	Panel	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1611	Negative	Off	Apartment	02-204 Kitchen	Door	Jamb	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1612	Negative	Off	Apartment	02-204 Kitchen	Door	Casing	Metal	B	Left	Intact	0.1 mg/cm ²	Action Level
1613	Negative	Off	Apartment	02-204 Kitchen	Door	Panel	Metal	B	Left	Intact	0.0 mg/cm ²	Action Level
1614	Negative	Off	Apartment	02-204 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.0 mg/cm ²	Action Level
1615	Negative	Off	Apartment	02-204 Kitchen	Window	Casing	Metal	B	Right	Intact	0.7 mg/cm ²	Action Level
1616	Positive	Off	Apartment	02-204 LR	Window	Casing	Metal	D	Right	Intact	1.0 mg/cm ²	Action Level
1617	Negative	Off	Apartment	02-204 LR	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
1618	Negative	Off	Apartment	02-204 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1619	Negative	Off	Apartment	02-204 LR	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1620	Negative	Off	Apartment	02-204 LR	A/C Housing		Metal	D	Left	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1621	Negative	Off	Apartment	02-204 LR	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1622	Negative	Off	Apartment	02-204 LR	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1623	Negative	Off	Apartment	02-204 LR	Wall		Drywall	B	UC	Intact	0.0 mg/cm ²	Action Level
1624	Negative	Off	Apartment	02-204 LR	Wall		Drywall	A	UR	Intact	0.1 mg/cm ²	Action Level
1625	Negative	Off	Apartment	02-204 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1626	Negative	Off	Apartment	02-204 Bedroom	Ceiling		Concrete	B		Intact	0.2 mg/cm ²	Action Level
1627	Negative	Off	Apartment	02-204 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.2 mg/cm ²	Action Level
1628	Negative	Off	Apartment	02-204 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.1 mg/cm ²	Action Level
1629	Negative	Off	Apartment	02-204 Bedroom	Closet	Shelf Support Panel	Wood	B	Left	Intact	0.2 mg/cm ²	Action Level
1630	Negative	Off	Apartment	02-204 Bedroom	Door		Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1631	Negative	Off	Apartment	02-204 Bedroom	Door	Jamb	Wood	B	Right	Intact	-0.2 mg/cm ²	Action Level
1632	Negative	Off	Apartment	02-204 Bedroom	Radiator	Cover	Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1633	Positive	Off	Apartment	02-204 Bedroom	Window	Casing	Metal	D	Left	Intact	1.3 mg/cm ²	Action Level
1634	Negative	Off	Apartment	02-204 Bedroom	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1635	Negative	Off	Apartment	02-204 Bedroom	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1636	Negative	Off	Apartment	02-204 Bedroom	Wall		Drywall	B	UR	Intact	0.2 mg/cm ²	Action Level
1637	Negative	Off	Apartment	02-204 Bedroom	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1638	Negative	Off	Apartment	02-204 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1639	Negative	Off	Apartment	02-204 Bathroom	Wall		Drywall	B	UR	Intact	0.2 mg/cm ²	Action Level
1640	Negative	Off	Apartment	02-204 Bathroom	Wall		Drywall	C	UL	Intact	0.2 mg/cm ²	Action Level
1641	Negative	Off	Apartment	02-204 Bathroom	Wall		Drywall	D	UL	Intact	0.2 mg/cm ²	Action Level
1642	Negative	Off	Apartment	02-204 Bathroom	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1643	Negative	Off	Apartment	02-204 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1644	Negative	Off	Apartment	02-204 Bathroom	Cabinet		Metal	A	Center	Intact	0.1 mg/cm ²	Action Level
1645	Negative	Off	Apartment	02-204 Bathroom	Window	Casing	Metal	B	Center	Intact	0.4 mg/cm ²	Action Level
1646	Negative	Off	Apartment	02-204 Bathroom	Door	Panel	Wood	C	Right	Intact	-0.2 mg/cm ²	Action Level
1647	Negative	Off	Apartment	02-204 Bathroom	Door	Jamb	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
1648	Negative	Off	Apartment	02-104 Kitchen	Door	Casing	wood	A	Left	Intact	-0.1 mg/cm ²	Action Level
1649	Negative	Off	Apartment	02-104 Kitchen	Door	Panel	Wood	A	Left	Intact	0.0 mg/cm ²	Action Level
1650	Negative	Off	Apartment	02-104 Kitchen	Cabinet		Wood	D	Left	Intact	0.0 mg/cm ²	Action Level
1651	Negative	Off	Apartment	02-104 Kitchen	Door	Panel	Metal	B	Left	Intact	-0.1 mg/cm ²	Action Level
1652	Negative	Off	Apartment	02-104 Kitchen	Door	Casing	Metal	B	Left	Intact	0.2 mg/cm ²	Action Level
1653	Negative	Off	Apartment	02-104 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1654	Positive	Off	Apartment	02-104 Kitchen	Window	Casing	Metal	B	Right	Intact	1.7 mg/cm ²	Action Level
1655	Negative	Off	Apartment	02-104 Kitchen	Wall		Drywall	B	UR	Intact	0.2 mg/cm ²	Action Level
1656	Negative	Off	Apartment	02-104 Kitchen	Wall		Drywall	C	UC	Intact	0.2 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1657	Negative	Off	Apartment	02-104 Kitchen	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1658	Negative	Off	Apartment	02-104 Kitchen	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1659	Negative	Off	Apartment	02-104 Kitchen	Closet	Wall	Drywall	A	Right	Intact	0.1 mg/cm ²	Action Level
1660	Negative	Off	Apartment	02-104 Kitchen	Closet	Ceiling	Concrete	A	Right	Intact	0.2 mg/cm ²	Action Level
1661	Negative	Off	Apartment	02-104 Kitchen	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
1662	Negative	Off	Apartment	02-104 Kitchen	Closet	Shelf Support Cover	Wood	A	Right	Intact	-0.1 mg/cm ²	Action Level
1663	Negative	Off	Apartment	02-104 LR	Radiator		Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
1664	Negative	Off	Apartment	02-104 LR	Window	Casing	Metal	D	Right	Intact	0.6 mg/cm ²	Action Level
1665	Negative	Off	Apartment	02-104 LR	Ceiling		Concrete	D		Intact	-0.1 mg/cm ²	Action Level
1666	Negative	Off	Apartment	02-104 LR	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1667	Negative	Off	Apartment	02-104 LR	Wall		Drywall	C	UR	Intact	0.0 mg/cm ²	Action Level
1668	Negative	Off	Apartment	02-104 LR	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1669	Negative	Off	Apartment	02-104 LR	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1670	Negative	Off	Apartment	02-104 Bedroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1671	Negative	Off	Apartment	02-104 Bedroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1672	Negative	Off	Apartment	02-104 Bedroom	Wall		Drywall	C	UL	Intact	0.3 mg/cm ²	Action Level
1673	Negative	Off	Apartment	02-104 Bedroom	Wall		Drywall	D	UC	Intact	0.2 mg/cm ²	Action Level
1674	Negative	Off	Apartment	02-104 Bedroom	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1675	Negative	Off	Apartment	02-104 Bedroom	Closet	Ceiling	Concrete	B	Left	Intact	0.0 mg/cm ²	Action Level
1676	Negative	Off	Apartment	02-104 Bedroom	Ceiling		Concrete	B		Intact	-0.1 mg/cm ²	Action Level
1677	Negative	Off	Apartment	02-104 Bedroom	Closet	Shelf Support Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
1678	Negative	Off	Apartment	02-104 Bedroom	Door		Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1679	Negative	Off	Apartment	02-104 Bedroom	Door	Jamb	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1680	Positive	Off	Apartment	02-104 Bedroom	Window	Casing	Metal	D	Left	Intact	1.6 mg/cm ²	Action Level
1681	Positive	Off	Apartment	02-104 Bathroom	Window	Casing	Metal	B	Center	Intact	1.6 mg/cm ²	Action Level
1682	Negative	Off	Apartment	02-104 Bathroom	Cabinet		Metal	A	Center	Intact	0.0 mg/cm ²	Action Level
1683	Negative	Off	Apartment	02-104 Bathroom	Radiator	Cover	Metal	A	Center	Intact	0.2 mg/cm ²	Action Level
1684	Negative	Off	Apartment	02-104 Bathroom	Ceiling		Concrete	A		Intact	0.0 mg/cm ²	Action Level
1685	Negative	Off	Apartment	02-104 Bathroom	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1686	Negative	Off	Apartment	02-104 Bathroom	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1687	Negative	Off	Apartment	02-104 Bathroom	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1688	Negative	Off	Apartment	02-104 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1689	Negative	Off	Apartment	02-104 Bathroom	Door	Panel	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
1690	Negative	Off	Apartment	02-104 Bathroom	Door	Jamb	Wood	C	Right	Intact	0.0 mg/cm ²	Action Level
1691	Negative	Off	Apartment	02-105 Entry	Door	Casing	Wood	C	Right	Intact	0.1 mg/cm ²	Action Level
1692	Negative	Off	Apartment	02-105 Entry	Door	Panel	Wood	C	Right	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1693	Negative	Off	Apartment	02-105 Entry	Door	Panel	Metal	B	Right	Intact	-0.2 mg/cm ²	Action Level
1694	Negative	Off	Apartment	02-105 Entry	Door	Jamb	Metal	B	Right	Intact	-0.1 mg/cm ²	Action Level
1695	Negative	Off	Apartment	02-105 Entry	Radiator	Cover	Metal	C	Left	Intact	-0.1 mg/cm ²	Action Level
1696	Negative	Off	Apartment	02-105 Entry	Closet	Shelf Support	Wood	A	Right	Intact	0.1 mg/cm ²	Action Level
1697	Negative	Off	Apartment	02-105 Entry	Closet	Ceiling	Concrete	A	Right	Intact	0.0 mg/cm ²	Action Level
1698	Negative	Off	Apartment	02-105 Entry	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1699	Negative	Off	Apartment	02-105 Entry	Closet	Wall	Drywall	A	Right	Intact	0.0 mg/cm ²	Action Level
1700	Negative	Off	Apartment	02-105 Entry	Wall		Drywall	A	LR	Intact	0.0 mg/cm ²	Action Level
1701	Negative	Off	Apartment	02-105 Entry	Wall		Drywall	B	LC	Intact	0.1 mg/cm ²	Action Level
1702	Negative	Off	Apartment	02-105 Entry	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1703	Negative	Off	Apartment	02-105 Entry	Wall		Drywall	D	UR	Intact	0.1 mg/cm ²	Action Level
1704	Negative	Off	Apartment	02-105 Bathroom	Wall		Drywall	D	UC	Intact	0.0 mg/cm ²	Action Level
1705	Negative	Off	Apartment	02-105 Bathroom	Wall		Drywall	A	UC	Intact	0.2 mg/cm ²	Action Level
1706	Negative	Off	Apartment	02-105 Bathroom	Wall		Drywall	B	UL	Intact	0.1 mg/cm ²	Action Level
1707	Negative	Off	Apartment	02-105 Bathroom	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1708	Negative	Off	Apartment	02-105 Bathroom	Door	Panel	Wood	A	Left	Intact	0.2 mg/cm ²	Action Level
1709	Negative	Off	Apartment	02-105 Bathroom	Door	Jamb	Wood	A	Left	Intact	0.1 mg/cm ²	Action Level
1710	Negative	Off	Apartment	02-105 Bathroom	Cabinet		Metal	C	Center	Intact	-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1711	Negative	Off	Apartment	02-105 Bathroom	Radiator	Cover	Metal	C	Center	Intact	-0.1 mg/cm ²	Action Level
1712	Positive	Off	Apartment	02-105 Bathroom	Window	Casing	Metal	B	Center	Intact	1.0 mg/cm ²	Action Level
1713	Negative	Off	Apartment	02-105 Bed 1	Window	Casing	Metal	D	Right	Intact	0.9 mg/cm ²	Action Level
1714	Negative	Off	Apartment	02-105 Bed 1	Radiator	Cover	Metal	D	Right	Intact	0.1 mg/cm ²	Action Level
1715	Negative	Off	Apartment	02-105 Bed 1	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1716	Negative	Off	Apartment	02-105 Bed 1	A/C Housing		Metal	D	Left	Intact	0.1 mg/cm ²	Action Level
1717	Negative	Off	Apartment	02-105 Bed 1	Wall		Drywall	D	UL	Intact	0.1 mg/cm ²	Action Level
1718	Negative	Off	Apartment	02-105 Bed 1	Wall		Drywall	C	UC	Intact	0.1 mg/cm ²	Action Level
1719	Negative	Off	Apartment	02-105 Bed 1	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1720	Negative	Off	Apartment	02-105 Bed 1	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1721	Negative	Off	Apartment	02-105 Bed 1	Closet	Wall	Drywall	B	Right	Intact	0.1 mg/cm ²	Action Level
1722	Negative	Off	Apartment	02-105 Bed 1	Closet	Ceiling	Concrete	B	Right	Intact	0.2 mg/cm ²	Action Level
1723	Negative	Off	Apartment	02-105 Bed 1	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
1724	Negative	Off	Apartment	02-105 Bed 1	Closet	Shelf Support	Wood	B	Right	Intact	0.0 mg/cm ²	Action Level
1725	Negative	Off	Apartment	02-105 Bed 1	Door	Panel	Wood	B	Left	Intact	-0.1 mg/cm ²	Action Level
1726	Negative	Off	Apartment	02-105 Bed 1	Door	Jamb	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
1727	Negative	Off	Apartment	02-105 Bed 2	Door	Casing	Wood	B	Right	Intact	-0.1 mg/cm ²	Action Level
1728	Negative	Off	Apartment	02-105 Bed 2	Door	Panel	Wood	B	Right	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1729	Negative	Off	Apartment	02-105 Bed 2	Closet	Shelf Support	Wood	B	Left	Intact	0.0 mg/cm ²	Action Level
1730	Negative	Off	Apartment	02-105 Bed 2	Closet	Ceiling	Concrete	B	Left	Intact	-0.1 mg/cm ²	Action Level
1731	Negative	Off	Apartment	02-105 Bed 2	Ceiling		Concrete	B		Intact	0.0 mg/cm ²	Action Level
1732	Negative	Off	Apartment	02-105 Bed 2	Closet	Wall	Drywall	B	Left	Intact	0.0 mg/cm ²	Action Level
1733	Negative	Off	Apartment	02-105 Bed 2	Wall		Drywall	B	UL	Intact	0.0 mg/cm ²	Action Level
1734	Negative	Off	Apartment	02-105 Bed 2	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1735	Negative	Off	Apartment	02-105 Bed 2	Wall		Drywall	C	UL	Intact	0.1 mg/cm ²	Action Level
1736	Negative	Off	Apartment	02-105 Bed 2	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1737	Negative	Off	Apartment	02-105 Bed 2	Radiator	Cover	Metal	D	Left	Intact	0.2 mg/cm ²	Action Level
1738	Positive	Off	Apartment	02-105 Bed 2	Window	Casing	Metal	D	Left	Intact	1.0 mg/cm ²	Action Level
1739	Positive	Off	Apartment	02-105 LR	Window	Casing	Metal	D	Right	Intact	1.1 mg/cm ²	Action Level
1740	Negative	Off	Apartment	02-105 LR	Radiator	Cover	Metal	D	Right	Intact	0.2 mg/cm ²	Action Level
1741	Negative	Off	Apartment	02-105 LR	A/C Housing		Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1742	Negative	Off	Apartment	02-105 LR	A/C Housing		Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1743	Negative	Off	Apartment	02-105 LR	A/C Housing		Metal	D	Left	Intact	0.0 mg/cm ²	Action Level
1744	Negative	Off	Apartment	02-105 Entry	Electric	Panel	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
1745	Negative	Off	Apartment	02-105 Entry	Electric	Panel	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level
1746	Negative	Off	Apartment	02-105 Entry	Electric	Panel	Metal	D	Center	Intact	0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
 Action Level: 1.0 mg/cm²
 Total Readings: 1765
 Unit Started: 12/08/2020 10:16:40
 Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
 1314 and 1342 West 15th Street
 Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure	-->Member	Substrate	Wall	Location	Condition	Lead (mg/cm ²)	Mode
1747	Negative	Off	Apartment	02-105 LR	Wall		Drywall	D	UC	Intact	0.1 mg/cm ²	Action Level
1748	Negative	Off	Apartment	02-105 LR	Wall		Drywall	C	UR	Intact	0.1 mg/cm ²	Action Level
1749	Negative	Off	Apartment	02-105 LR	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1750	Negative	Off	Apartment	02-105 LR	Wall		Drywall	A	UC	Intact	0.1 mg/cm ²	Action Level
1751	Negative	Off	Apartment	02-105 LR	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1752	Negative	Off	Apartment	02-105 Kitchen	Ceiling		Concrete	A		Intact	0.1 mg/cm ²	Action Level
1753	Negative	Off	Apartment	02-105 Kitchen	Wall		Drywall	A	UL	Intact	0.1 mg/cm ²	Action Level
1754	Negative	Off	Apartment	02-105 Kitchen	Wall		Drywall	B	UR	Intact	0.1 mg/cm ²	Action Level
1755	Negative	Off	Apartment	02-105 Kitchen	Wall		Drywall	C	UR	Intact	0.3 mg/cm ²	Action Level
1756	Negative	Off	Apartment	02-105 Kitchen	Wall		Drywall	D	UL	Intact	0.3 mg/cm ²	Action Level
1757	Negative	Off	Apartment	02-105 Kitchen	Radiator	Cover	Metal	B	Right	Intact	0.1 mg/cm ²	Action Level
1758	Positive	Off	Apartment	02-105 Kitchen	Window	Casing	Metal	B	Right	Intact	1.2 mg/cm ²	Action Level
1759	Negative	Off	Apartment	02-105 Kitchen	Cabinet		Wood	D	Center	Intact	0.0 mg/cm ²	Action Level
1760		Off	Calibration								1.0 mg/cm ²	Action Level
1761		Off	Calibration								1.0 mg/cm ²	Action Level
1762		Off	Calibration								1.0 mg/cm ²	Action Level
1763		Off	Calibration								0.0 mg/cm ²	Action Level
1764		Off	Calibration								-0.1 mg/cm ²	Action Level

Detailed Lead Paint Inspection Report

Inspection Date: 12/8/2020 - 12/9/2020
Action Level: 1.0 mg/cm²
Total Readings: 1765
Unit Started: 12/08/2020 10:16:40
Unit Ended: 12/09/2020 15:59:24

Inspection Site: Loomis Courts
1314 and 1342 West 15th Street
Chicago, IL 60608

Read #	Result	RTA Present	Room	-->RoomChoice	Structure -->Member	Substrate Wall Location	Condition	Lead (mg/cm ²)	Mode
1765		Off	Calibration					-0.1 mg/cm ²	Action Level

----- END OF READINGS -----

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix C: Lead-Based Paint Risk Assessor/Inspector License

124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608

IDPH **LEAD RISK ASSESSOR LICENSE**

LEAD ID	ISSUED	EXPIRES
001743	12/19/2019	1/31/2021

James W Sundberg
21W310 Audubon Rd.
Lombard, IL 60148



ILLINOIS LEAD PROGRAM
Environmental Health

Alteration of this license shall result in legal action
RISK ASSESSOR CERTIFICATE EXPIRES
4/24/2022

This license issued under authority of the State
of Illinois -Department of Public Health

This license is valid only when accompanied by
a valid training course certificate

If found return to 525 W. Jefferson St Springfield, IL 62761

➤

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix D: XRF Performance Characteristic Sheets

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

HEURESIS PCS December 2015

Performance Characteristic Sheet

EFFECTIVE DATE: December 1, 2015

MANUFACTURER AND MODEL:

Make: **Heuresis**
Models: **Model Pb200i**
Source: **⁵⁷Co, 5 mCi (nominal – new source)**

FIELD OPERATION GUIDANCE

OPERATING PARAMETERS:

Action Level mode

XRF CALIBRATION CHECK LIMITS:

0.8 to 1.2 mg/cm ² (inclusive)

SUBSTRATE CORRECTION:

Not applicable

INCONCLUSIVE RANGE OR THRESHOLD:

ACTION LEVEL MODE READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm²)
Results not corrected for substrate bias on any substrate	Brick	1.0
	Concrete	1.0
	Drywall	1.0
	Metal	1.0
	Plaster	1.0
	Wood	1.0

HEURESIS PCS December 2015

BACKGROUND INFORMATION

EVALUATION DATA SOURCE AND DATE:

This sheet is supplemental information to be used in conjunction with Chapter 7 of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing* ("HUD Guidelines"). Performance parameters shown on this sheet are calculated using test results on building components in the HUD archive. Testing was conducted on 146 test samples in November 2015, with two separate instruments running software version 2.1-2 in Action Level test mode. The actual source strength of each instrument on the day of testing was approximately 2.0 mCi; source ages were approximately one year.

OPERATING PARAMETERS

Performance parameters shown in this sheet are applicable only when properly operating the instrument using the manufacturer's instructions and procedures described in Chapter 7 of the HUD Guidelines.

XRF CALIBRATION CHECK:

The calibration of the XRF instrument should be checked using the paint film nearest 1.0 mg/cm² in the NIST Standard Reference Material (SRM) used (e.g., for NIST SRM 2579, use the 1.02 mg/cm² film).

If the average (rounded to 1 decimal place) of three readings is outside the acceptable calibration check range, follow the manufacturer's instructions to bring the instrument into control before XRF testing proceeds.

SUBSTRATE CORRECTION VALUE COMPUTATION:

Chapter 7 of the HUD Guidelines provides guidance on correcting XRF results for substrate bias. Supplemental guidance for using the paint film nearest 1.0 mg/cm² for substrate correction is provided:

XRF results are corrected for substrate bias by subtracting from each XRF result a correction value determined separately in each house for single-family housing or in each development for multifamily housing, for each substrate. The correction value is an average of XRF readings taken over the NIST SRM paint film nearest to 1.0 mg/cm² at test locations that have been scraped bare of their paint covering. Compute the correction values as follows:

Using the same XRF instrument, take three readings on a bare substrate area covered with the NIST SRM paint film nearest 1 mg/cm². Repeat this procedure by taking three more readings on a second bare substrate area of the same substrate covered with the NIST SRM.

Compute the correction value for each substrate type where XRF readings indicate substrate correction is needed by computing the average of all six readings as shown below.

For each substrate type (the 1.02 mg/cm² NIST SRM is shown in this example; use the actual lead loading of the NIST SRM used for substrate correction):

$$\text{Correction value} = (1\text{st} + 2\text{nd} + 3\text{rd} + 4\text{th} + 5\text{th} + 6\text{th Reading})/6 - 1.02 \text{ mg/cm}^2$$

Repeat this procedure for each substrate requiring substrate correction in the house or housing development.

EVALUATING THE QUALITY OF XRF TESTING:

Randomly select ten testing combinations for retesting from each house or from two randomly selected units in multifamily housing.

Conduct XRF re-testing at the ten testing combinations selected for retesting.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

HEURESIS PCS December 2015

Determine if the XRF testing in the units or house passed or failed the test by applying the steps below. Compute the Retest Tolerance Limit by the following steps:

Determine XRF results for the original and retest XRF readings. Do not correct the original or retest results for substrate bias. In single-family and multi-family housing, a result is defined as a single reading. Therefore, there will be ten original and ten retest XRF results for each house or for the two selected units.

Calculate the average of the original XRF result and the retest XRF result for each testing combination.

Square the average for each testing combination.

Add the ten squared averages together. Call this quantity C.

Multiply the number C by 0.0072. Call this quantity D.

Add the number 0.032 to D. Call this quantity E.

Take the square root of E. Call this quantity F.

Multiply F by 1.645. The result is the Retest Tolerance Limit.

Compute the average of all ten original XRF readings.

Compute the average of all ten re-test XRF readings.

Find the absolute difference of the two averages.

If the difference is less than the Retest Tolerance Limit, the inspection has passed the retest. If the difference of the overall averages equals or exceeds the Retest Tolerance Limit, this procedure should be repeated with ten new testing combinations. If the difference of the overall averages is equal to or greater than the Retest Tolerance Limit a second time, then the inspection should be considered deficient.

Use of this procedure is estimated to produce a spurious result approximately 1% of the time. That is, results of this procedure will call for further examination when no examination is warranted in approximately 1 out of 100 dwelling units tested.

TESTING TIMES:

In the Action Level paint test mode, the instrument takes the longest time to complete readings close to the Federal standard of 1.0 mg/cm². The table below shows the mean and standard deviation of actual reading times by reading level for paint samples during the November 2015 archive testing. The tested instruments reported readings to one decimal place. No significant differences in reading times by substrate were observed. These times apply only to instruments with the same source strength as those tested (2.0 mCi). Instruments with stronger sources will have shorter reading times and those with weaker sources, longer reading times, than those in the table.

Mean and Standard Deviation of Reading Times in Action Level Mode by Reading Level		
Reading (mg/cm ²)	Mean Reading Time (seconds)	Standard Deviation (seconds)
< 0.7	3.48	0.47
0.7	7.29	1.92
0.8	13.95	1.78
0.9 – 1.2	15.25	0.66
1.3 – 1.4	6.08	2.50
≥ 1.5	3.32	0.05

124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608

HEURESIS PCS December 2015

CLASSIFICATION OF RESULTS:

XRF results are classified as **positive** if they are **greater than or equal** to the stated threshold for the instrument (1.0 mg/cm²), and *negative* if they are *less than* the threshold.

DOCUMENTATION:

A report titled *Methodology for XRF Performance Characteristic Sheets* (EPA 747-R-95-008) provides an explanation of the statistical methodology used to construct the data in the sheets, and provides empirical results from using the recommended inconclusive ranges or thresholds for specific XRF instruments. The report may be downloaded at <http://www2.epa.gov/lead/methodology-xrf-performance-characteristic-sheets-epa-747-r-95-008-september-1997>.

This XRF Performance Characteristic Sheet (PCS) was developed by QuanTech, Inc., under a contract with the XRF manufacturer.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix E: Property Layout

(no drawings)

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**

Appendix F: Photograph Documentation of Components with LBP

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**



Exterior Building. Metal Hallway Fences with Intact Lead Based Paint (LBP).



Exterior Building. Metal Lintels (over Doors and Windows) with Intact LBP.



Exterior Building. Metal Hallway Fences and Lintels (over Doors and Windows) with Intact LBP.



Interior Common Areas (Only Stairways). Brick Walls and Concrete Support Columns and Beams with Intact LBP.

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**



**Interior Common Areas (Only Stairways).
Brick Walls and Concrete Support Columns and
Beams with LBP. Deteriorated Walls only found
in 1314 Building, NE Stairway, 6th Floor.**



**Interior Apartments. Metal Window Sills and
Casings (Original to Building) with Intact LBP.**



**Interior Apartments. Metal Window Sills and
Casings (Original to Building) with mostly Intact
LBP (Some metal casings are deteriorated and
need stabilized). Drywall and Plaster around
windows tested negative for LBP.**



**Exterior Building. Metal Hallway Fences and
Lintels (over Doors and Windows) with Intact
LBP.**

**124 Unit Apartment Building Complex
Loomis Courts Apartments
1314 and 1342 West 15th Street
Chicago, IL 60608**



**Interior Common Areas (Elevator Vestibules).
Metal Window Sills and Casings (Original to
Building) with Intact LBP.**

**Replacement Windows are not
painted but they were installed into
original Metal Window Trim (Sills and
Casings) that were original to
buildings. The original metal window
components is what tested positive
for LBP.**